## COMMISSION OF SILICON VALLEY CLEAN WATER JOINT POWERS AUTHORITY REGULAR MEETING – Thursday, February 9, 2017 4:00 p.m.

Place: Pelican Conference Room Silicon Valley Clean Water 1400 Radio Road, 2<sup>nd</sup> Floor Redwood City, California

### **COMMISSIONERS**

MAYOR JOHN SEYBERT, REDWOOD CITY – CHAIR COUNCIL MEMBER WARREN LIEBERMAN, PhD., BELMONT – VICE CHAIR BOARD MEMBER GEORGE S. OTTE, PE, WEST BAY SANITARY DISTRICT – MEMBER MAYOR ROBERT GRASSILLI, SAN CARLOS – SECRETARY

MANAGER: DANIEL T. CHILD ATTORNEY FOR THE AUTHORITY: CHRISTINE C. FITZGERALD CONTROLLER/TREASURER: KIMBRA MCCARTHY

#### **AMERICANS WITH DISABILITIES ACT**

In compliance with the Americans with Disabilities Act, if you need special assistance to participate in this meeting, please contact SVCW (650) 591-7121. Notification in advance of the meeting will enable the Authority to make reasonable arrangements to ensure accessibility to this meeting.

#### <u>AGENDA</u>

- 1. CALL TO ORDER
- 2. ROLL CALL
- 3. PLEDGE OF ALLEGIANCE

#### 4. PUBLIC COMMENT

Any member of the public may address and ask questions of the Chair under this item relating to any matter within the Commission's jurisdiction that does not appear as a separate item on the Agenda. An opportunity will be provided for members of the public to address the Chair and ask questions about any item that is listed on the agenda at the time the Commission considers the item and before action is taken. If you address the Commission on a non-agenda item, please be aware that the Ralph M. Brown Act (Gov. C. § 54950 et seq.) prohibits the Commission from acting on or discussing such matters at this meeting. Any such item may be referred to staff for a decision with regard to placing it on a future agenda for discussion, action or a report.

- 5. SAFETY MOMENT and REPORTS
  - A. Safety Moment
  - B. Manager's Report (verbal)
  - C. Financial Reports
    - 1. Investment Report
    - 2. Finance Status Update
  - D. Engineering Projects Status Update
  - E. Commission Requested Staff-Level Action Items
  - F. Conveyance System Program Update
- 6. MATTERS OF COMMISSION MEMBER'S INTEREST
- 7. CONSIDERATION OF MOTION APPROVING CONSENT CALENDAR
- 8. BUSINESS ITEMS
  - A. CONSIDERATION OF RESOLUTION APPROVING CONTRACT DOCUMENTS FOR FLO-BEAST INSTALLATION PROJECT (CIP #9229)

Proposed Action: Move adoption of RESOLUTION APPROVING CONTRACT DOCUMENTS FOR FLO-BEAST INSTALLATION CONTRACT - CIP #9229; AUTHORIZING EXECUTION OF AGREEMENT AND AUTHORIZING MANAGER TO APPROVE CHANGE ORDERS UP TO TEN PERCENT OF THE CONTRACT VALUE FOR SAID PROJECT – (\$96,432) – D.W. Nicholson Corporation

- 9. CLOSED SESSION
  - A. <u>CONFERENCE WITH LEGAL COUNSEL EXISTING LITIGATION</u>

Pursuant to Government Code §54956.9(d)(1)

Case Name: In the Matter of the Calculation of Final Compensation of David A. Hall, Respondent, and Silicon Valley Clean Water, Respondent (Board of Administration, California Public Employees' Retirement System, Agency Case No. 2015-1236 OAH NO. 2016030664)

B. <u>CONFERENCE WITH LEGAL COUNSEL – ANTICIPATED LITIGATION</u>

Significant exposure to litigation pursuant to paragraph (2) of subdivision (d) of Government Code §54956.9 (12 potential cases): CalPERS' Determination to Exclude Performance Pay from Retirement Benefit Calculations and Opportunity to Appeal Determination

- 10. RECONVENE IN OPEN SESSION Announce action taken in Closed Session, if any.
- 11. ADJOURN

- December 31, 2016 Report / Discussion January 2017
- Presentation / Discussion

### NOTICE TO PUBLIC

All matters listed under CONSENT CALENDAR are considered to be routine. There may be discussion on items on the CONSENT CALENDAR. All items will be enacted by one motion with a roll call vote unless members of the Commission, staff, or public request specific items be removed from the CONSENT CALENDAR for separate action.

- 7. A. APPROVAL OF MINUTES January 12, 2017
  - B. CONSIDERATION OF MOTION APPROVING CLAIMS AND CHECKS DATED DECEMBER 31, 2016 AND NECESSARY PAYMENTS THROUGH JANUARY 31, 2017
  - C. CONSIDERATION OF MOTION ACCEPTING THE SOLIDS PROCESS AUTOMATION FINAL PROJECT (CIP #8007, 8018, 8021) AND FILE NOTICE OF COMPLETION

Proposed Action: Move approval to ACCEPT SOLIDS PROCESS AUTOMATION PROJECT (CIP #8007, 8018, 8021) AND AUTHORIZE FILING OF NOTICE OF COMPLETION – Monterey Mechanical Company

D. CONSIDERATION OF RESOLUTIONS AND MOTIONS APPROVING MASTER SERVICES AGREEMENTS AND TASK ORDERS FOR FINANCIAL ADMINISTRATIVE ASSISTANCE ASSOCIATED WITH THE WATER INFRASTRUCTURE FINANCE AND INNOVATION ACT (WIFIA) LOAN PROGRAM AND OTHER GOVERNMENTAL FINANCE OPPORTUNITIES

Proposed Actions:

- i. Move approval of TASK ORDER SCOPE NO. 2017-01 AND BUDGET FOR WIFIA ADMINISTRATIVE SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$106,600 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – Fieldman, Rolapp & Associates
- ii. Move adoption of RESOLUTION APPROVING MASTER SERVICES AGREEMENT FOR PUBLIC RELATIONS CONSULTING SERVICES Ginger Bryant & Associates
- iii. Move approval of TASK ORDER SCOPE NO. 2017-01 AND BUDGET FOR WIFIA PUBLIC RELATIONS SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$144,200 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – Ginger Bryant & Associates

- iv. Move adoption of RESOLUTION APPROVING MASTER SERVICES AGREEMENT for INTERGOVERNMENTAL CONSULTING SERVICES Ferguson Group, LLC
- v. Move approval of TASK ORDER NO. 2017-01 SCOPE AND BUDGET FOR WIFIA INTERGOVERNMENTAL CONSULTING SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$126,000 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS –Ferguson Group, LLC

## "AGENDA ITEM 5A FEBRUARY 9, 2017



SAFETY MOMENT

Downed utility lines, power company blackouts, heavy snow falls or summer storms can all lead to power outages. Many people turn to a portable generator for a temporary solution without knowing the risks.

- ))) Generators should be used in well ventilated locations outside away from all doors, windows and vent openings.
- >>> Never use a generator in an attached garage, even with the door open.
- Place generators so that exhaust fumes can't enter the home through windows, doors or other openings in the building.
- Make sure to install carbon monoxide (CO) alarms in your home. Follow manufacturer's instructions for correct placement and mounting height.
- Turn off generators and let them cool down before refueling. Never refuel a generator while it is hot.
  - Store fuel for the generator in a container that is intended for the purpose and is correctly labeled as such. Store the containers outside of living areas.

# Just Remember..

When plugging in appliances, make sure they are plugged directly into the generator or a heavy duty outdoor-rated extension cord. The cords should be checked for cuts, tears and that the plug has all three prongs, especially a grounding pin.

If you must connect the generator to the house wiring to power appliances, have a qualified electrician install a properly rated transfer switch in accordance with the National Electrical Code® (NEC) and all applicable state and local electrical codes.

## FACT

CO deaths associated with generators have spiked in recent years as generator sales have risen.

Your Source for SAFETY Information
PA NFPA Public Education Division • 1 Batterymarch Park, Quincy, MA 02169

Net Funds	Available		58,759,013	58,782,904	59,912,951	55,474,057	55,485,956	48,708,841	50,842,827	48,501,813	46,311,156	45,780,338	39,141,172														
ГОС	\$s Drawn	÷ -	ı	ı	ı	(3,300,000)	(6,100,000)	(6,100,000)	(6,100,000)	(2,600,000)	(2,600,000)	(4,100,000)	(4,100,000)														<b>d</b> )
SRF	Receivable	6,268,110 \$	7,015,554	8,578,480	9,290,696	10,373,832	12,718,732	7,887,988	6,268,445	5,459,150	6,122,481	6,907,198	3,273,153				Bond	5 Proceeds		Stage 2 Reserves	CIP Reserves	Operating	Keserves Working		5 LOC \$s Drawn	+	Receivable
Cash &	Securities	53,364,685 \$	51,743,459	50,204,424	50,622,254	48,400,225	48,867,224	46,920,852	50,674,382	45,642,663	42,788,675	42,973,140	39,968,019				į	\$7.5	\$5.0		6./\$		\$15.1	0	\$3.5 \$1.0	\$(4.1)	
Bond	Proceeds	20,872,185 \$	19,960,391	19,100,794	18,090,084	17,490,349	15,556,753	15,581,048	15,581,048	11,697,458	10,996,789	8,869,835	7,482,629			j								0			
Debt	Reserves	5,006,246 \$	5,006,250	5,006,255	5,006,261	5,011,011	5,048,450	5,045,284	5,043,019	5,043,472	5,047,978	4,987,108	5,008,678	(\$ Millions)	1	Ì				i							
Stage 2	Reserves	5,981,490 \$	5,987,128	6,258,533	6,259,131	7,198,049	7,206,807	7,957,152	7,720,053	7,968,644	7,892,718	7,891,008	7,903,493	\$)						1			0				
CIP	Reserves	12,993,788 \$	13,002,861	13,625,771	13,834,514	14,042,310	14,271,457	14,427,004	14,201,050	14,372,231	14,231,655	14,918,669	15,108,271														
Operating	Reserves	3,383,128 \$	3,387,784	3,434,561	3,448,995	3,466,331	3,484,877	3,488,704	3,236,330	3,428,118	3,397,218	3,464,203	3,467,177		j					į							
Working	Capital	5,127,848 \$	4,399,045	2,778,510	3,983,269	1,192,175	3,298,880	421,661	4,892,883	3,132,741	1,222,317	2,842,317	997,770	\$60.0 J	\$50.0 -		\$40.0		\$30.0		\$20.0 -		\$10.0 -		ۍ. ارب	•	
Period	Ending	Jan-16 \$	Feb-16	Mar-16	Apr-16	May-16	Jun-16	Jul-16	Aug-16	Sep-16	Oct-16	Nov-16	Dec-16														50

SVCW Trailing 12 Months Cash Balance - December 31, 2016

## SVCW INVESTMENT LISTING

## **AGENDA ITEM 5C1 FEBRUARY 9, 2017**

Dec-16

Nov-16

Oct-16

Aug-16 Sep-16

Jul-16

Feb-16 Mar-16 Apr-16 May-16 Jun-16

Jan-16

\$(10.0)

## SILICON VALLEY GLEAN WATER

JOINT POWERS AUTHORITY ~ A PUBLIC ENTITY



1400 RADIO ROAD REDWOOD CITY, CALIFORNIA 94065 650.591.7121 | FAX: 650.591.7122 WWW.SVCW.ORG

CITY OF SAN CARLOS | CITY OF REDWOOD CITY | CITY OF BELMONT | WEST BAY SANITARY DISTRICT

#### SILICON VALLEY CLEAN WATER INVESTMENT LISTING December 31, 2016

Broker/Dealer_	Composite		Coupon	Yield to				Estimated Annual \$ Yield
Investment Name	Credit	Maturity	Rate	Maturity	Par Value	Market Value	Cost	Earnings
Annual OPS and CAP Budget Reserve				,			0001	Lunnigs
CLARK CNTY NEV FOR ISSUES DTD GO BDS	AA	7/1/2017	4.300%	1.07	50,000	50,841	51,407	546
FEDERAL HOME LN MTG CORP PARTN CTF	N.A.	3/1/2018	5.000%	1.20	65,852	66,660	68,219	800
FEDERAL HOME LN MTG CORP PARTN GOLD	N.A.	2/1/2020	5.000%	1.39	77,789	81,010	82.067	1,126
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/13/2019	2.375%	1.53	60,000	61,485	62,204	942
FEDERAL HOME LOAN BKS CONS BDS	AA+	2/18/2021	1.375%	1.86	30,000	29,450	30,468	548
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	2/10/2017	2.875%	1.00	50,000	50,133	50,553	499
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/8/2017	5.400%	0.98	50,000	51,043	51,131	498
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	1/17/2017	4.875%	0.53	50,000	50,089	51,061	263
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	1/5/2017	4.250%	4.16	50,000	50,014	50,908	2,082
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/8/2017	3.125%	1.04	85,000	86,763	86,877	906
FEDERAL HOME LOAN BKS CONS BDS	AA+	6/9/2017	1.125%	0.74	100,000	100,144	100,213	740
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	9/17/2018	1.950%	1.26	100,000	101,257	101,916	1,274
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	4/9/2018	0.699%	0.78	50,000	50,002	49,959	391
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/9/2016	4.625%	1.11	125,000	130,106	131,704	1,438
FEDERAL HOME LOAN BKS CONS BDS	AA+	3/9/2018	4.375%	1.46	50,000	53,605	53,782	782
FEDERAL HOME LOAN BKS CONS BDS	AA+	7/1/2019	4.500%	1.50	100,000	107,953	109,819	1,616
FEDERAL HOME LN MTG CORP	AA+	9/13/2019	1.000%	0.77	50,000	50,066	50,070	388
FEDERAL NATL MTG ASSN	AA+	7/25/2017	1.500%	1.62	30,000	29,875	30,440	485
FEDERAL NATL MTG ASSN	AA+	6/22/2020	1.500%	1.78	30,000	29,641	30,355	526
FEDERAL NATL MTG ASSN	AA+	11/30/2020	1.375%	1.88	30,000	29,433	30,362	552
FEDERAL NATL MTG ASSN	AA+	2/26/2021	1.625%	1.21	60,000	60,464	60,913	733
FEDERAL NATL MTG ASSN GTD REMIC	NR	11/27/2018	2.171%	1.72	150,000	150,611	151,969	2,592
FEDERAL NATL MTG ASSN	AA+	9/25/2019	1.750%	1.77	100,000	99,174	100,935	1,756
FEDERAL HOME LN MTG CORP MULTICLASS	NR	9/25/2020	1.869%	1.71	130,000	130,155	129,817	2,227
FEDERAL HOME LN MTG CORP	AA+	11/25/2019	1.250%	0.69	95,000	95,208	95,305	657
FEDERAL HOME LN MTG CORP	AA+	5/12/2017	1.750%	1.35	30,000	30,283	30,630	409
FEDERAL HOME LN MTG CORP	AA+	5/30/2019	1.250%	1.45	30,000	29,825	30,232	432
FEDERAL HOME LN MTG CORP MULTICLASS	N.A.	10/2/2019	4.000%	1.43	42,709	43,681	43,990	624
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	4/15/2020	5.500%	1.73	59,273	61,583	62,681	1,065
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	12/1/2019	5.500%	1.49	42,063	42,746	43,588	637
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	3/1/2020	5.000%	1.35	34,052	35,530	35,946	480
GNMA II PASSTHRU CTF POOL #003421	N.A.	4/1/2020	4.500%	1.54	25,430	25,966	26,642	400
GENERAL ELEC CAP CORP MTN	A+	8/20/2018	1.151%	1.15	75,000	75,137	74,771	863
GEORGIA MUN ELEC AUTH PWR REV SUB	A+	8/7/2018	3.202%	-	25,000	25,000	25,233	-
IOWA FIN AUTH REV ST REVOLVING FD	AAA	1/1/2017	3.280%	1.46	50,000	51,581	51,700	753
MCDONALDS CORP MED TERM NT FR	BBB+	8/1/2018	5.800%	1.33	25,000	25,854	26,162	345
NORTH ST PAUL MAPLEWOOD MINN I GO	AA	10/15/2017	5.000%	1.34	50,000	51,958	52,372	697
OREGON ST GO ENERGY BDS 2006 B AMT	AA+	2/1/2018	4.000%	3.67	100,000	100,187	100,000	3,676
SAN LUIS ARIZ PLEDGED EXCISE T REV	N.A.	10/1/2017	2.000%	1.24	50,000	50,051	50,000	622
SMALL BUSINESS ADMIN GTD LN POOL	N.A.	7/1/2017	3.325%	2.03	44,380	44,793	46,051	908
U S BANCORP MTNS BK ENT FR	AA-	2/25/2019	1.950%	1.61	50,000	50,255	50,101	810
UNIVERSITY CALIF REVS FOR PREV GEN	AA	12/15/2016	1.796%	1.66	50,000	50,142	49,568	832
WELLS FARGO & CO NEW SR GLBL NT	A+	11/15/2018	5.625%	1.59	50,000	51,838	51,986	824
WYETH NT	AA-	7/1/2019	5.450%	1.02	50,000	50,516	51,088	517
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	12/11/2017	1.010%	1.49	80,000	79,307	80,000	1,182
MONTGOMERY CNTY MD CTFS PARTN COPS	N.A.	4/1/2017	1.200%	1.80	100,000	98,410	100,058	1,775
RICHMOND VA GO PUB IMPT BDS C	AA	10/26/2018	2.599%	2.31	100,000	101,772	105,711	2,353
PORT MORROW ORE TRANSMISSION F REV	AA	11/1/2019	2.737%	2.41	100,000	102,130	105,266	2,458
WACO TEX INDPT SCH DIST REF BDS	N.A.	7/15/2021	4.000%	1.85	110,000	117,038	119,714	2,170
FEDERAL HOME LN MTG CORP	AA+	9/1/2021	1.500%	1.78	80,000	79,871	80,000	1,421
CASH & EQUIVALENTS	-	-	-	0.45	-	196,547	196,547	884
Annual OPS and CAP Budget Reserve Total						\$ 3,467,177	\$ 3,502,486	\$ 51,504

## SILICON VALLEY CLEAN WATER

JOINT POWERS AUTHORITY ~ A PUBLIC ENTITY



1400 RADIO ROAD REDWOOD CITY, CALIFORNIA 94065 650.591.7121 | FAX: 650.591.7122 www.svcw.org

CITY OF SAN CARLOS | CITY OF REDWOOD CITY | CITY OF BELMONT | WEST BAY SANITARY DISTRICT

Broker/Dealer	Composite		Coupon	Yield to				Estimated Annual \$ Yield
Investment Name	Credit	Maturity	Rate	Maturity	Par Value	Market Value	Cost	Earnings
Capital Improvement Program Reserve APPLE INC SR FLT NT	1.00			112.002000				
BERGEN CNTY N J TAXABLE GO BDS 2008	AA+	12/1/2016	1.137%	1.29	100,000	99,875	99,821	1,283
BERKSHIRE HATHAWAY FIN CORP GTD SR	N.A. AA	2/7/2020	6.000% 5.400%	1.49	100,000	108,535	108,630	1,614
CALIFORNIA ST GO BDS TAXABLE	AA AA-	11/1/2019 5/15/2018	5.400% 6.200%	1.45 2.15	100,000	105,244	105,817	1,523
CHEVRON CORPORATION SR NT	AA-	10/1/2019	4.950%	1.71	100,000 100,000	111,090 106,857	112,015	2,386
CISCO SYS INC SR GLBL NT	A+	3/3/2019	4.450%	2.04	125,000	133,968	107,275 135,775	1,823
CLARK CNTY NEV FOR ISSUES DTD GO BDS	AA	1/15/2020	4.300%	1.07	25,000	25,421	25,703	2,734 273
COLGATE PALMOLIVE CO MTNS FR	AA-	7/1/2017	1.500%	1.45	100,000	100,218	100,322	1,449
COOKEVILLE TENN GO INDUSTRIAL AND	N.A.	11/1/2018	3.000%	1.40	100,000	100,709	100,904	1,407
EXXON MOBIL CORP SR FLT NT	AA+	6/1/2017	1.113%	1.20	100,000	100,337	99,935	1,201
FEDERAL HOME LN MTG CORP PARTN CTF	N.A.	3/15/2019	5.000%	1.20	22,140	22,412	22,936	269
FEDERAL HOME LN MTG CORP PARTN GOLD	N.A.	3/1/2018	5.000%	1.67	73,821	75,630	77,836	1,263
FEDERAL HOME LOAN BKS CONS BDS	AA+	2/1/2019	2.375%	1.53	340,000	348,415	346,474	5,338
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/13/2019	1.375%	1.86	100,000	98,165	101,561	1,828
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	2/18/2021	2.500%	1.13	500,000	506,975	507,765	5,719
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	12/1/2017	4.500%	1.00	500,000	517,460	526,228	5,154
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	1/5/2018	5.000%	1.08	25,000	25,737	26,032	278
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	9/22/2017	5.050%	1.25	20,000	21,064	21,072	264
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/22/2018	5.300%	1.74	450,000	501,903	505,310	8,708
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	4/6/2020	4.750%	1.01	500,000	514,220	519,018	5,204
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	9/29/2017	5.320%	1.56	50,000	54,999	55,485	856
FEDERAL FARM CR BKS CONS SYSTEMWIDE FEDERAL HOME LOAN BKS CONS BDS	AA+	9/3/2019	4.670%	1.11	450,000	468,437	474,408	5,176
FEDERAL HOME LOAN BKS CONS BDS	AA+	2/27/2018	2.250%	0.79	250,000	252,503	253,238	1,990
FEDERAL HOME LOAN BKS CONS BDS	AA+ AA+	9/8/2017	2.875%	1.75	60,000	62,672	63,318	1,097
FEDERAL HOME LOAN BKS CONS BDS	AA+ AA+	9/11/2020 12/8/2017	2.625% 3.125%	1.05	500,000	508,070	508,420	5,325
FEDERAL HOME LOAN BKS CONS BDS	AA+ AA+	12/8/2017	1.125%	1.04 0.74	25,000	25,519	25,552	266
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/9/2017	1.520%	1.41	30,000 250,000	30,043 250,760	30,064	222
FEDERAL HOME LOAN BKS CONS BDS	AA+	6/24/2019	5.125%	1.46	60,000	65,656	250,000 66,338	3,526 959
FEDERAL HOME LOAN BKS CONS BDS	AA+	8/15/2019	4.625%	1.69	200,000	217,714	219,188	3,671
FEDERAL HOME LOAN BKS CONS BDS	AA+	6/12/2020	5.250%	0.85	500,000	509,485	511,280	4,305
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/9/2016	3.750%	1.29	250,000	261,985	262,078	3,369
FEDERAL HOME LOAN BKS CONS BDS	AA+	6/5/2017	4.375%	1.46	25,000	26,802	26,891	391
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/14/2018	4.125%	1.55	125,000	134,316	136,268	2,086
FEDERAL HOME LOAN BKS CONS BDS	AA+	7/1/2019	4.125%	1.58	700,000	754,796	758,907	11,956
FEDERAL NATL MTG ASSN	AA+	12/13/2019	1.625%	1.51	100,000	100,341	102,335	1,517
FEDERAL NATL MTG ASSN	AA+	3/13/2020	1.500%	1.62	50,000	49,792	50,733	808
FEDERAL NATL MTG ASSN	AA+	1/21/2020	1.500%	1.78	50,000	49,401	50,592	877
FEDERAL NATL MTG ASSN	AA+	6/22/2020	1.875%	1.77	325,000	326,047	333,132	5,781
FEDERAL NATL MTG ASSN	AA+	11/15/2016	1.375%	1.88	100,000	98,110	101,208	1,842
FEDERAL NATL MTG ASSN	AA+	11/30/2020	1.625%	1.21	150,000	151,160	152,282	1,832
FEDERAL HOME LN MTG CORP MULTICLASS	NR	12/28/2020	3.531%	1.99	100,000	104,821	106,188	2,084
FEDERAL HOME LN MTG CORP	AA+	2/26/2021	4.875%	1.13	115,000	121,254	121,538	1,368
FEDERAL HOME LN MTG CORP FEDERAL HOME LN MTG CORP	AA+	11/27/2018	3.750%	1.31	500,000	526,890	528,243	6,886
FEDERAL HOME LN MTG CORP	AA+ AA+	6/25/2020 6/13/2018	1.750% 1.250%	1.35	50,000	50,471	51,051	681
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	3/27/2019	3.840%	1.45 2.22	50,000	49,708 255,938	50,386	719
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	5/30/2019	2.680%	1.90	250,000 476,103	485,135	266,641 495,892	5,682
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	10/2/2019	1.940%	1.88	468,357	469,608		9,218
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	5/1/2018	5.000%	1.67	88,507	91,171	472,748 93,292	8,829 1,523
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	4/1/2019	4.890%	2.21	255,735	273,107	283,706	6,036
INTERNATIONAL BUSINESS MACHS SR GLBL	AA-	7/1/2019	1.071%	1.10	100,000	100,118	99,977	1,102
IOWA FIN AUTH REV ST REVOLVING FD	AAA	4/1/2019	3.280%	1.46	25,000	25,791	25,850	377
MICROSOFT CORP NT	AAA	7/1/2019	4.200%	1.54	100,000	106,262	105,783	1,633
MONONA WIS TAXABLE PROM NTS 2015B	N.A.	10/17/2016	3.250%	2.45	100,000	102,533	102,438	2,512
NEW YORK N Y GOBDS 2011 C TAXABLE	AA	2/6/2018	3.480%	1.40	100,000	103,405	102,992	1,448
OHIO ST GO BDS 2009 C TAXABLE	AA+	8/1/2018	4.371%	1.24	100,000	103,591	104,247	1,288
ORACLE CORP SR FLT NT	A+	6/1/2019	1.068%	1.04	25,000	25,019	25,042	259
OREGON ST GO ENERGY BDS 2006 B AMT	AA+	6/1/2020	4.000%	3.67	25,000	25,047	25,000	919
PASADENA CALIF PUB FING AUTH L LEASE	AA	10/1/2018	4.224%	1.50	25,000	25,710	25,739	386
TENNESSEE VALLEY AUTH GLBL PWR 07A	AA+	3/1/2018	5.500%	0.76	50,000	51,293	52,277	388
TENNESSEE VALLEY AUTH PWR BD 2008 B	AA+	7/7/2017	4.500%	1.18	500,000	520,930	524,868	6,157
WAL MART STORES INC SR GLBL NT	AA	10/1/2017	5.375%	1.00	100,000	101,096	102,239	1,011

## SILICON VALLEY GLEAN WATER

JOINT POWERS AUTHORITY ~ A PUBLIC ENTITY



1400 RADIO ROAD REDWOOD CITY, CALIFORNIA 94065 650.591.7121 | FAX: 650.591.7122 www.svcw.org

CITY OF SAN CARLOS | CITY OF REDWOOD CITY | CITY OF BELMONT | WEST BAY SANITARY DISTRICT

								Estimated
Broker/Dealer	Composite			Yield to			208 12	Annual \$ Yield
Investment Name WELLS FARGO & CO NEW SR GLBL NT	Credit	Maturity	Rate	Maturity	Par Value			0
FEDERAL FARM CR BKS CONS SYSTEMWIDE	A+ AA+	3/1/2018 11/1/2016	5.625% 1.010%	1.59 1.49	25,000 100,000	25,919 99,134	25,993	412
MONTGOMERY CNTY MD CTFS PARTN COPS	N.A.	2/15/2019	1.200%	1.49	100,000	98,410	100,000 100,058	1,478
RICHMOND VA GO PUB IMPT BDS C	AA	7/18/2017	2.599%	2.31	100,000	101,772	105,711	1,775 2,353
BANK NEW YORK MTN BK ENT FR	A+	4/1/2018	2.450%	2.41	100,000	100,036	103,394	2,333
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	4/5/2017	3.410%	2.25	119,098	124,430	127,583	2,800
GILEAD SCIENCES INC SR NT	A-	12/11/2017	2.550%	2.19	100,000	101,054	104,247	2,212
WISCONSIN ST GEN FD ANNUAL APP REV	AA-	10/26/2018	1.616%	2.40	100,000	96,645	100,150	2,319
PORT MORROW ORE TRANSMISSION F REV	AA	11/1/2019	2.737%	2.41	225,000	229,793	236,849	5,531
WACO TEX INDPT SCH DIST REF BDS	N.A.	7/15/2021	4.000%	1.85	165,000	175,557	179,571	3,255
FEDERAL NATL MTG ASSN	AA+	11/27/2020	1.800%	1.97	260,000	257,530	260,000	5,071
FEDERAL HOME LN MTG CORP	AA+	11/1/2020	1.500%	1.78	260,000	259,581	260,000	4,618
FEDERAL HOME LN MTG CORP	AA+	9/1/2020	1.750%	1.90	340,000	338,895	340,000	6,449
CASH & EQUIVALENTS Capital Improvement Program Reserve Total	-	-		0.45	-	1,357,781	680,342	6,110
oupital improvement Program Reserve Total						\$ 15,108,271	\$ 14,572,172	\$ 214,866
Stage 2 Capacity Reserve								
BERKSHIRE HATHAWAY FIN CORP GTD SR	AA	5/15/2018	5.400%	1.45	100,000	105,244	105,806	1,523
CEDAR PARK TEX CTFS OBLIG TAXABLE	AA	8/15/2018	5.280%	1.47	50,000	53,022	53,276	781
CISCO SYS INC SR GLBL NT	A+	1/15/2020	4.450%	2.04	75,000	80,381	81,465	1,641
CLARK CNTY NEV FOR ISSUES DTD GO BDS	AA	7/1/2017	4.300%	1.07	100,000	101,682	102,813	1,091
CONOCOPHILLIPS NT	BBB+	11/7/2016	5.200%	1.76	50,000	52,261	52,666	921
COOKEVILLE TENN GO INDUSTRIAL AND	N.A.	5/15/2018	3.000%	1.40	100,000	100,709	100,904	1,407
FEDERAL HOME LN MTG CORP PARTN GOLD FEDERAL HOME LN MTG CORP PARTN GOLD	N.A.	6/1/2017	5.000%	1.67	73,821	75,630	77,835	1,263
FEDERAL HOME LOAN BKS CONS BDS	N.A.	2/1/2019	4.500%	1.70	65,672	67,379	68,463	1,145
FEDERAL HOME LOAN BKS CONS BDS	AA+	11/1/2020	2.375%	1.53	100,000	102,475	103,674	1,570
FEDERAL HOME LOAN BKS CONS BDS	AA+ NR	12/13/2019 2/18/2021	1.375% 0.875%	1.86 1.12	100,000	98,165	101,561	1,828
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/29/2018	2.875%	1.12	100,000 100,000	99,667 100,266	100,107	1,115
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	2/10/2017	4.500%	1.15	100,000	104,570	101,105 104,616	999
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	5/15/2018	4.750%	1.01	250,000	257,110	259,365	1,205 2,602
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	9/29/2017	4.780%	1.27	55,000	58,338	58,600	740
FEDERAL HOME LOAN BKS CONS BDS	AA+	9/28/2018	2.250%	0.79	250,000	252,503	253,238	1,990
FEDERAL HOME LOAN BKS CONS BDS	AA+	9/8/2017	2.875%	1.75	60,000	62,672	63,318	1,097
FEDERAL HOME LOAN BKS CONS BDS	AA+	9/11/2020	3.125%	1.04	100,000	102,074	102,208	1,066
FEDERAL HOME LOAN BKS CONS BDS	AA+	12/8/2017	1.125%	0.74	100,000	100,144	100,213	740
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/9/2017	1.520%	1.41	200,000	200,608	200,000	2,821
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	6/24/2019	0.699%	0.78	50,000	50,002	49,959	391
FEDERAL HOME LOAN BKS CONS BDS	AA+	4/9/2018	5.125%	1.46	50,000	54,713	55,282	799
FEDERAL HOME LOAN BKS CONS BDS	AA+	8/15/2019	4.625%	1.11	75,000	78,064	79,022	863
FEDERAL HOME LOAN BKS CONS BDS FEDERAL HOME LOAN BKS CONS BDS	AA+	12/9/2016	4.375%	1.46	100,000	107,209	107,563	1,563
FEDERAL HOME LOAN BRS CONS BDS	AA+	3/9/2018	4.125%	1.58	125,000	134,785	135,376	2,135
FEDERAL NATL MTG ASSN	AA+ AA+	7/1/2019 3/13/2020	1.000% 1.625%	0.77 1.51	100,000	100,132	100,140	775
FEDERAL NATL MTG ASSN	AA+	7/25/2017	1.500%	1.62	100,000 100,000	100,341 99,584	102,335	1,517
FEDERAL NATL MTG ASSN	AA+	1/21/2020	1.500%	1.78	100,000	98,802	101,466 101,183	1,616 1,754
FEDERAL NATL MTG ASSN	AA+	6/22/2020	1.875%	1.77	175,000	175,564	179,379	3,113
FEDERAL NATL MTG ASSN	AA+	11/30/2020	1.375%	1.88	100,000	98,110	101,208	1,842
FEDERAL NATL MTG ASSN	AA+	12/28/2020	3.275%	1.34	100,000	103,974	104,239	1,389
FEDERAL HOME LN MTG CORP MULTICLASS	NR	2/26/2021	2.788%	1.79	76,517	77,762	78,430	1,394
FEDERAL HOME LN MTG CORP	AA+	1/14/2019	3.750%	1.31	250,000	263,445	264,046	3,443
FEDERAL HOME LN MTG CORP	AA+	10/25/2020	1.250%	0.69	55,000	55,120	55,177	380
FEDERAL HOME LN MTG CORP	AA+	3/27/2019	1.750%	1.35	100,000	100,942	102,101	1,363
FEDERAL HOME LN MTG CORP	AA+	5/12/2017	1.250%	1.39	100,000	99,588	101,316	1,384
FEDERAL HOME LN MTG CORP	AA+	5/30/2019	1.250%	1.45	100,000	99,415	100,772	1,439
FEDERAL HOME LN MTG CORP	AA+	8/1/2019	0.750%	1.05	100,000	99,631	99,836	1,048
FEDERAL NATL MTG ASSN GTD PASSTHRU FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	10/2/2019	3.840%	2.22	200,000	204,750	213,313	4,545
FEDERAL NATL MTG ASSN GTD PASSTHRU	N.A.	4/9/2018	4.000%	1.31	106,753	109,956	111,858	1,440
GARNER N C GO PUB IMPT BDS TAXABLE	N.A. AA	5/1/2018 12/1/2020	4.890% 3.050%	2.21 1.33	213,898 50,000	228,429 50,955	237,294	5,048
GENERAL ELEC CAP CORP MTN	AA A+	7/1/2020	3.050% 1.151%	1.33	100,000	100,182	51,183 99,695	677 1,150
IOWA FIN AUTH REV ST REVOLVING FD	AAA	2/1/2018	3.280%	1.46	100,000	103,162	103,399	1,506
JPMORGAN CHASE & CO SR NT	A-	8/7/2018	2.550%	2.66	50,000	49,843	51,202	1,323
LANCASTER CNTY NEB SCH DIST NO SCH	AA	8/1/2018	4.550%	2.60	50,000	53,803	55,903	1,398
						1. C. C. C. C. C. C. C.		187 D.C

## SILICON VALLEY GLEAN WATER

JOINT POWERS AUTHORITY ~ A PUBLIC ENTITY



1400 RADIO ROAD REDWOOD CITY, CALIFORNIA 94065 650.591.7121 | FAX: 650.591.7122 www.svcw.org

CITY OF SAN CARLOS | CITY OF REDWOOD CITY | CITY OF BELMONT | WEST BAY SANITARY DISTRICT

Broker/Dealer_	Composite		Coupon	Yield to				Estimated Annual \$ Yield
Investment Name	Credit	Maturity	Rate	Maturity	Par Value	Market Value	Cost	A CARL TO DE LA CARL AND A
MCDONALDS CORP MED TERM NT FR	BBB+	3/1/2021	5.800%	1.33	50,000	51,708	52.324	689
NORFOLK VA GO CAP IMPT BDS 2010 B	AA	1/15/2021	4.650%	1.87	100,000	106,710	106,524	1,998
NORTH ST PAUL MAPLEWOOD MINN I GO	AA	10/15/2017	5.000%	1.34	100,000	103,915	104,743	1,394
OREGON ST GO ENERGY BDS 2006 B AMT	AA+	3/1/2019	4.000%	3.67	100,000	100,187	100,000	3,676
SAN LUIS ARIZ PLEDGED EXCISE T REV	N.A.	2/1/2018	2.000%	1.24	100,000	100,102	100,000	1,243
TENNESSEE VALLEY AUTH PWR BD 2008 B	AA+	10/1/2017	4.500%	1.18	200,000	208,372	209,766	2,463
U S BANCORP MTNS BK ENT FR	AA-	11/1/2016	1.950%	1.61	100,000	100,509	100,201	1,620
UNIVERSITY CALIF REVS FOR PREV GEN	AA	7/1/2017	1.796%	1.66	50,000	50,142	49,568	832
WELLS FARGO & CO NEW SR GLBL NT	A+	10/1/2016	5.625%	1.59	100,000	103,676	103,971	1,648
WYETH NT	AA-	12/15/2016	5.450%	1.02	50,000	50,516	51,088	517
XTO ENERGY INC SR NT	AA+	4/1/2018	5.500%	1.58	100,000	105,516	106,117	1,670
FEDERAL FARM CR BKS CONS SYSTEMWIDE	AA+	11/15/2018	1.010%	1.49	200,000	198,268	200,000	2,956
MONTGOMERY CNTY MD CTFS PARTN COPS	N.A.	7/1/2019	1.200%	1.80	100,000	98,410	100,058	1,775
BANK NEW YORK MTN BK ENT FR	A+	12/11/2017	2.450%	2.41	150,000	150,054	155,091	3,615
GILEAD SCIENCES INC SR NT	A-	4/1/2017	2.550%	2.19	150,000	151,581	156,371	3,318
WISCONSIN ST GEN FD ANNUAL APP REV	AA-	6/15/2018	1.616%	2.40	100,000	96,645	100,150	2,319
FEDERAL HOME LN MTG CORP	AA+	10/26/2018	1.250%	1.97	90,000	88,058	90,000	1,738
METRO WASTEWTR RECLAMATION DIS REV	AA+	11/1/2019	4.718%	1.94	100,000	106,897	108,949	2,071
WACO TEX INDPT SCH DIST REF BDS	N.A.	11/27/2020	4.000%	1.85	55.000	58,519	59,857	1,085
FEDERAL HOME LN MTG CORP	AA+	9/1/2020	1.500%	1.90	60,000	58,006	60,000	1,100
FEDERAL HOME LN MTG CORP	AA+	5/1/2021	1.050%	2.41	100,000	97,570	99,900	2,347
FEDERAL NATL MTG ASSN	AA+	8/25/2021	1.250%	1.61	60,000	59,571	59,985	957
FEDERAL NATL MTG ASSN	AA+	4/1/2019	1.800%	1.97	60,000	59,430	60,000	1,170
FEDERAL HOME LN MTG CORP	AA+	2/15/2020	1.750%	1.90	100,000	99,675	100,000	1,897
CASH & EQUIVALENTS	-	-	-	0.45	-	426,298	426,298	1,918
Stage 2 Capacity Reserve Total				0.40		\$ 7,903,493	\$ 7,994,865	
5 1 3						φ 1,505,455	φ 1,554,005	\$ 110,000
Subtotal, Bank of the West						\$ 26,478,941	\$ 26,069,524	\$ 385,226
California Local Agency Investment Fund		LAIF	0.719%			\$ 836,747	\$ 836,747	6,016
						5. 		25 
TOTAL UNRESTRICTED INVESTMENTS						\$ 27,315,688	\$ 26,906,271	\$ 391,242
Bank of New York (Trustee)								
2008 Reserve Account - Morgan Stanley Treas Sec X9USDMORS			0.0000/			44		
2008 Revenue Account - Morgan Stanley Treas Sec X90SDMORS		-	0.000%	-		11 4	11 4	-
2008 Interest Account - Morgan Stanley Treas Sec X90SDMORS			0.000%					-
2009 Reserve Account - Federal National Mortgage Assn 313G3Q73	Aaa	- 7/26/2019	1.150%	- 1.16		4,322	4,322	-
2009 Reserve Account - BMW BK North Amer Salt Lake 05580ACK3	Aaa					4,739,035	4,780,000	54,973
2009 Reserve Account - Morgan Stanley Treas Sec X9USDMORS		7/24/2019	2.000%	1.98		151,620	150,000	3,002
			0.000%	-		104,681	104,681	-
2009 Revenue Account - Morgan Stanley Treas Sec X9USDMORS		-	0.000%	÷.		288	288	2 <b>.</b>
2014 Revenue Account - Goldman Sachs Fin Sq Instl X9USDGLD4		-	0.000%	-		426	426	3 <del>,7</del> 3
2014 Interest Account - Goldman Sachs Fin Sq Instl X9USDGLD4		-	0.000%			13	13	853
2014 Principal Account - Goldman Sachs Fin Sq Instl X9USDGLD4		-	0.000%	7		7	7	-
2014 Project Account - Goldman Sachs Fin Sq Instl X9USDGLD4		-	0.000%			3,258	3,258	-
2014 COI Account - Goldman Sachs Fin Sq Instl X9USDGLD4		-	0.000%	-		5,138	5,138	
2015 Project Account - LAIF		3 <b>-</b> 2	0.719%	0.719		7,481,625	7,481,625	53,793
2015 Project Account - JP Morgan Prime MMKT Instl		-	0.000%	-		717	717	6 <u>4</u> 75
2015 Revenue Account - JP Morgan Prime MMKT Instl			0.000%	-		163	163	5 <b>-</b> 1

## SILICON VALLEY CLEAN WATER

JOINT POWERS AUTHORITY ~ A PUBLIC ENTITY



1400 RADIO ROAD REDWOOD CITY, CALIFORNIA 94065 650.591.7121 | FAX: 650.591.7122 WWW.SVCW.ORG

161.024

Weighted Average Yield to Maturity %

\$ 39,968,019 \$ 39,597,946

161,024

1,390,297

1.52%

CITY OF SAN CARLOS | CITY OF REDWOOD CITY | CITY OF BELMONT | WEST BAY SANITARY DISTRICT

Composite		Coupon	Yield to				Estima Annual \$ Y	
Credit	Maturity	Rate	Maturity	Par Value	Market Value	Cost	Earni	
Aaa	1/31/2017	3.125%	3.12	for phy "	84,177	86,678		.626
Aaa	7/31/2017	2.375%	2.35		7,561,979	7,715,749	177.	707
	-	0.000%			850	850	1	-
Aaa	1/31/2017	0.875%	0.87		595,238	597,836	5.	179
Aaa	7/31/2017	0.625%	0.63		596,743	596,728	12274	759
Aaa	1/31/2018	0.875%	0.88		598,557	599,629		267
Aaa	7/15/2018	0.000%			331,990	329,183		
Aaa	7/31/2018	1.375%	1.37		264,170	265,978	3.0	619
Aaa	1/31/2019	1.500%	1.49		606,274	610,349	9.0	033
Aaa	7/16/2019	1.686%	1.69		40,242,406	40,944,692	680,0	
		0.000%			1,495	1,495	1	
				-	\$ 63,375,187	\$ 64,279,818	\$ 999,	055
ice					\$ (50,883,880)	\$ (51,749,166)	\$ (887,	287)
					\$ 12,491,308	\$ 12,530,652		
	Credit Aaa Aaa Aaa Aaa Aaa Aaa Aaa Aaa Aaa	Credit         Maturity           Aaa         1/31/2017           Aaa         7/31/2017           Aaa         7/31/2017           Aaa         1/31/2017           Aaa         7/31/2017           Aaa         7/31/2017           Aaa         7/31/2017           Aaa         1/31/2018           Aaa         7/15/2018           Aaa         1/31/2019           Aaa         1/31/2019           Aaa         7/16/2019	Credit         Maturity         Rate           Aaa         1/31/2017         3.125%           Aaa         7/31/2017         2.375%           -         0.000%           Aaa         1/31/2017         0.875%           Aaa         1/31/2017         0.625%           Aaa         1/31/2018         0.875%           Aaa         7/15/2018         0.000%           Aaa         7/15/2018         1.375%           Aaa         1/31/2019         1.500%           Aaa         7/16/2019         1.686%           -         0.000%	Credit         Maturity         Rate         Maturity           Aaa         1/31/2017         3.125%         3.12           Aaa         7/31/2017         2.375%         2.35           -         0.000%         -           Aaa         1/31/2017         0.875%         0.87           Aaa         1/31/2017         0.625%         0.63           Aaa         1/31/2018         0.875%         0.88           Aaa         7/15/2018         0.000%         -           Aaa         7/12/018         1.375%         1.37           Aaa         1/31/2019         1.500%         1.49           Aaa         7/16/2019         1.686%         1.69           -         0.000%         -         -	Credit         Maturity         Rate         Maturity         Par Value           Aaa         1/31/2017         3.125%         3.12           Aaa         7/31/2017         2.375%         2.35           -         0.000%         -           Aaa         1/31/2017         0.875%         0.87           Aaa         1/31/2017         0.625%         0.63           Aaa         1/31/2018         0.875%         0.88           Aaa         7/15/2018         0.000%         -           Aaa         7/15/2018         0.000%         -           Aaa         7/12017         1.375%         1.37           Aaa         1/31/2019         1.500%         1.49           Aaa         1/31/2019         1.686%         1.69           -         0.000%         -         -	Credit         Maturity         Rate         Maturity         Par Value         Market Value           Aaa         1/31/2017         3.125%         3.12         84,177           Aaa         7/31/2017         2.375%         2.35         7,561,979           -         0.000%         -         850           Aaa         1/31/2017         0.875%         0.87         595,238           Aaa         1/31/2017         0.625%         0.63         596,743           Aaa         1/31/2018         0.875%         0.88         598,557           Aaa         7/15/2018         0.000%         -         331,990           Aaa         7/31/2017         1.500%         1.49         606,274           Aaa         1/31/2018         1.375%         1.37         264,170           Aaa         1/31/2019         1.500%         1.49         606,274           Aaa         7/16/2019         1.686%         1.69         40,242,406           -         0.000%         -         1.495         \$ 63,375,187           Geo         -         -         5,0883,880)         \$ (50,883,880)	Credit         Maturity         Rate         Maturity         Par Value         Market Value         Cost           Aaa         1/31/2017         3.125%         3.12         84,177         86,678           Aaa         7/31/2017         2.375%         2.35         7,561,979         7,715,749           -         0.000%         -         850         850           Aaa         1/31/2017         0.875%         0.87         595,238         597,836           Aaa         1/31/2017         0.625%         0.63         596,743         596,728           Aaa         1/31/2018         0.875%         0.88         598,557         599,629           Aaa         7/15/2018         0.000%         -         331,990         329,183           Aaa         7/31/2017         1.500%         1.49         606,274         610,349           Aaa         1/31/2018         1.375%         1.37         264,170         265,978           Aaa         1/31/2019         1.500%         1.49         606,274         610,349           Aaa         1/31/2019         1.686%         1.69         40,242,406         40,944,692           -         0.000%         -         1.495 </td <td>Credit         Maturity         Rate         Maturity         Par Value         Market Value         Cost         Earn           Aaa         1/31/2017         3.125%         3.12         84,177         86,678         2           Aaa         7/31/2017         2.375%         2.35         7,561,979         7,715,749         177           -         0.000%         -         850         850         850         177           Aaa         1/31/2017         0.875%         0.87         595,238         597,836         55           Aaa         7/31/2017         0.625%         0.63         596,743         596,728         33           Aaa         1/31/2018         0.875%         0.88         598,557         599,629         5           Aaa         7/15/2018         0.000%         -         331,990         329,183         3           Aaa         7/31/2018         1.375%         1.37         264,170         265,978         3           Aaa         1/31/2019         1.500%         1.49         606,274         610,349         9           Aaa         7/16/2019         1.686%         1.69         40,242,406         40,944,692         680</td>	Credit         Maturity         Rate         Maturity         Par Value         Market Value         Cost         Earn           Aaa         1/31/2017         3.125%         3.12         84,177         86,678         2           Aaa         7/31/2017         2.375%         2.35         7,561,979         7,715,749         177           -         0.000%         -         850         850         850         177           Aaa         1/31/2017         0.875%         0.87         595,238         597,836         55           Aaa         7/31/2017         0.625%         0.63         596,743         596,728         33           Aaa         1/31/2018         0.875%         0.88         598,557         599,629         5           Aaa         7/15/2018         0.000%         -         331,990         329,183         3           Aaa         7/31/2018         1.375%         1.37         264,170         265,978         3           Aaa         1/31/2019         1.500%         1.49         606,274         610,349         9           Aaa         7/16/2019         1.686%         1.69         40,242,406         40,944,692         680

**Uninvested Operating Cash** 

TOTAL CASH & INVESTMENTS, UNRESTRICTED AND WITH TRUSTEE

Summary by Investment Type:	Market Value
US Treasuries	\$ 109,306
Agencies	22,377,711
Commercial Paper / Corporate Bonds	2,712,690
Municipal Bonds / Notes	4,298,569
Money Market / Certificates of Deposit	2,151,372
Local Agency Investment Fund	8,318,372
TOTAL	\$ 39,968,019
Summary by Purpose / Restriction Level	Market Value
Working Capital	\$ 997,770
Operations & Capital Budget Reserve	3,467,177
Capital Improvement Program Reserve	15,108,271
Stage 2 Capacity Reserve	7,903,493
Debt Service Payments Received	4,489
Debt Reserve	5,004,189
Debt Proceeds	7,482,629
TOTAL	\$ 39,968,019
Summary by Liquidity:	Market Value
0-1 years	\$ 14,810,688
1-2 years	5,501,227
2-3 years	11,351,654
3-5 years	8,304,451
TOTAL	\$ 39,968,019

SVCW has sufficient liquid resources available to meet expenditure requirements per SVCW's investment policy. All SVCW investments are in compliance with SVCW's Investment Policy.

M. Anderson

## FINANCE STATUS REPORT

## <u>ISSUE</u>

Operating Fund Financial Update as of December 31, 2016. This Update is a Preliminary Estimate of the Second Quarter of the 2016-17 Fiscal Year.

### DISCUSSION

Staff presents the Commission with a preliminary financial update each quarter of the fiscal year. The below points highlight key findings found in the attached summary table.

Revenue: After the second fiscal quarter, actual revenue was at Budget. All Member Agency contributions were received on time. Miscellaneous Income including grease & septic acceptance, pretreatment programs, restaurant grease programs, and laboratory analysis, ended the quarter \$10 thousand (0.1%) more than budgeted.

Expense: Through the second quarter, operating expenses were \$10.84 million, or 9.0% less than the \$11.91 million budgeted. Notable favorable variances (where spending was less than the amount budgeted) included:

- Salaries & Compensation was \$316.7 thousand (4.5%) below budget due to a maintenance vacancy and the timing of performance incentives payments, which are paid at the end of the fiscal year but were budgeted monthly.
- Utilities expense is \$34.5 thousand (7.9%) less than budget as the cogeneration engines continued to perform better than planned.
- Administrative fees are under budget by \$190 thousand (27.7%) due to timing of permitting fees including Regional Monitoring Programs and NPDES planning. Both were budgeted early in the year but will be paid in January 2017.
- Equipment Maintenance costs were \$216 thousand (21.4%) less than budget. Several Information Technology initiatives are scheduled for later this year including upgrades of software licenses, renewal of equipment support contracts, door security repairs, and equipment replacement.
- Chemicals expense was \$40.5 thousand (6.5%) below budget. The Operations Division has successfully utilized a lower-cost odor control chemical, Trioxyn®.
- The Operating Division budget was \$183 thousand (22.3%) less than budget for Contractual Services. This favorability was from less hauling costs as the use of drying beds has reduced the volume and weight of solids hauled away.

			:	-	3			
-		SVC -	W Operating Re	venue and Ex \$Better/	penditures v % Better/	rersus Budget - Thr	SVCW Operating Revenue and Expenditures versus Budget - Through December 31, 2016 Setter/ %Better/ %Be	
Description Revenue:		YTD Actual \$ 11,407,741	YTD Budget \$ 11,397,347	(Worse) \$ 10,394	(Worse) 0.1%	comment Revenues on budge	t. Grease delivery volumes hav	comment Revenues on budget. Grease delivery volumes have risen in response to rate decrease.
Expenditures:		_			_			
Personnel		\$ 6,779,944	\$ 7,096,657	\$ 316,713	4.5%	One vacancy in Maii payout that occurs l wet weather events.	intenance Department. Other later than the Budget's accrua.	One vacancy in Maintenance Department. Other timing issues related to year-end incentive program payout that occurs later than the Budget's accrual method. Overtime at budgeted levels despite frequent wet weather events.
Utilities		960,657	995,193	34,536	3.5%	Reduced use of nat	Reduced use of natural gas. Cogeneration engines performing well.	performing well.
Admin Exp, Supplies, Leases	es	496,816	686,706	189,890	27.7%	Timing of permittin automation softwa	Timing of permitting fees to Regional Monitoring I automation software license will occur in January.	Timing of permitting fees to Regional Monitoring Program and BACWA. Purchase of communications automation software license will occur in January.
Equipment Maintenance		791,882	1,008,041	216,159	21.4%	Delay in security ar schedule. No signifi	Delay in security and surveillance service. Decrease in instrumentati schedule. No significant cogeneration engine repairs were incurred.	Delay in security and surveillance service. Decrease in instrumentation services due to reduced work schedule. No significant cogeneration engine repairs were incurred.
Chemicals		581,591	622,165	40,574	6.5%	Reduced purchases	of nitrate due to trial of new o	Reduced purchases of nitrate due to trial of new odor control chemical, trioxyn, a less costly material.
Professional Services		412,004	481,003	68,999	14.3%	Delay in purchase on network security .	ıf 1.S. servicesfor Infor CMMS : iming of раутеnts for legal, а	Delay in purchase of 1.S. services for Infor CMIMS software, Worktech timecard software, SCADA, and network security . Timing of payments for legal, and contractor prequalification activity.
Contractual Services		639,168	822,665	183,497	22.3%	Less contractual se yet begun, use of d to better rag screei	vices due to delay in network s ying beds has reduced sludge ing, and postponement of was	Less contractual services due to delay in network support agreement. New dewatering process has not yet begun, use of drying beds has reduced sludge hauling volumes, tanks have needed less cleaning due to better rag screening, and postponement of wastewater educational support to the 2nd quarter.
Memberships, Conferences, & Training	es, & Training	179,189	200,446	21,257	10.6%	Timing of members	Timing of memberships, training, and conferences.	
TOTAL Expenditures:		\$ 10,841,252	\$ 11,912,876	\$ 1,071,624	<b>%0.6</b>			
			Operatir	ig Expendi	tures through (\$ Millions)	Operating Expenditures through December 31, 2016 (د مینانمید)	· 31, 2016	
	\$ 8.0					fend		
	\$ 7.0						Actual Sp	Actual Spending YTD
							Budget YTD	e
	\$ 6.0							
	\$ 5.0							
	\$ 4.0 -							
	\$ <b>3.0</b>							
	\$ 2.0 -							
	\$ 1.0 -		ŝ	ī	I.			
	-	Personnel Util	Utilities Adm Supplie	Admin Exp, E Supplies, Leases Mi	Equipment Maintenance	Chemicals	Professional Contractual Services Services	Memberships, Conferences, & Training
]								

## ENGINEERING REPORT: JANUARY 2017 CAPITAL IMPROVEMENT PROGRAM IMPLEMENTATION

<u>Solids Process Automation (8007, 8018, 8021)</u>: In support of automating the entire treatment process, this project works to automate the primary sedimentation, solids thickening, and digestion processes.

The Solids Process Automation project has been in construction since 2013, with Monterey Mechanical doing the construction. It is a very large and complex project and involves modifying and installing new mechanical, electrical, structural, and controls equipment. This project was funded via SRF funds along with two other projects that have already been completed.

Planned Commission Actions: Accept Project – February 2017

**Food Waste: Receiving Station Improvements (9229):** Plan, design and construct a receiving station for accepting municipal organic waste for anaerobic digestion and methane production.

SVCW staff has engaged technology experts and potential food waste providers in an effort to optimize its existing anaerobic digester, grease receiving, and cogeneration infrastructure. By accepting organic food waste, minimally processing it, and injecting it into the digesters, SVCW will be able to produce more digester gas and generate more electricity, reducing the monthly PG&E bills, and receiving tipping fees for the waste acceptance. Based on successful discussions, SVCW plans to build a pilot facility to determine the effect of food waste acceptance on digester performance and operations. Improvements to the Grease Receiving Station are needed to complete the pilot study for food waste technology. In May 2016, staff was authorized to purchase a liquid waste receiving unit (Flo-Beast) that has significantly reduced the amount of maintenance required as well as optimized performance for the Grease Receiving Station. The Commission will be asked to Authorize the installation contract at the February 2017 meeting.

<u>Planned Commission Actions:</u> Award Installation Contract for Flo-Beast – February 2017

**Dual Media Filters 6A and 6B (9222):** Outfit the remaining two Dual Media Filters, including coatings, underdrain system, filter media, air scour equipment, and associated valves and piping.

The DMF 6A and 6B project will provide reliability for wet weather events; currently wet weather flows are bypassed around the filters when storm flows reach approximately 60 to 65 MGD. Completion of this work will allow higher flow to be treated before it is necessary to divert some or all flow around the filters. The practice of diverting flow around the filters is currently allowed in SVCW's NPDES permit, but is expected to be deleted in upcoming permits. This work will duplicate

the systems already installed in the ten active filters. The construction work is being performed by ERS with design assistance from Kennedy/Jenks.

Planned Commission Actions: Accept Project – March 2017

**Effluent Pipeline Replacement Project (6012):** Replace the entire effluent pipeline from where it exits the main structure to where it enters the San Francisco Bay.

The pipeline taking treated effluent to the bay for final discharge was found to be leaking and a project was awarded to Power Engineering to replace the pipeline in June 2015. Work has been ongoing since that time.

A method to protect the connection between the plant main structure and the HDPE pipeline needed to be designed as the project progressed, as it was not determined at the time the original project cost was developed. A change order was negotiated with the contractor to place a concrete bridge around the connection point to protect the pipe from unnecessary loads. Work is nearing completion on this critical project.

Planned Commission Actions: Accept Project – March 2017

**Conveyance System Program Planning (6006):** Perform environmental review of conveyance system alternatives and planning for various program elements.

The project team has performed detailed in-depth analysis of alternative alignments for the entire conveyance system. After developing and evaluating many alternatives, and receiving consent from the Commission on pursuing Alternative 4BE by initiating CEQA for this alternative, the project team is moving forward with the environmental review phase of the program. The Draft EIR was completed and circulated on November 29, 2016. A presentation was provided to the Commission in December 2016. A public meeting was held on December 14; four people attended. Comments on the DEIR were due on January 13<sup>th</sup>. Staff and consultants are preparing responses to the comments received and finalizing the EIR for presentation to the Commission for possible certification in April.

Planned Commission Actions: Certify EIR – April 2017

<u>Conveyance System Program Project Delivery (6006)</u>: Evaluate possible and preferred methods for project delivery.

In January 2016, the Commission approved a policy outlining procedures for using the Design-Build method for project delivery. The Commission also provided direction to staff to prepare an RFQ for wastewater treatment plant projects that are good candidates for the design-build method of project delivery. Task Orders were presented at the January 2017 meeting for approval of Owner's Advisor services to prepare Requests for Qualifications (RFQs) and Requests for Proposals (RFPs) for Progressive Design-Build delivery of some of the Conveyance System Projects.

Planned Commission Actions: Approve Procurement Documents – April 2017

Menlo Park Pump Station and Redwood City Pump Station Valve Replacement Project (Capital Project 262 and 263): Replace major valves at Menlo Park and Redwood City Pump Stations

The Maintenance Department has identified that replacement of valves at Menlo Park and Redwood City Pump Stations is necessary to keep the pump stations reliable over the next 5 - 7 years, until they are rehabilitated/replaced. Due to the lead time on the valves, SVCW will procure and install the valves as two separate contracts. The procurement of the valves was presented for approval at the January Commission Meeting and the installation contract will be presented for approval at the April or May Commission Meeting.

Planned Commission Actions: Award Installation Contract – April or May 2017

### SVCW Capital Improvement Program Actual Expenditure vs. Plan Through December 31, 2016

Project Phase	Project Count		Amended 2015 CIP Update	A	ctual Spent thru December 2016	\$ Unspent/ Remaining	% Unspent/ Remaining
Completed	103	\$	139,194,565	\$	137,312,790	\$ 1,881,775	1.4%
In Construction	29		75,997,343		60,507,570	15,489,773	20.4%
Planning & Design	35		461,274,545		25,527,134	435,747,411	94.5%
Other	33		136,483,183		4,888,461	131,594,722	96.4%
TOTAL	200	* \$	812,949,637	\$	228,235,956	\$ 584,713,681	71.9%

\* Consistent with the January 2017 Long Range Financial Plan, project cost estimates were increased by the construction cost index as provided by Engineering News Record.

				2008 CIP	2013 CIP	2015 CIP	30-Jan-17 Actual Spent
Project	Project	Ducto et Nous e		(Original,	Update	Update	thru
Phase Complete	No. 6001	Project Name 48-inch Force Main Reliability	Project Description/Status Replace the entire length of 48-inch diameter section of force main \$	2007 \$s) 2,539,400 \$	(2010 \$s) 43,060,000 \$	(2015 \$s) 40,000,000 \$	December 2016 41,204,050
complete	0001	Improvement	from RCPS to SCPS. This project incorporated CIP #6005 which was deleted in the CIP Update.	2,333,400 9	43,000,000 9	40,000,000 \$	41,204,050
Complete	6002	Conveyance System Master Plan (CSMP)	Planning for replacement and/or repail of force main and all five pump stations, including screening at the treatment plant.	1,250,000	2,386,483	2,374,494	0
Complete	7010	Pump Stations Preliminary Design and CEQA	Prepare preliminary design (up to 30% design) for all pump station work including support for CEQA and SRF loan application	-	3,000,000	3,128,769	3,079,614
Complete	7013	Pump Stations Secondary Communications	Provide secondary communications for remote monitoring and control	-	-	51,900	33,289
Complete	8001	Central Data Acquisition Unit PLC	Central Data Acquisition Unit PLC System Upgrade; Replacement	127,700	32,592	32,592	25,220
Complete	8002	System Upgrade Auto-reset of Effluent Pumps	for Automation Program. Remote reset of effluent pumps after a power outage.	38,900	15,266	15,266	
Complete	8003	Disinfection Area SCADA	Tie-in disinfection area to the SCADA network in conjunction with	16,100	-	-	-
Complete	8004	Install SCADA Servers	Hypochlorite proejct (9015) Purchase and install and program independent servers for SCADA	170,200	163,002	91,040	91,040
Complete	8005	Install MCC PLC	use only. Installation of MCC PLC in support of the Automation Program	214,900	209,226	209,225	202,370
Complete	8006	Turbine #1A-4B Air Flow Monitor	Combined with Activated Sludge Automation (CIP 8017)	160,900	-		
Complete	8008	Aeration Basins #1-4 Motorized Effluent Gate Controls	Combined with Activated Sludge Automation (CIP 8017)	201,100	-	-	-
Complete	8009	Aeration Basins #1-4 Mudvalve Operation	Combined with Activated Sludge Automation (CIP 8017)	80,500	-	-	-
Complete	8010	WAS Flow Controls	Combined with Activated Sludge Automation (CIP 8017)	20,200	-		-
Complete	8011	RAS Pump #1-6 Speed Adjust	Combined with Activated Sludge Automation (CIP 8017)	360,600	-	-	-
Complete	8012	Secondary Clarifier Inner / Outer Gates Motorized Controls	Combined with Activated Sludge Automation (CIP 8017)	80,500	-	-	-
Complete	8013	WAS Pump #1-4 Speed Adjust	Combined with Activated Sludge Automation (CIP 8017)	244,400	-	-	-
Complete	8015	CCT Weir Sluice Gate Operator	Combined with Activated Sludge Automation (CIP 8017)	128,500		-	
Complete	8017		Combine automation projects for processes related to Activated Sludge; this project is complete. Automates the activated sludge	4,411,400	8,428,965	7,474,051	7,473,607
Complete	8019	Clarifiers). Aeration Basin Gate Actuators	process. Combined with Activated Sludge Automation (CIP 8017)	278,836	6,569	6,569	
Complete	8020	Aeration Basin #1-4 Inlet Gate Controls	Combined with Activated Sludge Automation (CIP 8017)	80,500	-	-	
Complete	8022	SCADA Process Graphics on Information Management System	Enable SCADA view and data across IMS Network to allow data views from remote locations (offsite)	103,500	107,041	62,936	62,936
Complete	8026	Septic System (Grease Receiving) Auto Controls and Level	Automatic controls tied into SCADA system for monitoring grease receiving station operation. Expenditures charged to CIP #9021	47,600	19,019	-	
Complete	8027	Measurement Drying Bed Feed Flow Measurement	Install a new magnetic flow meter for measuring the amount of	54,100	6,232	6,232	0
Complete	8037	Automation System Integration -	sludge discharged to drying beds. Pulls out global automation programming tasks being completed by	-	620,260	646,883	637,048
Complete	9005	Bond Funded Primary Scum Grinders	B&V into SRF or Bond funded categories. Purchase and install 3 new grinders. Work was completed in house	265,700	-	-	
Complete	9006	Purchase Integrated Tool Vehicle	and via maintenance budget. Eliminate need for rental. Purchase vehicle to facilitate access to	104,000	79,502	81,992	81,992
Complete	9008	Centrifuge Motor Drive Replacement	decks with large equipment Replace motor drive on centrifuge.	161,500	71,808	71,808	(0)
Complete	0010			10.000	1 (22	1 (22)	
Complete	9010	Real-time Wind Direction Information	Monitor wind direction & speed; download to SCADA. Use for odor complaint documentation. Project complete.	19,000	1,633	1,633	-
Complete	9011	Portable Trash Pump	Replaces need to rent portable pump in response to flooding, overflows, and routine dewatering. Trailer-mounted, diesel driven 6" pump. Project complete.	-	-	37,859	37,859
Complete	9012	Digester #3 Rehabilitation and Upgrade	Repair digester for use as a primary digester. Clean digester, repair dome and skirt, slip-line bottom mix line.	1,811,400	3,415,426	3,792,600	3,792,600
Complete	9013	Waste Gas Burner Rehabilitation	Rehabilitate existing burners, including pilot and air flow monitoring equipment. Air permit required. Complete before re-	999,800	649,231	726,141	725,594
Complete	9016	High Pressure Air Piping and	roofing SHB Replace galvanized piping throughout the Plant used for	273,000	474,200	468,552	468,552
Complete	9018	Instrument Air Recycled Water For In-Plant Use	compressed air delivery. Utilize recycled water for sprinkler system in new administration	807,300	556,934	585,790	585,790
Complete	9019	Bisulfite Injector System	buildng as well as other in-plant uses. Alternate dechlorination injection system for reliability	225,900	16,740	16,740	6,231
Complete	9021	Improvements Grease Receiving Station Reliability	improvement. Convert station to two pits, allowing for expanded volume storage.	320,200	1,698,002	1,730,417	1,730,417
Complete	9022	Improvements and Odor Control Existing Freight Elevator	Improvements to controls, pumping, mixing. Bring passenger and freight elevators up to modern standards;	496,700	1,080,137	1,092,137	1,092,137
Complete	9022	Modernization	pring passenger and regine elevators up to modern standards; replaces controls. Passenger elevator deleted from this project and included with Administration/Plant Control Building project.	496,700	1,080,137	1,092,137	1,092,137
Complete	9023	Odor & Corrosion Control Master Plan	Address overall plant odor control and corrosion control needs.	148,500	95,182	95,182	-
Complete	9028	Laboratory Building Roof Rehabilitation	Rehabilitate laboratory building roof.	23,400	80,000	106,978	106,978
Complete	9029	Solids Handling Building Control Room HVAC/Scrubber	Air scrubbing to protect sensitive equipment, includes new breaker in (E) MCC, disconnect switch, conduit & wire for air handling unit.	473,400	349,334	390,681	390,681
Complete	9030	Secondary Clarifier Collector Drive Rehabilitation	Project complete. Work done in conjunction with	251,200	435,000	471,182	471,182
Complete	9032	Wireless Network Access Expansion	Extend wireless network throughout plant.	185,900	250,000		

				2008 CIP	2013 CIP	2015 CIP	30-Jan-17 Actual Spent
Project	Project			(Original,	Update	Update	thru
Phase	No.	Project Name	Project Description/Status	2007 \$s)	(2010 \$s)	(2015 \$s)	December 201
Complete	9035	Effluent Pipe Access Hatch	Install an access hatch to the effluent pipe to facilitate inspection,	215,300	215,300	123,508	123,508
Complete	9036	Primary Sludge Piping Rehabilitation	cleaning, and repairs. Combined with Bilge Pit and Pumping project (221)	136,300	541,152	559,131	559,131
Complete	9038	Moyno Progressive Cavity Pump	Replace all Moyno pumps throughout the plant; replacement parts	814,600	-	-	-
		Replacement	no longer available.				
Complete Complete	9040 9075	Digester #2 Cleaning IMS System Equipment Replacement	Clean D2; 1 digester every 5 years Purchase replacement and additional servers for overall Plant	269,100 572,800	162,630 572,800	162,630 67,517	162,630 52,474
complete	5075	initio System Equipment Replacement	computer information management system.	572,000	572,000	07,517	52,474
Complete	9076	Digester Mix Pump Rehabilitation	Rebuild one pump every three years; purchase a spare pump.	275,000	-	-	-
Complete	9095	Digester #2 Cover Repair	Scheduled repair and recoat of D2; expect to replace 15-20 years out	788,200	3,000,000	3,072,075	3,072,075
Complete	9099	Solids Handling Building HVAC Air	· · · · · · · · · · · · · · · · · · ·	1,673,100	1,911,100	2,152,400	2,340,918
		Scrubber-Implementation	Implement odor and corrossion control for entire SHB	,,	,- ,	, - ,	,,
Complete	9101	Fresh Water Lagoon Cleaning	Clean fresh water lagoon to provide necessary volume for	1,123,200	711,618	795,845	795,845
Complete	9104	Septage Receiving Area Odor Control	stormwater runoff. 2nd grease pump, in-line grinder and local control panel. Odor	1,115,400	71,602	71,602	71,602
complete	5104	septage necessing fired oddir control	control pulls negative pressure in pit to eliminate foul odors. Delete	1,113,400	71,002	,1,002	71,002
			and combine with 9021.				
Complete	9106	, , ,	Plan and proceed with implementation of LIMS for laboratory data and process information.	490,100	156,939	116,083	152,667
Complete	9114	System (LIMS) Historian Software	Software purchase and installation to facilitate historical tracking of	34,100	2,366	2,366	
			SCADA data.	- ,,	_,	_,,	
Complete	9124	Biosolids Master Plan	Master plan for handling, hauling and disposal/reuse of biosolids.	6,373,600	694,523	694,523	694,974
Complete	9125	Plant Service Road Resurfacing-Phase	Phase 1 of overall Plant resurfacing project; repairs or expansion of paved areas in anticipation of upcoming construction activities.	182,200	448,890	503,138	503,138
		1	Project complete. Transfer funds from 9131 to cover overage.				
Complete	9154	Cogeneration Engine Replacement	Upgrade cogeneration engine to enable full utilization of biogas	7,227,900	10,005,000	13,500,000	17,555,210
	0455		produced.	404 500	404.042	110 6 10	440.640
Complete	9155	Natural Gas to Plant	Pipe natural gas from front entrance to enable its use as fuel blending for the cogeneration engines and in administration	181,500	401,042	419,640	419,640
			building.				
Complete	9156	Administation and Plant Control	Build a new administration and control building at existing location.	11,408,900	20,000,000	21,247,355	21,236,430
Complete	0157	Building Replacement		226,200	70,203	70,203	70 202
Complete	9157	Solids Handling Building Roof Replacement	Replace the roof on SHB; leaks occurring.	226,200	70,203	70,203	70,203
Complete	9163	Demolition of Abandoned Equipment	Demolish/remove equipment in SHB that has not bee in operation	-	1,469,383	1,557,091	0
		in Solids Handling Building	for over 25 years.				
Complete	9167	Poilor Poplacoment	· · · · · · · · · · · · · · · · · · ·		400,000	108,050	
Complete	9167	Boiler Replacement	Replace boilers due to age and undersized for future use. Includes replacement of piping. Project is being constructed as a CCO to the	-	400,000	108,050	-
			Cogen Project.				
Complete	9178	Levee Repair behind Warehouse	Levee leaks when the stormwater retention basin fills to a certain	-	375,000	10,782	-
Complete	9179	Pretreatment Program Sample Room	level; this project repairs the levee. Provide a wet lab receiving area for source control to prepare		389,000	575,000	633,142
complete	5175	i retreatment i rogram sample koom	samples prior to analysis and also storage of equipment.		505,000	575,000	000,142
Complete	9180	Maintenance Shop Reconfiguration	Reconfigure maintenance spaces that have been displaced by other	-	1,372,800	228,038	280,541
Complete	9183	Stage 1 Screening at Plant Influent	projects. Construct a screening facility at influent end of plant.Originally to		858,000	4,844,000	4,217,215
complete	5185	Stage 1 Screening at Flant Innuent	be funded partially via CIP and partially from Operating budget in	-	838,000	4,844,000	4,217,215
			approximately 25/75 split.				
Complete	9193	T1 and T2 Replacement	Replace Transformers T1 and T2. Do work as CCO to 9801 - 9804	-	1,029,600	-	-
Complete	9194	T3 Replacement	(Power Reliability). Transfer project budget. Replace Transformer T3. Do work as CCO to 9801 - 9804 (Power		514,800		
complete	5154	15 hepideement	Reliability). Transfer project budget.		514,000		
Complete	9195	Wetside Power	Installs new PDP-2 and replaces old transformers, T1, T2, and T3.	-	1,716,000	111,831	-
			Adds new T4. Do work as CCO to 9801 - 9804 (Power Reliability).				
Complete	9198	Hot Water Piping Improvements -	Transfer project budget. Provide pumps and piping to allow the hot water loop to serve the	-	171,600	31,738	
		Phase I	new Plant Control and Lab Buildings.			,	
Complete	9199	Hot Water Piping Improvements -	Add primary and secondary pumping to connect new cogeneration	-	669,200	1,542	-
		Phase II	engines to the Plant hot water loop. Do work as CCO to 9154, Cogen. Transfer project budget				
Complete	9202	DMF Valve Replacement	Replace old valves in the DMF gallery. Valves are high in the air		915,749	962,654	997,139
			and scaffolding will be required for access.				·
Complete	9205	1406 Radio Road Property	Provide for general improvements at the newly purchased property	-	1,135,000	234,666	234,666
Complete	9207	Improvements Maintenance Building Roof	at 1406 Radio Road Replaces the roof atop the maintenance building, including		18,749	18,949	-
		Replacement	drainage improvements at the electrical room		_0,,	10,5 15	
Complete	9208	Solids Handling Building Demolition	Ready the SHB for new Cogeneration and dewatering equipment,	-	1,900,000	2,759,901	2,772,117
		and Improvements - Phase II	and seismic bracing and column repairs. Do project in conjunction				
Complete	9216	3W System Improvements	with CIP #9099. Make improvements to Plant Water system to assure adequate		171,600	314,600	312,088
Jonpiete			flow to all processes		1, 1,000	514,000	512,000
Complete	9127	PEC & PST 1 & 2 Protective Coatings	Do SSC #3 with CIP #9014; also replace SSC drive.	-	-	946,092	946,092
Complete	8032	Final Effluent Pumping Control	Combine w/CIP #8017; Existing PLC-5 equipment is aging and not	-	179,025	179,025	179,025
		System (FEP) Upgrade	up to latest Automation Standards and best practices dicate decoupling controls from other distinct process systems for				
			reliabiltiy. Add new SCADA View at existing FEP Platform. Includes				
			programming needed to decouple existing scheme and enhance				
			new controls. Construction completed as a CCO to ASA and CCO				
			funds deleted from this project.	1		,	

				2008 CIP	2013 CIP	2015 CIP	30-Jan-17 Actual Spen
Project	Project			(Original,	Update	Update	thr
Phase Complete	No. 8033	Project Name Dechlorination Control System	Project Description/Status Combine w/CIP #8017; Existing PLC-5 equipment is aging and not	2007 \$s)	(2010 \$s) 179,026	(2015 \$s) 179,026	December 201 179,026
complete	0033	Upgrade	up to latest Automation Standards and best practices dicate		175,020	175,020	175,020
			decoupling controls from other distinct process systems for				
			reliabiltiy. Move new Dechlor Control Panel and the SCADA View				
			above flood line to the newly provided platform at RAS/WAS				
			gallery. Includes programming needed to decouple existing				
			scheme and enhance new controls. Construction completed as a CCO to ASA and CCO funds deleted from this project.				
Complete	8034	Tertiary Filter Feed Pump Control	Combine w/CIP #8017; Existing PLC-5 equipment is aging and not	-	224,130	224,130	224,130
		System Upgrade	up to latest Automation Standards and, best practices dictate				
			decoupling controls from other distinct process systems for				
			reliabiltiy. Add new SCADA View to the existing platform. Includes				
			programming needed to decouple existing scheme and enhance new controls. Construction completed as a CCO to ASA and CCO				
			funds deleted from this project.				
Complete	8035	Chorination Control System Upgrade	Combine w/CIP #8017; Existing PLC-5 equipment is aging and not	-	185,478	185,479	185,479
			up to latest Automation Standards and best practices dicate				
			decoupling controls from other distinct process systems for				
			reliability. Includes programming needed to decouple existing				
			scheme and enhance new controls. Construction completed as a CCO to ASA and CCO funds deleted from this project.				
Complete	9007	Industrial Roll-up Doors for		21,700	19,664	19,664	19,664
		Warehouse	Combine with CIP #9132. Project complete				
Complete	9077	Engine Generator #4 Complete	Rebuild top end (valve job and associated parts; needed every	561,000	246,213	246,212	246,212
		Rebuild	20,000 hrs) and lower end (cam shaft, main and rod bearings, rods,				
			pistons and liners and ancillary parts and pieces; needed every 40,000 hrs).				
Complete	9098	Shipping and Receiving Trailer	Combine with CIP #9132. Project complete	34,700	-		
Complete	9119	RAS Discharge Line 36" Butterfly	Project Completed w/CIP #8017; Replace existing 36-inch butterfly	143,200	-	-	-
		Valve Replacement	valve with a knife gate valve to resolve ragging problem.				
Complete	9132	Storage and Purchasing Warehouse	Construct a new warehouse for secure storage of supplies,	430,700	994,655	1,001,862	1,001,862
			material, and equipment. Construct offices for Purchasing				
			department staff. Replace existing warehouse siding and skylights. Install two new roll-up doors and one double door.				
Complete	9150	Odor & Corrosion Control Program -	Work completed to date satisfactory for moving forward. Provides		100,000	75,450	75,450
		General Support	support and funding for general requirements of projects			,	,
			contained within the Odor & Corrosion Control Program.				
Complete	9153	High Pressure Pump Safety Cutout	Work completed in-house. Project Complete.	28,700	11,233	11,233	-
Complete	9161	Switch Replacement Digester #3 Cleaning	Combine w/CIP #9012; Clean Digester #3 to facilitate effective				
complete	5101		solids treatment and provide access for Digester #3 Rehabilitation				
			and Upgrade project (CIP 9012). Includes purging of Digester #1,				
			screened transfer of contents from Digester #3 to Digester #1, and				
			disposal of screenings and Digester #3 residual contents.				
Complete	9162	Digester Mix System Improvements	Combine w/CIP #9012; Replace three existing Digester Mixing	-	-	-	-
			Pumps with three screw centrifugal pumps and one spare to improve pumping and digester operation and reduce maintenance.				
			The work is included with the Digester #3 Rehabilitation and				
			Upgrade Project (CIP 9012).				
Complete	9166	Digestion System Enhancements	Combine w/CIP #8021 and transfer budget. Upgrade existing	-	-	-	-
			digestion system to allow enhanced operation with three primary				
			digesters in service. Enhancements include a third heat exchanger				
			and replacement of the aging sludge recirculation pumps for all three digesters.				
Complete	9182	Property Acquisition	Per Engin 7/16, Transfer costs to Proj 264	-	2,540,000	2,540,000	-
Complete	9191	Cathodic Protection at WWTP	This project replaces the worn out Plant rectifier for cathodic	-	130,000		
			protection on the influent and effluent pipes. Delete project from				
			CIP; work done in house.				
Complete	9201	Dimminutor procurement and	Purchase and install 2 dimmunitors for each MPPS and SCPS.	-	334,814	374,323	374,442
		installation	Purchase 1 spare for emergency installation. Budget allocated out of 9152				
Complete	9203	Central Chillers Replacement	Existing Chillers 1 and 2 are undersized and have reached the end	-	996,448	1,109,003	1,109,003
•			of their useful lives and provide no redundancy. Chiller #1 has				
			stopped functioning and is no longer serviceable. This project				
			replaces the two chillers with three new chillers, providing one for				
			redundancy and greatly enhancing reliability. Budget allocated out of 9152				
Complete	9204	MPPS Concrete Repair	Severe corrosion and spalling concrete have been witnessed at the		68,155	68,155	68,155
			Menlo Park Pump Station, compromising the integrity of the		,-50	,	-0,200
			structure and posing a safety hazard to SBSA Utility Workers. This				
			project will also remove the chemical storage tanks, piping, and				
6	-	Constant Ch. 15. Clinic	pumps that are no longer used. Budget allocated out of 9152				
Complete	9211	Secondary Clarifier 6" Water Line	Replace the 6-inch water line situated on the eastern wall of the	-	70,000	59,496	59,496
		Replacement	secondary clarifiers under the Activated Sludge Automation project. Project pulled from CIP #9152.				
	9213	Area Lighting	Replacement of Plant area lighting to LED lights by in-house staff		56,000	55,547	68,415
Complete							

Project Phase	Project No.	Project Name	Project Description/Status	2008 CIP (Original, 2007 \$s)	2013 CIP Update (2010 \$s)	2015 CIP Update (2015 \$s)	30-Jan-17 Actual Spent thru December 2016
Complete	9227	Sodium Bisulfite Tank Alarms & Controls	Provide additional level indicating device, alarms for chemical loading, and controls for heat trace equipment. Currently the 4 tank system has only a single LIT; for safety and critical process control, a redundant LIT is needed. Project will also install visual and audible alarms.		-	-	-
Complete	9801	12 kV Primary Switchgear Replacement	Replace primary switchgear due to existing one's obsolescence. Project includes full enclosure and SCADA connection, cabling to T1&T2. Join CIP #s 9801 through 9804 into a larger Power Reliability Improvements project.	-	-	3,152,470	3,188,875
Complete	9802	Motor Control Center P-1,2,3, &4 Replacement	Replace all main Motor Control Center Panels P1 through P4 which have reached the end of their useful lives. Join CIP #s 9801 through 9804 into a larger Power Reliability Improvements project.	-	-	3,130,760	3,160,662
Complete	9803	Electrical System Redundancy	Replace Power Distribution Panels PD1 and PD2 due to obsolescence. Includes tie-breakers for flexibility between T1 and T2. Join CIP #s 9801 through 9804 into a larger Power Reliability Improvements project.	-	-	3,134,080	3,163,940
Complete	9805	Cogeneration System Connection to Primary Switchgear	Work completed under Power Reliability Improvements (9801 to 9804). Project Complete.	-	800,000	3,429	-
Complete	9804	Standby Power Upgrade	Install new standby bus for P1 through P5. Including new ATS's and cabling to P-6 and 2 new standby generators rated at 1MW each. Join CIP #s 9801 through 9804 into a larger Power Reliability Improvements project.	-	-	3,412,623	3,506,324
OTALS - CO	MPLETED	PROJECTS		\$51,504,236	\$126,514,271	\$139,194,565	\$137,312,790

#### SVCW Capital Improvement Program CIP Project Status - IN CONSTRUCTION

				2008 CIP			ded 2015 CIP	Actual Sp
ect Phase	Project No.	Project Name	Project Description/Status	(Original, 2007 \$s)	Update (2010 \$s)		Update (2015 \$s)	December 2
onstr		Influent Force Main Emergency	As-needed repairs if leaks in the influent force main occur.	\$ 2,145,000	· · · · · · · · · · · · · · · · · · ·		3,840,157	2,751,
		Repair	· · · · · · · · · · · · · · · · · · ·					
Constr	6012	Effluent Pipeline and Outfall	Improve reliability of Effluent Pipeline and Outfall, which have	-	12,450,438	\$	10,063,562	9,600,
Constr	7012	Reliability Improvement Pump Stations Processor Upgrade &	historically experienced leaks Install new PLC processors for existing Pump Station Controls			\$	298,151	86,
.0130		T-1 Transition for Primary Communications				Ļ	256,151	60,
Constr	8007	Primary Sedimentation Control	Install basic PLC and Communication equipment, conduit and	3,245,100	2,899,640	\$	5,442,406	5,902
		System	primary sensing devices for primary sedimentation tanks. Do as part of SPA project					
Constr	8018	Gravity Thickener Process	Install basic PLC and Communication equipment, conduit and	2,105,800	4,285,314	\$	6,223,412	7,330
		Automation	primary sensing devices in thickener area. Part of SPA project.	2 500 500	0.000.000			=
Constr		Anaerobic Digestion Process Automation	Automate digester process. Part of SPA project.	2,589,600	8,882,096		9,535,154	7,383
Constr	8023	SCADA/Auto Response to Plant Alarm Conditions	Planning and programming effort to maintain reliability while reducing labor demand. Requires Automation Program and	1,446,700	1,255,286	Ş	744,749	226
Constr	8025	No. 3 Water Control System	Communications Upgrade to be completed. Install basic PLC and Communication equipment, conduit and	111,700	225,000	ć	231,430	44
Jonsti	8025	No. 5 Water Control System	primary sensing devices for #3 water system.	111,700	223,000	Ş	231,430	44
Constr	8036	Automation System Integration - SRF Funded	Use funding for global automation tasks funded by SRF loan program	-	416,545	\$	445,294	137
Constr	8038	Process Return Flow Meter and	Install flow meters and samplers on small side streams to be able	-	357,500	\$	382,370	115
		Sampler Installation	to monitor and track these flows. Project is being installed in- house.					
Constr	9014	Process Tanks Concrete and Steel Protective Coatings Replacement	Replace coating in PEC and PST 1&2 (1st phase). Add FFR Wet Pit to project scope. Do with CIP #9127.	-	-	\$	5,293,542	3,368
Constr	9015	Hypochlorite Dosing System Rehabilitation Automation	Replaces pipe, valves, pumps, manifold to allow chlorination for disinfection & odor control; work done in house. Current project	372,900	1,350,000	\$	820,044	613
			replaces the two tanks with double-walled tanks.					
Constr	9034	Electrical Conductor Replacement - MCC Room to Wetside/Dryside	Multiple year project to replace old and corroded electrical cabling throughout the Plant.	4,903,500	2,400,000	\$	2,791,033	308
	0067	Loads		400,400				
Constr	9067	Dewatering Process Control System Upgrade	Work being completed under CIP #8021, SPA project. Adds new SCADA View at existing location, programming for cutover of new evolution believe by four while project and the second sec	108,400	-	\$	-	
Constr	9080	Primary Sedimentation Tanks	controls. Delete budget from this project. Replace or rebuild collector drive system, including chains and	1,929,100	1,929,100	Ś	4,309,732	1,985
		Collector System Replacement	filghts; one tank every 2 years.	_,,	_,,-		.,,	_,
Constr	9096	Plant Architectural Painting	Plant-wide painting including pumps, piping, equipment and structures. Painting necessary to prevent corrosion & for longevity	1,564,900	1,564,900	\$	1,813,307	388
	0110	CODA laboration with laborated	of Plant's assets.	491.000	2 1 69 5 60	ć	2 459 002	2 0 2 2
Constr	9118	SCADA Integration with Integrated Business Management System	Information Management System and SCADA to be tied together for asset management and maintenance scheduling.	481,000	2,168,560	Ş	2,458,093	2,023
Constr	9128	PST 3 & 4 Protective Coatings	Complete with 9080 - PST Collector System Replacement	714,150	714,150	\$	2,869,160	1,617
Constr	9131	Plant Service Road Resurfacing-Phase 2	Plant site grading and paving.	1,089,000	821,310	\$	953,372	153
Constr	9152	Small Capital Equipment Replacement	Ongoing replacement of equipment for maintenance needs throughout plant	3,714,000	1,954,500	\$	2,238,071	1,231
Constr	9164	Dewatering and Solids Handling Improvements - Phase I	Recommendations from the Biosolids Master Plan for dewatering improvements.	-	3,897,253	\$	5,536,578	6,377
onstr	9177	Implement Security Plan	Implement inhancements outlined in Security Document; conjoin	-	1,920,000	Ś	1,165,990	526
		Enhancements	with capital improvements as they are being implemented.					
Constr	9188	DMF Underdrain Access Hatches	There is no access point to the DMF underdrains. This project will provide such access.	-	105,600	\$	116,871	2
Constr	9214	Alternate Bisulfite Injection Point	Provide an alternate bisulfite injection point in order to reduce the	-	423,660	\$	457,631	10
Constr	9222	Dual Media Filters 6A and 6B	chance of permit violation Construct two new Dual Media Filters and associated valves and	-	3,452,571	\$	2,053,201	567
Constr	9226	DMF Platforms	piping. Work is being performed as a CCO by ERS. Construct platforms for access to maintain valves in the DMF			Ś	155,490	
.011301	5220		Gallery. Currently the valves are not accessible. Do work as a CCO to DMF 6A & 6B construction project (CIP #9222)	_		Ļ	155,450	
Constr	9228	Diesel Pump Upgrade	Relocate and replace diesel pumps and generator day tanks.	-	-	\$	879,178	486
Constr	9231	BioforceTech Dryer System	Work with BioforceTech for half-scale biosolids drying Facility.	-	-	\$	2,048,637	792
			SVCW to provide suitable site and utilities; Bioforce Tech to construct and operate. Tipping fee will be established based on this					
onct-	0000	Wotcido Doductort Decus	relationship.			ć	2 020 724	c
Constr	9806	Wetside Redundant Power	Addition of two standby power generators to PDP2 switchgear. In order to save monies, PDP2 was constructed to be completely	-	-	\$	2,830,731	6,475
			ready for new generators and was originally proposed to allow					
			existing generators to backfeed through existing primary					
			transformers T1 and T2. Concerns raised during the Rule 21 process					
			caused this plan to be superceded with standalone generators.			,	)	

#### SVCW Capital Improvement Program CIP Project Status - PLANNING & DESIGN

				2008 CIP	2013 CIP	Amended 2015 CIP	30-Jan-17 Actual Spent
Project	Project			(Original,	Update	Update	thru
Phase	No.	Project Name	Project Description/Status	2007 \$s)	(2010 \$s)	(2015 \$s)	December 2016
Planning	6004	Flow Equalization Facility	Build wet weather and diurnal storage facilities on plant property	\$8,981,300	\$28,600,000		594,260
Planning	6006	Conveyance System CEQA	Project Development, CEQA, and Planning for the Conveyance System Project Elements	-		\$ 5,100,580	3,741,561
Planning	6008	Tunnel and Gravity Pipeline	Installation of gravity pipeline, using tunneling construction methods for conveying wastewater to the plant.	-	63,190,000	\$ 220,007,111	9,165,826
Planning	6010	Force Main Conveyance System Program - General Support	Provides support and funding for general requirements of projects contained within the Conveyance System Program.	-	200,000	\$ 208,810	204,388
Planning	6013	Receiving Lift Station	Construct new pump station to lift flow out of the gravity pipeline and into headworks of the plant.	-	-	\$ 50,517,763	490,627
Planning	6014	Influent Connector Pipe	Install new pipeline that connects headworks process to current plant influent.	-	-	\$ 9,081,206	425,174
Planning	7004	Menlo Park Pump Station Rehabilitation	Replace Menlo Park Pump Station to accommodate future Conveyance System needs	5,454,200	10,900,000	\$ 23,847,974	123,607
Planning	7005	Redwood City Pump Station Rehabilitation	Replace Redwood City Pump Station to accommodate Conveyance System needs	23,400,000	25,140,000	\$ 30,216,325	2,959,998
Planning	7008		The existing pump station is at the end of its useful life. This project will replace the pump station equipment at the same location with details to be identified upon completion of the Conveyance System Program planning under Alternative 4BE. In the interim, until new pump station is constructed or deemed unnecessary, this project will fund necessary maintenance.	14,872,000	-	\$ 10,106,624	6,458
Planning	7009	Pump Stations Program - General Support	Provide general support to the Program Manager and in support of the overall pump station program.	-	400,000	\$ 426,505	162,104
Planning	7011	Belmont Force Main	Construct Pipeline between Belmont Pump Station and San Carlos Pump Station location.	-	22,022,000	\$ 3,308,933	296,339
Planning	9017	Plant #1 Water System Pipe Repair and Supply Upgrade	Rehabilitate potable water system: replace air gap tank or install backflow preventer, hydropneumatic tank, and pumps.	148,400	365,474	\$ 456,857	458,760
Planning	9033	Future Plant Electrical System Panel Replacement	Complete replacement and addition of additional panels and subpanels	5,748,600	5,570,322	\$ 6,357,363	4,010,534
Planning	9097	Plant Deck Re-coating	Add painted walkway and H20 rated hatch covers for pedestrian/cart access under the Plant Control building. Some hatches replaced under other CIP projects.	179,400	179,400	\$ 209,376	2,685
Planning	9102	Storm Drain System Improvements and Maintenance Wash Rack	Replace the last existing stormwater pump with a submersible pump and install 400' of buried 6" C900 PVC pipe and control valves to deliver storm water to the influent junction box or storm lagoon. Construct new wash rack to facilitate ability to clean equipment for maintenance overhauls. Includes upgraded electrical and control system. These two items occur in the same Plant area; stormwater PS work complete; wash rack not complete.	482,100	482,100	\$ 211,947	108,287
Planning	9103	Landscape Impoundment Improvements	Project is slated to provide improvements to the impoundment. Work in addition to what was originally intended may be done for future Plant process needs.	269,100	269,100	\$ 312,190	55,239
Planning	9105	Document Management System	Phase 2 of the IMMS; use for CIP information management.	1,995,500	1,995,500	\$ 2,318,059	326,974
Planning	9107	CCT Concrete and Steel Protective Coating Replacement	Recoat walls and Ceiling of CCT	4,807,400	4,901,400	\$ 5,719,970	87,284
Planning	9120	RAS Pump Suction Pipe Replacement	Slip-line the in-slab pipe. The high content of solids in sludge piping wears the pipe out over time; the RAS piping is thin due to the continued abrasion of the sludge transported through it.	511,800	311,800	\$ 362,864	32,962
Planning	9144	Solids Handling Program - General Support	Project provides support and funding for general requirements of projects contained within the Solids Handling Program through the life of the CIP.	-	100,000	\$ 137,681	240,574
Planning	9145	Plant Energy System Program - General Support	Provides support and funding for general requirements of projects contained within the Plant Energy System Program.	-	75,000	\$ 87,192	10,418
Planning	9160	WWTP Headworks and Screening Facility	Project provides for a new headworks and screening facility at the WWTP. Pump station predesign efforts will take headworks needs into account.	-	16,422,000	\$ 43,011,190	814,279
Planning	9169	Dewatering and Solids Handling Improvements - Phase II	Implement the dewatering improvements recommended by the Biosolids Master Plan, including replacing the existing centrifuge with a third rotary press. Timing is dependent upon several projects currently being considered (Food Waste, Bioforce Tech, future Plant loadings) and when Operations require redundancy.	-	1,123,200	\$ 1,443,215	219,271
Planning	9175	Security Program for New Conveyance System Pump Stations	Conduct an evaluation of the security and monitoring needs (required and optional) to be designed into the new conveyance system pump stations. The goal is to have a list of design criteria to give to the pump station design firm to ensure consistency of security equipment and controls. This project will investigate remote monitoring alternatives desired for operational needs. The project includes SVCW making decisions on security equipment, software and integration into the plant data system assuming this project will be conducted before the Plant Security Assessment and Plan project.	-	200,000	\$ 15,113	(0

#### SVCW Capital Improvement Program CIP Project Status - PLANNING & DESIGN

Planning 9176Plant Vulnerability Assessment and Security PlanConduct a Sit Security Plan based on pot the Pump Sta and overall n specific to thePlanning9189DMF Pump and Discharge Piping ReplacementReplace moto includes repla and the uppe included in C horizontal miPlanning9215Digester #1 RehabilitationRepair of coa includes repla and the uppe includes repla and the uppe includes repla and the uppePlanning9223Final Effluent Pump Replacement PlanningIncrease the discharge 80 Provide pipel to improve provide pipel to improve pPlanning9224FEP Connection to Chlorine Mix Box Provide pipel to improve pPlanning9222Long Term Strategic Recycled Water PlanningSVCW would term planning water supply is for staff tim plus work wid dollars are in treatment mic complianceDesign9186Thickening Improvements - Phase I ReplacementThe 2010 FFF blowers and are maintain added in 201Design9206Site Waste Piping and Pump ReplacementReplacedisct to significant Plan, DesignDesign9220Aeration Basin Venturi Removal Revoce a bo Plan, DesignPlan Aeration Basin Venturi Removal Plan, DesignDesign9220Food Waste: Receiving Station and Plan, DesignPlan Plan, DesignPartPoor Waste: Receiving Station and Plan, DesignPlan Plan, Design	1	2008 CIP (Original,	2013 CIP Update		ended 2015 CIP Update	30-Jan-1 Actual Sper thr
Planning9176Plant Vulnerability Assessment and Security PlanSecurity PlanPlanning9189DMF Pump and Discharge Piping ReplacementReplace moto includes repland and overall in specific to the replacementPlanning9215Digester #1 Rehabilitation Final Effluent Pump ReplacementRepair of coa includes repland and the uppe to horizontal mi to rovide pipelPlanning9223Final Effluent Pump Replacement PlanningIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box PlanningSVCW would term planning9232Long Term Strategic Recycled Water 	scription/Status	2007 \$s)	(2010 \$s)		(2015 \$s)	December 201
9176Plant Vulnerability Assessment and Security Planbased on pot night time str the Pump Str and overall in specific to the PlanningPlanning9189DMF Pump and Discharge Piping ReplacementReplace motoPlanning9215Digester #1 RehabilitationReplare moto nicludes repland and the uppe includes repland and the uppe includes repland and the uppePlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box PlanningProvide pipel to improve p SVCW would term planning9232Long Term Strategic Recycled Water PlanningSVCW would term planning9233Thickening Improvements - Phase I Replacement of Aeration BlowersReabilitato FF blowers and are maintain added in 201 replacementDesign9186Replacement of Aeration BlowersThe 2010 FF blowers and are maintain added in 201 replacementDesign9206Site Waste Piping and Pump ReplacementRenove a bo Plan, DesignDesign9220Aeration Basin Venturi Removal Renove a boPlan, Design Plan, Design	Site Vulnerability Security Assessment and prepare a	-	250,000	\$	66,986	-
9176Plant Vuinerability Assessment and Security Plannight time sta the Pump Sta and overall n specific to the performancePlanning9189DMF Pump and Discharge Piping ReplacementReplace moto includes replantPlanning9215Digester #1 RehabilitationRepair of coa includes replantPlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box Provide pipel to improve pProvide pipel to improve pPlanning9232Long Term Strategic Recycled Water PlanningSVCW would term planning water supply is for staff tim planning92329168Thickening Improvements - Phase I Replacement of Aeration BlowersRehabilitate The 2010 FFF blowers and are maintain added in 2010 replacementDesign9206Site Waste Piping and Pump ReplacementReplace discr to significant Plan, DesignDesign9220Aeration Basin Venturi Removal ReplacementRenove a bo Plan, DesignDesign9220Food Waste: Receiving Station and Plan, DesignPlan Replacement	an. This is to identify the security needs at the plant	1		}		
9176Security Plannight time state the Pump State and overall in specific to the specific to the ReplacementPlanning9189DMF Pump and Discharge Piping ReplacementReplace motoPlanning9215Digester #1 RehabilitationRepair of coa includes replicant of the included in CL horizontal miPlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box Provide pipelProvide pipel to improve pPlanning9222Long Term Strategic Recycled Water PlanningSVCW would term planning water supply is for staff tim plus work wid dollars are in treatment mic complianceSVCW would term planning water supply is for staff tim plus work wid dollars are in treatment mic complianceDesign9186Replacement of Aeration BlowersThe 2010 FFF blowers and are maintain added in 2010 replacementDesign9206Site Waste Piping and Pump ReplacementReplace discr to significant Plan, DesignDesign9220Aeration Basin Venturi Removal Revoce a bo Plan, DesignPlan, Design Plan, Design9206Site Waste Receiving Station and Plan, DesignPlan, Design Plan, Design9206Site Waste Receiving Station and Plan, DesignPlan, Design Plan, Design	otential for vandalism and the planned elimination of					
Planning9189DMF Pump and Discharge Piping ReplacementReplace motoPlanning9215Digester #1 RehabilitationRepair of coa includes repland and the uppe included in CU horizontal miPlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box PlanningProvide pipel to improve pPlanning9224FEP Connection to Chlorine Mix Box PlanningProvide pipel to improve pPlanning9232Long Term Strategic Recycled Water PlanningSVCW would term planning water supply is for staff tim plus work wit dollars are in treatment mic complianceDesign9168Thickening Improvements - Phase 1 ReplacementRehabilitation FF blowers and are maintain added in 201 replacementDesign9206Site Waste Piping and Pump ReplacementReplace discr to significant Plan, DesignDesign9220Aeration Basin Venturi Removal Replace mentRemove a bo Plan, DesignDesign9220Food Waste: Receiving Station and Plan, DesignPlan Replace	staffing. This plan will incorporate the decisions made in					
Planning9189DMF Pump and Discharge Piping ReplacementReplace motoPlanning9215Digester #1 RehabilitationReplace moto includes repla and the uppe included in C horizontal miPlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box Provide pipelProvide pipel to improve pPlanning9222FEP Connection to Chlorine Mix Box Provide pipelSVCW would term planning water supply is for staff tin plus work wid dollars are in treatment mic complianceDesign9168Thickening Improvements - Phase I ReplacementRehabilitate blowers and are maintain addel in 2010Design9206Site Waste Piping and Pump ReplacementReplaced sicr to significant DesignDesign9220Aeration Basin Venturi Removal Food Waste: Receiving Station and Waste from Station and Plan, DesignPlanning Plan	tation Security Program (CIP #9175) for software, I/C,					
Planning9189DMF Pump and Discharge Piping ReplacementReplace motoPlanning9215Digester #1 RehabilitationRepair of coa includes repland and the uppe included in CPlanning9213Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix Box PlanningProvide pipel to improve pPlanning9224FEP Connection to Chlorine Mix Box PlanningProvide pipel to improve pPlanning9232Long Term Strategic Recycled Water PlanningSVCW would term planning water supply is for staff tim planningDesign9168Thickening Improvements - Phase I Replacement of Aeration BlowersRehabilitate to significant replacementDesign9206Site Waste Piping and Pump ReplacementReplace discr to significant Plan, DesignDesign9220Aeration Basin Venturi Removal Replace Receiving Station and Plan, DesignPlan PlanDesign9220Food Waste: Receiving Station and Plan, DesignPlan Plan, Design	network controls. Additional hardware and equipment					
Replacement         Replace moto           Planning         9215         Digester #1 Rehabilitation         Repair of coa includes replacement           Planning         9215         Digester #1 Rehabilitation         and the uppe included in C           Planning         9223         Final Effluent Pump Replacement         Increase the discharge 80           Planning         9224         FEP Connection to Chlorine Mix Box         Provide pipel to improve p           Planning         9232         Long Term Strategic Recycled Water Planning         Pisor staff tin dollars are in treatment m. compliance           Design         9168         Thickening Improvements - Phase I         Rehabilitater blowers and are maintain added in 2010 replacement           Design         9206         Site Waste Piping and Pump Replacement         Replace discr to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design           Design         9220         Food Waste: Receiving Station and         Plan, Design	the plant will be evaluated.			<u> </u>		
Planning9215Digester #1 RehabilitationRepair of coa includes repl and the uppe included in C horizontal miPlanning9223Final Effluent Pump ReplacementIncrease the discharge 80Planning9224FEP Connection to Chlorine Mix BoxProvide pipel to improve pPlanning9222FEP Connection to Chlorine Mix BoxSVCW would term planning9232Long Term Strategic Recycled Water PlanningSVCW would term planning9232Long Term Strategic Recycled Water PlanningSVCW would term planningDesign9168Thickening Improvements - Phase I DesignThe 2010 FFF blowers and are maintain added in 2011Design9206Site Waste Piping and Pump ReplacementReplacement to significant plan, DesignRenove a bo Plan, DesignDesign9220Aeration Basin Venturi Removal Pool Waste: Receiving Station and Plan, DesignPlan, Design PlanPlan, Design Plan, Design	them and drives on DME Durnes	- }	858,000	Ş	1,793,236	2,236
9215     Digester #1 Rehabilitation     includes repl. and the uppe included in C       Planning     9223     Final Effluent Pump Replacement     Increase the discharge 80       Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     Long Term Strategic Recycled Water Planning     SVCW would term plannin water supply is for staff tin plus work wit dollars are in treatment m. compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate blowers and are maintain added in 2010 replacement       Design     9206     Site Waste Piping and Pump Replacement     Replaced ciscf to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and     Plan, Design	otors and drives on DMF Pumps.					
9215     Digester #1 Rehabilitation     includes repl. and the uppe included in CO       Planning     9223     Final Effluent Pump Replacement     Increase the discharge 80       Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     Long Term Strategic Recycled Water Planning     SVCW would term planning water supply is for staff tin plus work wit dollars are in treatment mic compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate blowers and are maintain added in 2010 replacement       Design     9206     Site Waste Piping and Pump Replacement     Replaced ciscf to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and     Plan, Design	patings and structural elements in Digester #1. Project		2,000,000	\$	2,161,884	32,341
Planning     9223     Final Effluent Pump Replacement     Increase the discharge 80       Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     Long Term Strategic Recycled Water Planning     SVCW would term plannin water supply       9232     Long Term Strategic Recycled Water Planning     Rehabilitate plus work wil dollars are in treatment m. compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate blowers and are maintain added in 201       Design     9206     Site Waste Piping and Pump Replacement     Replacement to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       9239     Food Waste: Receiving Station and Plan, Design     Plan	placement of the two mix nozzles, two wall penetrations		, ,			,
Planning     9223     Final Effluent Pump Replacement discharge 80     Increase the discharge 80       Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     FEP Connection to Chlorine Mix Box     SVCW would term planning water supply is for staff tim plus work wit dollars are in treatment m. compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FFF blowers and are maintain added in 201       Design     9206     Site Waste Piping and Pump Replacement     Replacement to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and Plan, Design     Plan, Design	per and lower vertical mix pipe manifold as previously					
Planning         9223         Final Effluent Pump Replacement discharge 80           Planning         9224         FEP Connection to Chlorine Mix Box Provide pipel to improve p           Planning         9224         FEP Connection to Chlorine Mix Box Provide pipel to improve p           Planning         9232         Long Term Strategic Recycled Water Planning         SVCW would term plannin water supply is for staff tin plus work wit dollars are in treatment mic compliance           Design         9168         Thickening Improvements - Phase I         Rehabilitate blowers and are maintain added in 201           Design         9186         Replacement of Aeration Blowers         The 2010 FFF blowers and are maintain added in 201           Design         9206         Site Waste Piping and Pump Replacement         Replace discr to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design' Waste From Station and	CIP #9170. Also include interior coating of 24-inch					
Planning     9224     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     FEP Connection to Chlorine Mix Box     Provide pipel to improve p       Planning     9232     Long Term Strategic Recycled Water Planning     SVCW would term plannin water supply is for staff tin plus work wit dollars are in treatment mic compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate blowers and are maintain added in 2010 replacement       Design     9206     Site Waste Piping and Pump Replacement     Replace discr to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and 9230     Plan, Design	mix piping as previously included in CIP #9171.					
Planning         9224         FEP Connection to Chlorine Mix Box         Provide pipel to improve p           Planning         9232         Long Term Strategic Recycled Water Planning         SVCW would term plannin water supply is for staff tin plus work wid dollars are in treatment m. compliance           Design         9168         Thickening Improvements - Phase I         Rehabilitate <sup>-</sup> Design         9186         Replacement of Aeration Blowers         The 2010 FFF blowers and are maintain added in 201           Design         9206         Site Waste Piping and Pump Replacement         Replace disch to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design           Design         9220         Food Waste: Receiving Station and 9220         Plan, Design	e capacity of the final effluent pumps to be able to	-	2,301,714	\$	2,484,794	97,693
Planning       to improve p         Planning       SVCW would term planning         9232       Long Term Strategic Recycled Water         Planning       plus work wit dollars are in treatment m. compliance         Design       9168         Thickening Improvements - Phase I       Rehabilitate         Design       9186         Replacement of Aeration Blowers       The 2010 FFF         blowers and are maintain added in 201       replacement         Design       9206       Site Waste Piping and Pump Replace disch to significant         Design       9220       Aeration Basin Venturi Removal       Remove a bo Plan, Design         Design       9220       Food Waste: Receiving Station and       Plan, Design						
Planning     SVCW would term planning water supply       9232     Long Term Strategic Recycled Water Planning     SVCW would term planning water supply       0esign     9168     Thickening Improvements - Phase I       Design     9186     Replacement of Aeration Blowers     The 2010 FF blowers and are maintain added in 201       Design     9206     Site Waste Piping and Pump Replacement     Replacement to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       0     9220     Food Waste: Receiving Station and Waste from 0     Plan, Design Plan, Design	eline to conect effluent pumps to the chlorine mix box	- }	200,000	\$	216,219	-
9232     Long Term Strategic Recycled Water Planning     term plannin, water supply is for staff tin plus work wit dollars are in treatment m. compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FFF blowers and are maintain added in 2010 replacement       Design     9206     Site Waste Piping and Pump Replacement     Replace discr to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design 9220       Pesign     9220     Food Waste: Receiving Station and 9220     Plan, Design Waste from 0	plant hydraulics and chlorine contact time			Į		
9232     Long Term Strategic Recycled Water Planning     water supply is for staff tin plus work wil dollars are in treatment mic compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate The 2010 FFF blowers and are maintain added in 2010       Design     9186     Replacement of Aeration Blowers     The 2010 FFF blowers and are maintain added in 2010       Design     9206     Site Waste Piping and Pump Replacement     Replace discr to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design Waste: Receiving Station and	ld begin collaboration with outside stakeholders for long	-	-	\$	1,032,137	134,399
9232     Long Term Strategic Recycled Water Planning     is for staff tin plus work wit dollars are in treatment m. compliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate <sup>-</sup> Design     9186     Replacement of Aeration Blowers     The 2010 FFF blowers and are maintain are del in 2011 replacement       Design     9206     Site Waste Piping and Pump Replacement     Replace disch to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       9239     Food Waste: Receiving Station and 9229     Plan, Design Aeration Basin Venturi Removal     Plan, Design Waste from O	ing of recycled water expansion as a drought proof					
9232     Planning     plus work with dollars are in treatment micrompliance       Design     9168     Thickening Improvements - Phase I     Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FFF       Design     9186     Replacement of Aeration Blowers     The 2010 FFF       Design     9206     Site Waste Piping and Pump     Replace disch to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       9239     Food Waste: Receiving Station and     Plan, Design	ly, explore IPR/DPR treatment requirements etc. Budget					
Design     9168     Thickening Improvements - Phase I     Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FFR       Design     9186     Replacement of Aeration Blowers     The 2010 FFR       Design     9206     Site Waste Piping and Pump     Replacement       Design     9220     Aeration Basin Venturi Removal     Remove a bo       Design     9220     Food Waste: Receiving Station and     Plan, Design	ime to attend meetings and begin long-term planning,					
Design     9168     Thickening Improvements - Phase I     Rehabilitate Rehabilitate       Design     9186     Replacement of Aeration Blowers     Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FF blowers and are maintain added in 2010       Design     9206     Site Waste Piping and Pump Replacement     Replace discr to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and Waste from C     Plan, Design	vith consultants on conceptual studies. No construction included. Large scale expansion of recycled water					
Design     9168     Thickening Improvements - Phase I     Rehabilitate       Design     9186     Replacement of Aeration Blowers     The 2010 FFF       blowers and in are maintain     added in 201     replacement       Design     9206     Site Waste Piping and Pump     Replace disch       Design     9220     Aeration Bain Venturi Removal     Remove a bo       Design     9220     Food Waste: Receiving Station and     Plan, Design	may offset dollars spend on future nutrient removal					
Design         9168         Thickening Improvements - Phase I         Rehabilitate           Design         9186         Replacement of Aeration Blowers         The 2010 FFF           blowers and in are maintain         added in 201         replacement           Design         9206         Site Waste Piping and Pump         Replace disch to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design           Design         9220         Food Waste: Receiving Station and         Plan, Design		}				
Design     9186     Replacement of Aeration Blowers     The 2010 FFF       blowers and are maintain added in 2010     Design     9206     Site Waste Piping and Pump Replacement     Replace disch to significant       Design     9220     Aeration Basin Venturi Removal     Remove a bo Plan, Design       Design     9220     Food Waste: Receiving Station and Waste from Station     Plan, Design Waste from Station and	e Thickeners 2 and 3		2,808,000	Ś	1,448,690	69,680
Design     9206     Site Waste Piping and Pump     Replacement       Design     9220     Aeration Basin Venturi Removal     Remove a bo       Design     9220     Food Waste: Receiving Station and     Plan, Design	FR preliminary design report evaluated the existing	-	4,290,000		4,750,568	31,302
Design     9206     Site Waste Piping and Pump     Replace discl replacement       Design     9220     Aeration Basin Venturi Removal     Remove a bo       Design     9220     Aeration Basin Venturi Removal     Plan, Design       9220     Food Waste: Receiving Station and 9229     Plan, Design     Plan, Design	d indicated an additional 10 years life remain if the units		,,	1	,	- ,
Design         9206         Site Waste Piping and Pump Replacement         Replace disch to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design           Design         9220         Food Waste: Receiving Station and Plan, Design         Plan, Design Waste from Comparison	ined well and ventilation is added to the room. Project	}				
Design         9206         Site Waste Piping and Pump Replacement         Replace disch to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo Plan, Design           929         Food Waste: Receiving Station and 9229         Plan, Design Waste from 0         Plan, Design Waste from 0	012 Update; use project as a placeholder for future					
Replacement         to significant           Design         9220         Aeration Basin Venturi Removal         Remove a bo           Design         9220         Food Waste: Receiving Station and         Plan, Design	nt and for change to mixers inside the ABs.					
Design         9220         Aeration Basin Venturi Removal         Remove a bo           Design         Food Waste: Receiving Station and         Plan, Design	charge piping and header and add one new pump due	- }	99,528	\$	109,901	9,005
Design 9229 Food Waste: Receiving Station and Waste from S	nt number of leaks in the system.					
9229 Food Waste: Receiving Station and Waste from S	pottleneck to allow peak flow of 80 mgd	-	1,150,857	\$	1,243,488	19,033
4779 Waste from S	n and Construct Receiving Station for Accepting Food	- }	-	\$	14,330,203	593,835
Digester Improvements	n SBWMA. Project would include new receiving station	}				
and intercon	nnection to Digesters	\$66,849,800	\$197,244,395	<u>}</u>	\$461,274,545	\$25,527,134

Note - \$0 values where project did not yet exist in the identified CIP, was deleted, or was merged with another project

#### SVCW Capital Improvement Program CIP Project Status - REMAINING

							30-Jan-1
Droject Dhace	Project	Restort Norma	Project Description (Status	2008 CIP (Original,	2013 CIP Update (2010 \$c)	Amended 2015 CIP Update (2015 \$c)	Actual Spe th
Project Phase Project On	No. 9071	Project Name Plant Gallery Floor and Wall Crack	Project Description/Status Seal gallery floors to prevent infiltration of GW. Unplug in-slab	2007 \$s) 250,000	(2010 \$s) 484,832	(2015 \$s) 561,364	December 20: 129,65
Hold Project On	9113	Sealing	drain pipes. IV or otherwise investigate various piping embedded in concrete	371,800	371,800	434,129	125,05
Hold			throughout the Plant	371,800			-
Project On Hold	9192		Expands the drying bed to the north with a new 3-acre bed.	-	1,656,000	35,102	102,60
Project On Hold	9400	Nutrient Removal	Placeholder for faciities required to remove nutrients (nitrogen and phosphorous) to meet future regulations.	-	-	103,636,229	649,49
Project Not Started	8045		This project is for the system integration of the pump stations' security systems into the WWTP control system. The project budget assumes 1) that all the security costs associated with specific pump station design and installation of equipment will be included in specific pump station rehabilitation projects and 2) the costs for security control equipment at the WWTP is included in new CIP #9177.	-	150,000	175,146	-
Project Not Started	9041	Underground Fuel Tank Replacement	Future Underground Storage Tank regulations may require removal of this tank. Remove 15,000 gallon underground fuel (diesel) tank and replace with a tank that meets regulatory requirements when necessary. Electrical costs include conduit and wiring for new underground tank leak detection equipment necessitated by moving the tank.	458,000	458,000	534,779	-
Project Not Started	9084		Install lateral bracing on the DMF 42" effluent piping. (Seismic Improvement Program No. P14).	167,300	167,300	195,346	-
Project Not Started	9093	Headworks Odor Control	Cover grating and open areas, treat odorous air.	929,500	929,500	1,085,321	-
Project Not	9094		The butterfly valve is worn and no longer working as it is intended.	28,300	28,300	-	-
Started Project Not Started	9171		The Horizontal 24" Mix Pipe Lines were inspected in 2009 and minimial reduction in pipe thickness was noted and the pipes were placed back into service. It was noted that the coating was peeling off in places so this project will inspect the pipes next time the digesters are taken down for maintenance and replace interior coating and corroded piping as needed. Digester 2 piping replaced under CIP #9095. D1 piping to be included with CIP #9215, Digester 1 Rehabilitation. D3 piping remains to be replaced.	-	100,000	116,764	
Project Not Started	9172	Thickening Improvements - Phase II	Gravity Belt Thickeners were installed under CIP #8018, Thickening Automation in 2014-2015. If and when flows and loadings increase, Phase II will install one or more GBTs. This is a project placeholder and not currently funded.	-	2,808,000	-	-
Project Not Started	9173	Dewatering and Solids Handling Improvements - Phase III	Implement the dewatering improvements recommended by the Biosolids Master Plan, including installation of a fourth rotary press.	-	1,123,200	1,311,493	-
Project Not Started	9174	Upgrades	The existing supernatant piping only allows for supernating to Digester 3 from Digesters 1 and 2 and there is no passive overflow system at any of the Digesters. This project will investigate the future need for additional supernatant piping and alternative destinations for receiving supernantant flow. The project cost assume \$50,000 for the evaluation and a placeholder of \$250,000 for implementation.	-	300,000	350,292	-
Project Not Started	9185	Water Cannons at Aeration Basins	Provide 3W piping and appurtenances required to supply high volume, high pressure water for aeration basin wash-down.	-	107,250	118,783	-
Project Not Started	9187	Secondary Clarifier Weir Washers	Install weir washers on secondary clarifier weirs to facilitate routine daily washing and in support of eventual single shift operations and maintenance.	-	248,820	275,576	-
Project Not Started	9196		Develop Electronic O&M manuals to replace existing paper manuals. Extent of e-manuals will be determined to coincide with full plant automation requirements.	-	1,000,000	1,036,600	-
Project Not Started	9197	In-Plant Recycled Water System Expansion	Expand the recycled water pipeline installed under CIP 9018 to supply cooling water to the new emergency generators in the SHB and the new chillers in the Thickener gallery.	-	231,660	256,570	-
Project Not Started	9212	*	Install security lift arm gates to block access to cars from areas of the plant past the parking lot.	-	80,000	86,488	-
Project Not Started	9225	DCP2 Processor Upgrade	DCP2 Control Logix Upgrade (Dual Chassis) for central data collection and Critical Alert Alarm (CAA) system monitoring and management. The current system is beyond it's useful life and has no redundancy.	-	-	107,599	-
Project Not Started	9233	Strategic Technology Testing Assistance	Set aside a small project budget to assist with future possible pilot studies. Do not fund project at this time.	-	-	-	-
Project Not Started	9235	Digester Gas Storage	Construct storage for digester gas gas equalization in support of optimizing the cogeneration engine operation/electricity output. Gas production expected to rise with introduction of co-digestion materials (food waste and FOG)	-	-	1,451,240	-
Project Merged	6005	or Parallel	Project redefined into pipeline segments; retire this CIP #. Repair and Replacement work on the SBSA Force Main as joints fail (start to leak). The force main has approximately 4,000 single "O" ring bell and spigot joints while the entire pipe rests in bay mud and moves constantly.	125,053,500	2,786,934	3,031,955	3,031,95

## SVCW Capital Improvement Program CIP Project Status - REMAINING

						Amended 2015	
				2008 CIP	2013 CIP	CIP	Actual Spen
	Project			(Original,	Update	Update	thru
Project Phase	No.	Project Name	Project Description/Status	2007 \$s)	(2010 \$s)	(2015 \$s)	December 2016
Project	8014	Primary Sludge Piping System Valve	Install valve actuators and new valves as needed to facilitate	281,700	-		-
Merged		Automation	automation of the primary sludge system. Delete project and				
. 0			merge with 8007.				
Project	8024	Thickening Pump #1-6 Remote on /	Combined with Thickener Automation (CIP 8018) via SPA project.	360,600	10,978	26,869	0
Merged		off / speed controls	Includes effort for motor replacement.			,	
Project	8030	Automation: Instrumentation &	Provides support and funding for general requirements of projects	-	670,509	433,239	452,062
Merged		SCADA Program - General Support	contained within the Energy and Automation Program. Do not fund				
			project in 2015 Update				
Project	9108	Scum Flowmeter	Combined with Thickener Automation (CIP 8018).	29,200	-	-	-
Merged							
Project	9165	Seismic Upgrade of Digester Mix	Do work under SPA project, CIP # 8021.	-	111,500	-	-
Merged		Room and Boiler Room Piping	bo work under SFA project, CIF # 8021.				
Admin	9078	10-Yr CIP Program Annual Updates	Update the 10-Year CIP and costs annually or as needed to ensure	180,000	300,000	348,705	61,155
			that projects are scheduled and funds are available each year				
Admin	9130	Capital Improvement Engineering	Funds staff required to coordinate and implement the Capital	7,000,000	7,000,000	13,349,767	300,686
			Improvement Program.				
Admin	9158	CIP Financial Assistance	State Water Resources Control Board SRF construction loan	-	1,000,000	1,165,569	81,054
			assistance. Funding received for Admin Building and WWTP				
			Improvements and planning loan for Conveyance System. Future				
			applications will be submitted for Conveyance System and Future				
			Treatment Plant projects. Budget includes ongoing compliance				
			with loan requirements.				
Admin 91	9159	OCIP Funding	Repository for funding the OCIP and payment to Aon for	-	6,000,000	6,217,403	79,801
			management of the program for first five years. New OCIP program				
			being evaluated in 2015.				
Admin	9184	LOC Funding - Phase I	Fees for setting up and managing LOC with Bank of the West.	-	105,431	11,124	(0)
			Process complete.				
Admin	9209	LOC Funding - Phase II	Initial Set-up and Annual fee for LOC with Wells Fargo as of 2015.	-	120,000	129,731	-
OTALS - REM	AINING P	ROJECTS		\$135,109,900	\$28,350,014	\$136,483,183	\$4,888,461

TOTALS - REMAINING PROJECTS Note - \$0 values where project did not yet exist in the identified CIP, was deleted, or was merged with another project

## Commissioners' Requested Action Items Last Update: 1/27/2017

Commission Meeting Date	Action Item		Requested or Estimated Date for	Status			Date of Completion	Notes
			Completion	Ongoing	In Progress	Complete		
	1							
1/12/2017	1	CalPERS actions on performance pay	NA		1			Inform all persons who received the CalPers letters apprised of what actions the Commission is taking on their behalf
	2	SVCW Financial Reports	2/9/2017		1		Implemented	Send warrant registers for review by Commissioners via email prior to Commission meeting they will approve them at. Do not send hard copies with agenda packet.
	3	SRF Funding	<1/30/2017			1	1/19/2017	Send the letter from Commission to state legislatures for SRF funding prior to Jan 30th meeting w/SWRCB
	4	Long Term Financial Plan	2/9/2017		1			Add statement to LRFP re: debt and generational equity; a statement re: debt interest due to not having \$ for pay-as- you-go.
	5	CIP Funding	Spring 2017		1			Present a recommendation to Commission re: timing for bond issuance.
				[	[			
12/8/2016	1	Prepare discussion re: financing the CIP (bonds/no bonds)	1/12/2017	l	l	1	1/12/2017	Preliminary discussion with LRFP presentation in January
11/10/2016	1	Discuss 2017 Commission Meeting Dates	12/8/2016			1	12/9/2016	Commissioners confirmed meeting dates.
	2	Conveyance System DEIR	>12/8/2016		1			Presentation provided at December Commission meeting; no additional meeting needed until FEIR. Staff to report at each Commission meeting comments received during the 45-day comment period. Ensure drafters of EIR are present at FEIR meeting in April.
	3	Investment Report	12/8/2016			1	12/8/2016	Ensure numbers in report tie in to front page numbers.
10/13/2016	1	IT System Shut-down of October 17th	10/14/2016			1	10/14/2016	Notify public of planned IT shutdown via website.
10/13/2016	2	Conveyance System DEIR	>12/8/2016			✓ ✓	10/14/2016	See discussion under 11/10/2016 above.
	3	SRF Funding Availability	January or February			<i>v</i>	1/19/2017	Letter to State legistators and SWRCB advocating CA issuing more bonds to fund the SRF program drafted and presented to Commission. Letter sent mid-January.
	4	Conveyance System Commission sub-committee	NA			~	11/7/2016	Subcommittee (Lieberman and Moritz) met on Nov 7 to discuss conveyance system progress.
	5	Greendale property construction progress	6/30/2017		1			Report on construction progress from Manager.
9/8/2016	1	Job Classification and Total Compensation Study	1/31/2017		1			Upon FY16/17, kickoff meeting occurred and work is proceeding. Report expected to be complete early 2017.
	2	Control Building HVAC System	NA		1			Seek damages recovery from Architect of Record
	3	JPA re-write: prepare RFP and concurrently reach out to Legal Counsels of each member agency.	NA		1			Staff is working with legal counsel to identify base issues for consideration and hiring of special counsel to facilitate the re- write.

AGENDA ITEM 5E FEBRUARY 9, 2017

#### **Commissioners' Requested Action Items**

Last Update: 1/27/2017

Commission Meeting Date		Action Item	Requested or Estimated Date for		Status		Date of Completion	Notes
			Completion	Ongoing	soing Progress Complete			
	4	Connection Fees	NA		1			Additional plant capacity evaluation is underway to ensure proper flow numbers are used in the calculations.
8/18/2016	1	SCBS Ratify Emergency Condition - Valve Replacement	NA			1	12/8/2016	Reported in December the emergency condition has been alleviated.
7/14/2016		No new items at this meeting						
6/9/2016	1	Contract Change Orders	NA	1			8/18/2016	When there is a change in contract amount, note % increase over original contract amounts; began at August meeting.
	2	MOU Negotiations	NA		1		NA	When MOU negotiations occur, present status updates to the Commission - anticipated in late 2017/early 2018.
5/12/2016	1	Consider a Press Release for APWA award received	NA			1		Determined to not address at this time.
	2	Cost Delta for SRF vs no SRF	8/18/2016			1	7/14/2016	Part of Risk Assessment analysis. Will be an ongoing report at future Commission meetings
	3	Vendor Gifts	10/13/2016			1	11/10/2016	Draft policy provided at October meeting. Action item to be added to November meeting.
4/14/2016	1	Change to descriptive minutes from Commission meetings	5/5/2016			1	5/5/2106	Descriptive minutes began for April meeting and was provided with May meeting agenda; minutes approved in May.
	2	Present increase to reserves by \$1M	8/18/2016			1		Determined by SVCW CFO to not proceed with increase at this time.
	3	Perform risk analysis by independent consultant for conveyance system	7/14/2016			1	7/14/2016	PO approved for Exponent to complete risk assessment at May meeting. Results reported at July meeting.
	4	Cogeneration Gas Conditioning	NA			1		Cogen engines back online as of late April 2016.
3/10/2016	1	Conveyance System Program - Report out on public comments received through Public Scoping period	4/14/2016			1	4/7/2016	Summary complete and included as Item 8B on April 14, 2016 Commission meeting
	2	Review policy re: gifts received from vendors	5/12/2016			1	5/12/2016	Item discussed at May meeting; see notes above.
2/11/2016	1	File Retention Policy change	3/10/2016			1	3/3/2016	Change retention period for Comission meeting recordings to match minutes
	2	Engineering Monthly Report changes	2 months+/-			1	3/10/2016	Add project budgets and actual spend on completed as well as active projects
	3	BioForce Tech project status	3/10/2016			1	3/10/2016	Provide status update to Bob Grassilli (can be separate and direct memo)
	4	FOG Station	3/10/2016			1	3/10/2016	Provide information on grease receiving rates within the Bay Area (memo to the Commission; no action)

### MINUTES OF SILICON VALLEY CLEAN WATER SPECIAL MEETING – JANUARY 12, 2017

### <u>ITEM 1</u>

CALL TO ORDER

The meeting was called to order at 8:02 a.m.

## <u>ITEM 2</u>

ROLL CALL - Commissioners Duly Appointed By Each Agency Mayor John Seybert, Redwood City – Chair Council Member Warren Lieberman, PhD., Belmont– Vice Chair Board President Edward Moritz, West Bay Sanitary District - Member Mayor Robert Grassilli, San Carlos – Secretary

Staff, Consultants and Visitors Present

Christine C. Fitzgerald, SVCW Legal Counsel Daniel T. Child, SVCW Manager Teresa Herrera, SVCW Assistant Manager/Authority Engineer Monte Hamamoto, SVCW Wastewater Superintendent Matt Anderson, SVCW Chief Financial Officer Linda Bruemmer, SVCW Administrative Services Director Jennifer Flick, SVCW HR Manager Kim Hackett, SVCW Engineering Director Bill Brvan, SVCW Senior Engineer Bruce Burnworth, SVCW Senior Engineer Arvind Akela, SVCW Senior Engineer Cindy Hui, SVCW Financial Analyst Jeff Hubbard, SVCW CIP Manager Ilana Schmidt, SVCW Administrative Assistant Jay Walter, City of San Carlos George Otte, West Bay Sanitary District Bill Tanner. Tanner Pacific. Inc. Charlie Joyce, Brown and Caldwell Carolyne Kerans, City of Redwood City Ken Kaufman, SVCW Retiree Kathy Suter, SVCW Retiree Fred Gerke, SVCW Retiree Mike Fazio, SVCW Retiree

ITEM 3 PLEDGE OF ALLEGIANCE

Mr. Lieberman led those attending the meeting in the recital of the Pledge of Allegiance.

## ITEM 4 PUBLIC COMMENT

Mr. Seybert began the meeting by stating that there were some members of the public who wished to address the Commission and reminded them they were allowed approximately 3 minutes for their individual statements.

Mr. Ken Kaufman began by stating that he has lived in the SVCW service area for 29 years. He was an employee of SVCW for over 30 years while holding several positions and was a management employee most of that time. He then gave a brief history of the Performance Pay Program for management employees explaining that Performance Pay was developed in 2002 to address the concerns of one or more Commissioners.

According to Mr. Kaufman, the Commission at the time was concerned that management employees would reach the top of their salary range, stop performing at a high level and collect the COLA increase each year. The Commission wanted a change in salary structure to provide monetary incentive to encourage management employees to perform at a high level. The former Authority Manager, with Commission approval, created the program called Performance Pay. Management employees were told that Performance Pay was CalPERS eligible and would count toward their pension calculations, and they have paid CalPERS contribution on it when they received it. It was understood that it was a plan to keep the management staff achieving goals and working at maximum levels.

The management staff felt that the Commission had always been fair and reasonable in their approach to the Management Group so the new salary structure was accepted. In 2003, the first Performance payment appeared in their paychecks. Payroll deducted seven percent (7%) of the Performance Pay to make the pension contribution to CalPERS. The Agency also contributed a percentage to CalPERS. These pension contributions have continued through the years.

Additionally, Mr. Kaufman stated that for the next ten (10) years, he made retirement decisions assuming his total salary was "PERSable." That was the term that was used. Therefore, he contributed less to Supplemental Retirement Plans such as IRA's and the Agency's 457 Plan. While his decision to retire was complex, his foremost concern was whether his pension was adequate to pay his expenses throughout his remaining lifetime. He didn't want to outlive his resources. At the end of 2012, he believed that his pension would be sufficient and he chose to retire.

Two weeks ago, he received a letter from CalPERS stating that Performance Plan income would be excluded from pension calculations. Twelve (12) other retirees received the same letter. While he is still sorting out the details, he can see that this will have significant impact in his life. This is a huge issue for him and the other retirees. Many of the retirees would have delayed retirement a few years and approached their financial planning differently.

Since the Commission will be addressing this topic later this morning in Closed Session. Mr. Kaufman hoped that the Commission would take time to view the situation from the retirees' perspective and find a way to treat them with the same fair and reasonable approach they have in the past.

Mr. Seybert next recognized Mr. Fred Gerke.

Mr. Gerke stated he did not have a specific statement to make, but rather attended the meeting to show support for his fellow retirees. In addition, he thanked the Commission for making time to listen to the retirees and hopes the issue will be settled timely and in a fair manner.

Mrs. Kathy Suter commented that it was a shock to her to receive the letter from CalPERS, especially right before Christmas and that the tone of the letter was offensive to her. She has been retired for eight (8) years and is experiencing other strains on her financial resources. In addition, she wanted the Commission to know that she gave her all to her job and she really enjoyed her time working at SVCW.

Mr. Seybert then indicated that he wanted to make a couple of general comments about this subject. First, he apologized on behalf of CalPERS and indicated that he had dealt with CalPERS in the past. In addition, he stated that this situation has nothing to do with SVCW's gratefulness towards those who had worked for the Authority and thanked all the retirees for their service and stated that the Commission will do everything in their power to correct this situation.

Mr. Seybert asked Mrs. Bruemmer to act as the point person for communications between the Commission and the retirees concerning this issue.

Mr. Seybert wanted to know, in view of the letter, if the payments from CalPERS will be reduced immediately because of this letter or if there is a way to "stay" their actions. Ms. Fitzgerald told the Commissioners that she will research the question and provide them a legal opinion letter prior to the next Commission Meeting.

Mr. Mike Fazio, another retired SVCW employee in attendance, responded that payments have not gone down yet, but the intent of the letter was to do so and that there was also the possibility that CalPERS would want to be reimbursed for payments already made.

## ITEM 5A SAFETY MOMENT

Mr. Child presented the Safety Moment on ATM card safety. He recommended using ATM's during daylight hours and when using one at night, make sure the area is well lit.

### ITEM 5B MANAGER'S REPORT

Mr. Child began by stating that SVCW is holding its Annual Employee Recognition Event and extended an invitation to the Commissioners, including soon to be Commissioner George Otte, to attend the brunch event at 10:00 a.m. on February 1<sup>st</sup>.

Last month Mr. Child mentioned that the Commission might need a Closed Session to discuss the Bay Area Air Quality Management District concerning permit issues. During the last couple of weeks, SVCW has been negotiating with them and may be able to avoid a legal struggle.

The Commission also asked about the status of the CEQA comments. The CEQA period ends on January 13<sup>th</sup> at 5:00 p.m. To-date, SVCW received three (3) email comments and one (1) letter (from the Audubon Society).

Mr. Child continued his report by requesting that the October 12, 2017, Commission meeting be moved to October 5, 2017. The Commission agreed to change the meeting date to October 5, 2017.

The final item of the Manager's Report was a handout showing a recap of storm events for the last week. SVCW did extremely well. The day before yesterday, January 10, 2017, SVCW had the highest total daily flow ever recorded - 50.7 million gallons (MGD) of water was treated by the treatment plant, which is rated for 29 million gallons. Peak flow reached 89.3 MGD, plus just over 10 MGD was diverted to the FEF, totaling a peak recorded flow of approximately 100 MGD in the system. This confirms the anticipated volume being used for the CIP, as 107 Million gallons is the expected peak flow over the twenty (20) year study period. The fact that the Agency was able to document and manage 100 MGD in the system is not only a high achievement for the Operations and Maintenance staff, but also provides significant data for the Engineering Group to use in the design of the upcoming CIP work.

The recap also indicates SVCW's flow meters were maxed out. The meters literally hit their top and it is not only possible, but highly likely, that more water was actually in the system. Since the meters were topped out, there is no way to measure the exact amount. Mr. Child also pointed out that every member entity significantly exceeded their JPA flow limits at one time or the other during the storms, but SVCW staff did everything in their power to keep the system running and the water in the pipes!

These were very challenging days, but the good news is due to the automation work being done at the Plant, there was a decrease in the amount of staff needed. Rather than seven (7) or more people working during a storm event in the Operations Group, there were only two (2). Operators were able to sit at the Control Panel and open and close valves. In prior years, an Operator would have to send someone out to operate a valve or make a change. It was the same situation at the Pump Stations. Typically Redwood City Pump Station would hit a 150 inch wet well level. Due to a Redwood City pipe project crossing Highway 101, there is a need to keep the water level under 125 inches. During these storm events, the maximum measured level was only 77 inches.

The Plant experienced some challenges because of a power loss right in the middle of the storm and when the power came back on, it zapped one of the control units. This created a situation that if the power had gone out again, there would not of been access to back-up power. SVCW Electricians and instrumentation personnel responded immediately and within forty-five (45) minutes they had the situation corrected. Mr. Child stated that he wanted to publicly thank the entire SVCW staff for what was an incredible effort and show

of dedication to get through these storms, treat this amount of water and not violate any discharge requirements.

Mr. Child concluded his report by saying that the handout would be distributed to all the Technical Committee members as well.

Mr. Lieberman asked if when power is lost does that mean equipment had to be manually operated. Mr. Child responded that when power is lost, it takes a couple of minutes but everything is supposed to be automatic. When the power goes off, the standby emergency generators come on. It takes a couple of minutes for the generators to kick in and everything to transfer over. If for some reason, some equipment doesn't start back up, an Operator will physically go out and verify the situation and if appropriate, manually start the piece of equipment. This time, what caused an unusual situation is that when the PG&E power came back on, a control module on one of the standby generators decided to revert back to the factory settings rather than to the previously configured SVCW specific settings.

Mr. Lieberman asked if the power had gone out again before staff fixed that, what would have happened. Mr. Child stated that water from the Pump Stations would continue to come into the Plant and depending on the flow rate, all the tanks (before they hit the pumps) would fill up and eventually sewage would start spilling out of the top of the tanks.

Mr. Lieberman then asked if power was lost again and should this switch go out, would staff be able to make a quicker response. Mr. Child informed him that as of yesterday, 2 of the 3 stand-by emergency generators could be manually started. Unfortunately, when it comes to automation bugs, one doesn't know they exist until they happen and he could not honestly answer that question as until it happens, you just really do not know.

Mr. Lieberman commented that now, at least, staff has learned something from this situation. Mr. Child responded that with lessons learned, Wastewater Superintendent Monte Hamamoto, Consultants Chuck Fenton and Kip Edgley, along with SVCW's electrical and instrumentation staff are evaluating what happened, checking systems and putting in improvements to reduce the risk of it happening again.

Mr. Lieberman asked how Mr. Child would categorize this storm event. Would it be something like 1 out of a 10 year event, 1 out of 3 or 1 out of 50 year event and how intense was the amount of rainfall that was received? Mr. Child responded that the previous record was 48.5 million gallons and that occurred in 1996, so roughly twenty (20) years ago, with some other years pushing up closely against them. It was very intense and rainfall reports in the service area varied between 3 inches in San Carlos and Belmont to over 4.75 inches in Menlo Park.

Mr. Lieberman commented that he felt the main message, relative to past occurrences, was that the amount of rainfall that occurred on this occasion was probably as much as or more than occurred on other occasions.

Mr. Child concurred that it was definitely a big storm, but the real secret which he had to explain to some employees, was that with a big rainstorm at the beginning of the rainy season, it just runs off or starts to put moisture back in the ground, but right now the ground

is saturated, so when an inch of water falls on the top of the ground, it pushes an inch of water out the bottom and that water will find a place to go. There have been so many really "perfect" storms this year that have saturated the ground and when a big storm like this hits, it pushes all that water into the systems.

In summary, Mr. Lieberman stated that this storm pushed the system, maybe not to its absolute limits, and impressed SVCW got through it. Mr. Child concurred, and added pushing 89 million gallons through the Plant, is a truly incredible feat. The highest number known before was just over 70 million gallons and again praised the SVCW staff for their efforts.

Mr. Moritz asked about the battery packs (Uninterruptible Power Supplies) that support the automation system and networks computers. He noted they were still being worked on as part of an Emergency Declaration. Did the system work as needed?

Mr. Child responded that they actually worked well. There were a few glitches but for the most part because of the battery back-ups, the SCADA System stayed up the whole time. In addition SVCW has an Engineer on staff whose job is to basically focus on energy issues. SVCW is developing more energy alternatives to keep costs down and in addition, give even more dependable power.

ITEM 5C FINANCIAL REPORTS There were no questions on the Financial Reports.

## ITEM 6 MATTERS OF COMMISSION MEMBER'S INTEREST

Commissioner Moritz announced that starting in February, Mr. George S. Otte will take his place on the Commission and Mr. Moritz will serve as Mr. Otte's alternate. Since Mr. Otte will be on vacation in Europe on October 5th, Mr. Moritz will be filling in for him at that meeting.

Mr. Moritz stated that he felt compelled to inform the Commission that West Bay has had a project going for the past two (2) years to build a recycled water treatment facility and the first user of that recycled water will be the Sharon Heights Golf Club.

In addition, West Bay has plans to commence a study to do a similar project at their old treatment plant site that is now being used as the Flow Equalization Facility by SVCW. The current project is their first effort and if successful, they are planning to do the second project in what West Bay calls the "Facebook Area". This will be in the area that is their industrial area and relates to high users.

He continued by stating that West Bay has had an environmental report out and they thought their closure date had past. LAFCO had reopened the environmental report and a letter was received from Silicon Valley Clean Water questioning a number of items on the report which was a concern for West Bay's Board.

He continued by pointing out the problem with using letters as opposed to phone calls. Rather than calling up and asking questions, West Bay had to respond to each one of those issues. The West Bay Board's consensus was that the questions were poorly thought out and could have easily been taken care of. In this situation a consultant was hired and money was spent to address the issues. On top of that, SVCW's letter was then sent, by LAFCO, to Portola Valley which is one of the sources of water that West Bay is going to use.

Because of the letter, the Portola Valley Manager wanted to know about their rights to the water. That resulted in their lawyer calling West Bay's lawyer and spending an hour of time on the phone. At the end of that conversation, the Portola Valley Manager, the lawyers and the city official in charge of facilities were all fine with the project. However, there are other items that will cost money. Mr. Moritz implored SVCW, that in the future, please pick up the phone. Member agencies are partners and other projects are going to come along. If questions arise or there is no response, Mr. Moritz asked that SVCW please let him or Mr. Otte know about it.

Mr. Child responded by saying that there was nothing in the letter not previously discussed with Mr. Scott, West Bay's District Manager. In addition, this all started because LAFCO contacted him and asked if SVCW was okay with the project. SVCW was not contacted as a "Responsible Agency" as part of West Bay's original CEQA process and didn't want to miss the opportunity a second time to note items that affected SVCW in the project. Mr. Child did not feel that this would have come as a surprise to Mr. Scott, however, looking back, Mr. Child now realizes Mr. Scott should have been "copied" on the letter and apologized for the omission.

When SVCW received a call from Portola Valley, staff advised them that they should have their attorney get with West Bay's attorney because SVCW should not be in the middle of this. Mr. Child didn't feel there was anything in the letter that would or should stop or hurt the project, but it is going to protect West Bay in the long run because those questions will now be answered, where they were not in the past. Mr. Child again apologized for not notifying Mr. Scott and indicated it would not happen again.

Mr. Seybert added that a response in an official CEQA process should always be documented in writing, not a phone call. If he found out that an official CEQA response had been given by means of a phone call, he would have been upset because fifteen years from now, an agency would want a written record of the CEQA questions and responses.

## <u>ITEM 7</u>

## CONSIDERATION OF MOTION APPROVING CONSENT CALENDAR

Commissioner Grassilli asked about the new format for approving Warrant Registers under the Consent Calendar.

Mr. Child pointed out that it has always bothered him that the Commission did not officially approve SVCW expenditures and this is a way the Commission would have the opportunity to review and approve the checks written for purchases made by SVCW.

After considerable discussion, the Commission agreed, that in the future, SVCW staff will email the Warrant Registers to the Commissioners for review when they are produced, and approval will be an item on the Consent Calendar of the following meeting agenda for Commission approval.

As an aside, Mr. Moritz stated he is delighted that SVCW is processing recycled water especially during California's current drought situation.

## Motion/Second: Mr. Moritz / Mr. Grassilli

The motion carried by unanimous roll call vote.

### <u>ITEM 8A</u>

CONSIDERATION OF RESOLUTION AWARDING CONTRACT DOCUMENTS AND AUTHORIZING PURCHASE OF VALVES AND EXPANSION JOINTS FOR THE PUMP STATION VALVE REPLACEMENT PROJECT – CAPITAL PROJECTS #262 AND #263

Ms. Herrera explained that this item was for procuring valves and expansion joints for two (2) pump stations – Menlo Park and Redwood City. She then showed pictures of what the valves and expansion joints look like.

The first picture was from the Menlo Park Pump Station showing where SVCW is replacing seventeen (17) valves and five (5) expansion joints. At the Redwood City Pump Station, twelve (12) valves and five (5) expansion joints are being replaced. Of the total cost of \$391,000.00, approximately sixty-five percent (65%) of the cost is for the equipment at Menlo Park. This is a revenue funded capital project (Fund 14) with a budget of \$927,000.00 for these two pump stations. The remaining budget will be used to cover the cost of the installation contract. The installation contract will be presented for approval at the April Commission meeting. Next Fiscal Year's budget will include funding for replacement of valves and expansion joints at both the San Carlos and Belmont Pump stations.

Mr. Grassilli asked if the valves would be replaced every twenty-five to thirty years.

Ms. Herrera responded that the valves typically have a twenty (20) year lifespan, though in this case, they will no longer be needed when the Pump Stations are replaced in about eight (8) years.

### Motion/Second: Mr. Grassilli / Mr. Lieberman

Move adoption of RESOLUTION APPROVING CONTRACT DOCUMENTS AND PURCHASE OF VALVES AND EXPANSION JOINTS FOR THE PUMP STATION VALVE REPLACEMENT PROJECT (CAPITAL PROJECTS #262 AND #263), DECLARING AND ACCEPTING BID OF LOWEST RESPONSIBLE BIDDER FOR SAID MATERIALS, REJECTING ALL OTHER BIDS, AUTHORIZING AND DIRECTING EXECUTION OF CONTRACT FOR PURCHASE OF SAID MATERIALS AND DIRECTING RETURN OF BID SECURITY UPON EXECUTION OF CONTRACT BY LOWEST RESPONSIBLE BIDDER – (\$391,993.63) – ALL WEST EQUIPMENT, DBA FRANK OLSEN COMPANY

The resolution carried by unanimous roll call vote. <u>ITEM 8B</u> CONSIDERATION OF MOTIONS APPROVING TASK ORDER AMENDMENTS FOR THE CONVEYANCE SYSTEM PROGRAM

Ms. Herrera began the discussion by stating that an informational report on the Conveyance System was given at last month's meeting and the Commission provided direction to staff to begin the process of utilizing an alternative construction delivery method (such as Progressive Design/Build) for construction of appropriate projects related to the Capital Improvement Program. Since then, staff members have met with two consultants to negotiate the Scope of Work to develop Requests for Qualifications (RFQ) and Requests for Proposals (RFP) for firms capable of meeting the Authority's alternative construction delivery method goals. These two firms are anticipated to act as SVCW's Owner's Engineering Advisors (OEA) for various projects. The initial role of an OEA is to assist SVCW staff in the development and evaluation of the RFQ and RFP process.

The Task Order Motions before the Commission are for Kennedy/Jenks for the gravity pipeline related projects, including the shaft and tunnel, and for Brown and Caldwell for the Receiving Lift Station, headworks and influent connector pipeline related projects.

In the next month or two, SVCW staff anticipates bringing Task Orders to the Commission for Freyer & Laureta for other projects related to the construction of the conveyance system. In the past CDM Smith did planning work for SVCW on the headworks and the influent connector pipeline, but they have chosen to propose as a design/build entity and, therefore, their work on these projects as a design firm or as an OEA has stopped to avoid any potential conflict of interest related to the work. CDM Smith has both an engineering arm and a construction arm that have considerable experience in design/build projects and because of this they have chosen to participate as a potential design/build firm in the future.

For the record, Mr. Grassilli stated that the reason this is being done, using the OEA firms, is because the program is so large. It is not done for every project. Though it seems like an additional cost, the support and extra money is needed because of the size and scope of the conveyance system program in whole.

Mr. Child agreed and added that the reason for these Task Orders is because SVCW is embarking on its first, and also extremely large and complicated, alternative construction delivery method program. Several SVCW staff members have various experiences with design/build from both the owner and design/build firm side of the project. SVCW as an organization, however, has not done design/build previously and staff needs assistance to insure it is done properly.

Mr. Seybert questioned what is the role, if any, of Staff Engineers with regard to these projects?

Mr. Child responded that SVCW's Staff Engineers remain the Project Managers and these firms are there solely to advise and help them work through the process and, in fact, years

ago the Commission directed that all Project Managers must be SVCW employees and that the role would not be turned over to consultants.

In summary, Mr. Seybert said that these firms are going to influence as well as take direction from SVCW staff to which Mr. Child and Ms. Herrera both concurred that is the case.

Mr. Seybert further commented that typically if he worked for the owner that is doing the building, he's the owner representative and going to make sure their interests are being carried out by the Consultants who actually consult back and forth and who would eventually manage the design/build process.

Ms. Herrera replied that in SVCW's case, the owner is the Commission, Mr. Child and herself and then the Project Managers. These firms will work directly for the Project Managers. In addition, there will be legal staff under Ms. Fitzgerald working as part of the team, as well as some acquisition staff.

Mr. Seybert asked how many people will be working on this for Kennedy/Jenks for the \$314,000.00 and was he correct in assuming that if these people were brought on staff, this number would increase.

Mr. Minkowski, from Kennedy Jenks Consultants responded that approximately ten (10) people would be working on this project with various levels of time commitments. Mr. Child confirmed that SVCW could not hire the personnel to do this work for less money and in the timeframe needed as compared to the budget for the proposed work with the named consultants.

# Motion/Second: Mr. Grassilli / Mr. Moritz

- i. Move approval of AMENDMENT 1 TO TASK ORDER 2016-11 SCOPE AND BUDGET FOR OWNER'S ADVISOR SERVICES FOR THE GRAVITY PIPELINE PROJECT (CIP #6008 AND 6004) IN AN AMOUNT NOT TO EXCEED \$314,092 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – KENNEDY/JENKS
- ii. Move approval of AMENDMENT 1 TO TASK ORDER 2016-11 SCOPE AND BUDGET FOR OWNER'S ADVISOR SERVICES FOR THE RECEIVING LIFT STATION, HEADWORKS, AND INFLUENT CONNECTOR PIPELINE PROJECTS (CIP #6013, 6014, and 9160) IN AN AMOUNT NOT TO EXCEED \$451,435 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – BROWN AND CALDWELL

The motions carried by unanimous roll call vote.

<u>ITEM 8C</u>

CONSIDERATION OF MOTION TO RECEIVE AND ACCEPT SILICON VALLEY CLEAN WATER'S LONG RANGE FINANCIAL PLAN UPDATE

Mr. Anderson reported it has been a year since the last update of SVCW's Long Range Financial Plan (The Plan). The Plan informs the Commission of what the cash flow requirements are anticipated to be for the next decade. This planning document provides critical information for the rate setting process. Mr. Anderson added the report is customized to incorporate basic foundations of budgets, the Joint Powers Agreement and the Capital Improvement Program's (CIP) key pieces of information. This information was also used to build the financial model built and presented to the Commission.

Mr. Anderson said there were three key changes this year identified in the Staff Report. First, is the timing of the CIP. Over the last year, there has been a shift in the original plan since the last update in 2015. In addition, the Agency is now looking at nearly \$400 million dollars that will be deferred from years one and two to years three and four of the program. That is a major change in this plan. The second point of change is the availability of SRF loans. As previously discussed, SRF is now over-subscribed. Last year's plan did not recognize this and anticipated receiving about 80% of funding from SRF low cost loan money. The last key change and factor is inflation. Inflation is projected at 3.7% in construction and 4% on operations and maintenance. As a baseline, today the Agency spends approximately \$39 million dollars annually, mostly for Operations and Maintenance of facilities and the other large part is debt service payments.

Mr. Anderson displayed a graph of the remaining capital spending forecast for the next nine years, broken down by the each SVCW Member Agency totaling \$590 million dollars.

Mr. Anderson proceeded to display a chart indicating what SVCW anticipated at this time last year. There is a significant change in the next two fiscal years. Whereas the Agency thought they would spend upwards of \$140 million in the fiscal year 2018, the expected spend is now considerably less due to still being in the planning mode. Expenditures will of course rise over the next two years as the program progresses. Looking at it on the project level, the planning for treatment facilities, gravity pipeline and front of the plant is starting now and will take SVCW into year 2021. The program is expected to finish with the construction of replacement pump stations by 2024. Finally, nutrient removal is still out there and would add another \$104 million by the end of the planning window.

By applying the JPA Stage 1 Ownership and Stage 2 Capacity Rights, the breakdown for funding is as follows: Belmont - \$56 million dollars, Redwood City - \$287 million dollars, San Carlos - \$89 million dollars and West Bay Sanitary District - \$158 million dollars. Ultimately the question is how to finance these large sums of required money. Mr. Anderson ran through three different scenarios using bonds, government loans and a hybrid approach of both. Last year, the agency relied on availability of funding though SRF and moving away from that assumption is a big change in the plan.

Mr. Anderson said SVCW will continue to pursue funding and he is going to Sacramento in a few weeks with Ms. Herrera to discuss the two active applications submitted (Conveyance System and Wastewater Treatment Plant Improvements) with SRF staff. In the meantime, Mr. Anderson has suggested using the hybrid approach for planning future rate needs.

Mr. Seybert suggested the letter in support of SRF Funding to be signed by the Commission go out before Mr. Anderson goes to Sacramento. Mr. Child will arrange for the letter to be circulated and mailed out as soon as possible, but definitely within the next week.

Mr. Grassilli and Mr. Lieberman asked for clarification of the \$48 million highlighted for debt service repayment and Mr. Anderson replied that this represents the maximum level of annual payments needed to amortize the debt over a 30-35 year period. It is shown broken down into each Member Agency's own needs over the 35 year span. The document given to the Commission is based on a 10-year projection.

Mr. Anderson proceeded to show a graph with a dotted line representing last year's finance plan. Debt service last year was planned to be around \$40 million dollars per year. Due to inflation and the unavailability of less expensive government loan programs, there's been a rise of between \$4 million and \$5 million versus last year's plan for the hybrid approach of financing the program. At this point, the Plan is intended to be used for planning and for rate setting and to also prepare for worst-case scenarios. Mr. Anderson believes this is the prudent thing to do.

On an entity level, the dotted line represented last year's long range finance plan and shows that with this update, the first few years of debt payments are below last year's plan. This is caused by shifting of expenses out to future years, which lowers debt service payments in the early years and increases payments in the later years. The good news is this gives the Member Agencies time to get rates in place to prepare for the surge in debt service payments beginning the ninth year. The bad news is that there will be that surge in year nine.

SVCW is hoping to take advantage of the new WIFIA (Federal Water Infrastructure Financing Reform Act) program to offset some of the increased cost anticipated from the lack of SRF funding, WIFIA is also a low interest loan program (not as low as SRF) and allows delay of payments for up to five years after project completion. SRF has better loan rates and SVCW will continue to pursue them in hopes of obtaining the best possible financing package. Upon Commission approval of the 2017 Long-Term Financial Plan, Mr. Anderson stated he will commence the 2017-18 Budget process.

Mr. Grassilli made the comment that by the time the debt service and government loans are paid off in 30 years for the current work, there will be a need for a new plant or other capital improvements, maybe even before the loans are paid off. Mr. Child added it is very likely the current work will have reached the end of its useful life and new improvements will be needed. Mr. Grassilli wants to make sure it is understood that there is a possibility of the debt not being fully paid off before there is need for more improvements. Mr. Child stated this is definitely possible, but pointed out that the current SVCW Commission has put in place a Capital Reserve Plan that requires setting aside money to build the annual reserve contribution up to an amount equal to the annual depreciation beginning in a couple of years. The purpose of that policy is to save a substantial amount of money to, hopefully, meet the needs or at least soften the blow of future capital project costs.

Mr. Seybert said this is the result of the fact that improvements weren't done when needed in the past and nothing was set aside to pay for the future, now current, needs to replace the worn out facilities. Mr. Grassilli responded that it's unfortunate the future will have debt and also understands that at this point there is no way to get around the situation. Mr. Child again noted the foresight of the current Commission in adopting the Capital Reserve Policy to put aside money for these needs in the future.

Mr. Moritz said going through all the numbers, he found a couple things that may be in the report that he missed, but wanted to be sure discussion about the equity of using debt as a social issue is included. Mr. Moritz added he understands the position members are in due to previous years and he'd like to make a modification/correction in the report itself because it becomes a public document and historically, people will look back at this and it's worth stating why the agency is in this situation financially. Pay as you go would've been the perfect generational way of paying for this. The thing that might be worth inserting for additional information would be the cost per year of debt, both the placement costs as well as the interest costs so it's recognized that the increase in cost is because no money was put aside for a sinking fund. That should set the tone for future Commission's when approaching this and shows pay-as-you-go may be the way to go, versus debt.

Mr. Moritz then noted when looking at the percentage of overall increases each year that there are some years with large increases (15% and 21% are coming in two years) due to debt service needs. This relates to the rate setting requirements and having to face the people who have to pay this. West Bay is starting their annual rate evaluation and had a preliminary discussion at their Board meeting. The preliminary look shows a 5% increase next year. Any time a large percentage amount is dropped on the ratepayers, they get excited and for good reason. Mr. Moritz is thinking that if they adjust numbers this and next year, they may want to be conservative and go to 6% in order save some money to cushion the projected 21% and 15% increases.

Mr. Anderson said he has looked at each member agency's financial state and believes the current revenue at the Member Agencies is doing exactly what Mr. Moritz stated. They have been increasing rates due to the upcoming SVCW CIP needs and have accumulated cash balances that allow them to either pay cash now rather than borrowing (as Redwood City and Belmont did on the last bond sale) or being able to use the cash on hand to soften increases in the future by paying debt service with it. This allows the Member Agencies to take a moderate approach to rate-setting over the coming years and still have adequate revenue to make debt service payments when they increase in the future. Mr. Moritz replied West Bay has been working on a rate-modification model for this very purpose.

Mr. Seybert added this is why Redwood City was able to build up cash and make a big one-time payment by looking to future needs rather than year to year. Mr. Anderson said members have the option to reduce debt requirements by accruing and deploying cash on hand. Mr. Moritz asked Mr. Anderson if he has a calendar of when he expects to go to market for debt and how far will the \$30 Million Line of Credit support this. Mr. Anderson replied the agency currently has approximately \$8 million cash on hand and will probably spend around \$25 Million this year. Mr. Anderson doesn't think the Agency will reach a \$40 to \$50 Million spend rate this coming year based on engineering estimates. He added the Line of Credit could be used, but with the rise in interest rates (currently up 40 basis points) it may not be the best route. Mr. Anderson is keeping an eye on rates, raising the question of whether SVCW should continue to use the Line of Credit or issue more fixed-rate bonds to meet the Agency's needs for the next year or two. Mr. Anderson will return in late Spring 2017 with a recommendation of next steps.

Mr. Lieberman stated that he supports Commissioner Moritz's comments about trying to make sure the report is written as clearly as possible regarding the impact of not having any kind of reserves on hand when commencing the CIP. He added that having reserves while still ten to twenty years away from needing the money is the best practice for future generations. He emphasized the importance of not using debt and wants future Commissioners informed of what the ultimate goal is of having the money saved.

Mr. Child said the current Reserve Policy has another year or two of a fixed dollar contributions and after that, the policy requires contributions increase over a period of years until they are equal to annual depreciation. This is how the Commission addressed the concerns being voiced today and it was seen as the best way to build the fund into the future. The challenge is to keep future Commissions from seeing what they perceive as a large pot of money and either using it for other purposes or deciding to stop funding it to keep rates low.

Mr. Seybert concluded the presentation by thanking Mr. Anderson and reiterating the importance of having a long-term plan in place by working with the SVCW Member Agencies. He added he agrees fully with the move towards pay-as-you-go and also realizes nutrient removal was not originally forecasted and it is not possible to capture all foreseeable events. Also, in this world, inflation in construction often far outpaces what one can expect in planning for the future. Every little bit helps and if nothing else, it leaves the Commission with many less debt service decisions to face. Mr. Seybert reinforced that the current SVCW Commission is in this position because capital improvements and aging infrastructure weren't addressed since the plant's inception. As a final comment, Mr. Seybert stated that when making decisions one shouldn't shortcut things and at some point, some group has to bite the bullet and quit kicking the can down the road.

# Motion/Second: Mr. Grassilli / Mr. Lieberman

Move approval of RECEIPT AND ACCEPTANCE OF SILICON VALLEY CLEAN WATER LONG RANGE FINANCIAL PLAN 2017 UPDATE

The motion carried by unanimous roll call vote.

ITEM 9 CLOSED SESSION

Closed Session was called to order at 9:11 a.m.

A. <u>CONFERENCE WITH LEGAL COUNSEL – EXISTING LITIGATION</u> Pursuant to Government Code §54956.9(d)(1) Case Name: In the Matter of the Calculation of Final Compensation of David A. Hall, Respondent, and Silicon Valley Clean Water, Respondent (Board of Administration, California Public Employees' Retirement System, Agency Case No. 2015-1236 OAH NO. 2016030664)

B. <u>CONFERENCE WITH LEGAL COUNSEL – ANTICIPATED LITIGATION</u> Significant exposure to litigation pursuant to paragraph (2) of subdivision (d) of Government Code §54956.9 (12 potential cases): CalPERS' Determination to Exclude Performance Pay from Retirement Benefit Calculations and Opportunity to Appeal Determination

ITEM 10 RECONVENE IN OPEN SESSION

Open Session reconvened at 9:27 a.m. Legal Counsel reported that discussion was held, instruction was given to Staff and Counsel by the Commission and no action was taken.

<u>ITEM 11</u> ADJOURN

There being no further business, the meeting adjourned at 9:29 a.m.

Robert Grassilli, Secretary By: Daniel T. Child, Manager

# SVCW WARRANT REGISTER

SVCW Warrant Register dated January 31, 2017 for Retiree Health. Scanned copy was e-mailed to Commissioners on January 31, 2017.

	SILICON VALLEY CLEAN WATER		
01-31-17	WARRANT REGISTER		PAGE 9551
	FUND RECAP		
NAME		FUND	AMOUNT
RETIREE HEALTH INS	UR. FD.	12	22,738.47
TOTAL FOR APPROVAL			\$22,738.47

THIS IS TO CERTIFY THAT THE CLAIMS LISTED ON PAGES NUMBERED FROM 9547 THROUGH 9551 INCLUSIVE, AND/OR CLAIMS NUMBERED FROM 19542 THROUGH 19578 INCLUSIVE, TOTALING IN THE AMOUNT OF \$22,738.47, HAVE BEEN CHECKED IN DETAIL AND APPROVED BY THE PROPER OFFICIALS, AND IN MY OPINION REPRESENT FAIR AND JUST CHARGES AGAINST THE AUTHORITY IN ACCORDANCE WITH THEIR RESPECTIVE AMOUNTS AS INDICATED THEREON.

RESPECTFULLY SUBMITTED,

Full grome of 1,20,17 Mer 1/26/2017



PAGE 9547

NAME BUENROSTRO, BENJAMIN RETIREE MEDICAL PAYMENTS	WARRANT NUMBER 19542	1,338.78	DETAIL 1,338.78	
DONALDSON, ROBERT M. RETIREE MEDICAL PAYMENTS	19543	605.39 217 02/17 RETIREE HEALTH PREMIUM REFUND	605.39	12
FLAHERTY, LISA M. RETIREE MEDICAL PAYMENTS	19544	788.74 217 02/17 RETIREE HEALTH PREMIUM REFUND	788.74	12
LEACH, PRESTON L. RETIREE MEDICAL PAYMENTS	19545	172.48 217 02/17 RETIREE HEALTH PREMIUM REFUND	172.48	12
REEVES, DENNIS D. RETIREE MEDICAL PAYMENTS	19546	472.96 217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	12
REYES, CESAR V. RETIREE MEDICAL PAYMENTS	19547	472.96 217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	12
SCHIECHL, WARREN RETIREE MEDICAL PAYMENTS	19548	196.21 217 02/17 RETIREE HEALTH PREMIUM REFUND	196.21	12
WALSH, WALTER RETIREE MEDICAL PAYMENTS	19549	520.42 217 02/17 RETIREE HEALTH PREMIUM REFUND	520.42	12
WIDGER, RICHARD RETIREE MEDICAL PAYMENTS	19550	1,338.78 217 02/17 RETIREE HEALTH PREMIUM REFUND	1,338.78	12
BAKER, ANDREW RETIREE MEDICAL PAYMENTS	19551	1,223.22 217 02/17 RETIREE HEALTH PREMIUM REFUND	1,223.22	12
BEWLEY, JAMES B. RETIREE MEDICAL PAYMENTS	19552	472.96 217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	12

PAGE 9548

NAME BOVE, LEONARD F. RETIREE MEDICAL PAYMENTS	WARRANT NUMBER 19553	INVOICE #/DESCRIPTION 217 02/17 RETIREE HEALTH PREMIUM REFUND	AMOUNT 605.39	DETAIL 605.39	-
BUSCH, JOSEPH A. RETIREE MEDICAL PAYMENTS	19554	217 02/17 RETIREE HEALTH PREMIUM REFUND	172.48	172.48	12
CHAPMAN, ROBERT G RETIREE MEDICAL PAYMENTS	19555	217 02/17 RETIREE HEALTH PREMIUM REFUND	905.87	905.87	12
DIAZ, CLARA L. RETIREE MEDICAL PAYMENTS	19556	217 02/17 RETIREE HEALTH PREMIUM REFUND	261.76	261.76	12
FAZIO, MICHAEL RETIREE MEDICAL PAYMENTS	19557	217 02/17 RETIREE HEALTH PREMIUM REFUND	172.48	172.48	12
FORD, LARENCE RETIREE MEDICAL PAYMENTS	19558	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12
GERKE, FRED RETIREE MEDICAL PAYMENTS	19559	217 02/17 RETIREE HEALTH PREMIUM REFUND	605.39	605.39	12
GROSSO, LORNA RETIREE MEDICAL PAYMENTS	19560	217 02/17 RETIREE HEALTH PREMIUM REFUND	172.48	172.48	12
HALL, DAVID A. RETIREE MEDICAL PAYMENTS	19561	217 02/17 RETIREE HEALTH PREMIUM REFUND	.,778.81	1,778.81	12
HERNANDEZ, JOHN M. RETIREE MEDICAL PAYMENTS	19562	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12
JONES, REGGIE H. RETIREE MEDICAL PAYMENTS	19563	217 02/17 RETIREE HEALTH PREMIUM REFUND	196.21	196.21	12

PAGE 9549

NAME KAUFMAN, KENNETH J RETIREE MEDICAL PAYMENTS	WARRANT NUMBER 19564	INVOICE #/DESCRIPTION 217 02/17 RETIREE HEALTH PREMIUM REFUND	AMOUNT 172.48	DETAIL	FUND 12
KELLY, DIANE L. RETIREE MEDICAL PAYMENTS	19565	217 02/17 RETIREE HEALTH PREMIUM REFUND	579.26	579.26	12
KERTZ, FELIX J. RETIREE MEDICAL PAYMENTS	19566	217 02/17 RETIREE HEALTH PREMIUM REFUND	172.48	172.48	12
KLOKKE, KARL W. RETIREE MEDICAL PAYMENTS	19567	217 02/17 RETIREE HEALTH PREMIUM REFUND	579.26	579.26	12
MA, PO KUI RETIREE MEDICAL PAYMENTS	19568	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12
MURRAY, GENE RODGER RETIREE MEDICAL PAYMENTS	19569	217 02/17 RETIREE HEALTH PREMIUM REFUND	901.24	901.24	12
PINEDO, JESSE RETIREE MEDICAL PAYMENTS	19570	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12
POSCH, MICHAEL A. RETIREE MEDICAL PAYMENTS	19571	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12
SMITH, JULIE RETIREE MEDICAL PAYMENTS	19572	217 02/17 RETIREE HEALTH PREMIUM REFUND	1,338.78	1,338.78	12
SMITH, RAYMOND C. RETIREE MEDICAL PAYMENTS	19573	217 02/17 RETIREE HEALTH PREMIUM REFUND	520.42	520.42	12
STORMS, VERNON GARY RETIREE MEDICAL PAYMENTS	19574	217 02/17 RETIREE HEALTH PREMIUM REFUND	772.02	772.02	12

PAGE 9550

NAME SUTER, KATHERINE J. RETIREE MEDICAL PAYMENTS	WARRANT NUMBER 19575	INVOICE #/DESCRIPTION 217 02/17 RETIREE HEALTH PREMIUM REFUND	AMOUNT 905.87	DETAIL 905.87	FUND 12
TAYLOR, TERRY M. RETIREE MEDICAL PAYMENTS	19576	217 02/17 RETIREE HEALTH PREMIUM REFUND	905.87	905.87	12
VON SEEBACH, NANCY RETIREE MEDICAL PAYMENTS	19577	217 02/17 RETIREE HEALTH PREMIUM REFUND	579.26	579.26	12
WOODSTOCK, CRAIG M. RETIREE MEDICAL PAYMENTS	19578	217 02/17 RETIREE HEALTH PREMIUM REFUND	472.96	472.96	12

TOTAL

\$22,738.47

# SVCW WARRANT REGISTER

SVCW Warrant Register for period covering January 14, 2017 to January 27, 2017. Scanned copy was e-mailed to Commissioners on January 31, 2017.

	SILICON VALLEY CLEAN WATER		
01-27-17	WARRANT REGISTER	1	PAGE 9572
	FUND RECAP		
NAME		FUND	AMOUNT
CAPITAL IMPROV	EMENT FUND	14	7,641.14
OPERATION		18	175,650.07
PLANT - CIP BC	ND	20	929,847.69
TOTAL FOR APPROVAL			\$1,113,138.90

THIS IS TO CERTIFY THAT THE CLAIMS LISTED ON PAGES NUMBERED FROM 9552 THROUGH 9572 INCLUSIVE, AND/OR CLAIMS NUMBERED FROM 19579 THROUGH 19674 INCLUSIVE, TOTALING IN THE AMOUNT OF \$1,113,138.90, HAVE BEEN CHECKED IN DETAIL AND APPROVED BY THE PROPER OFFICIALS, AND IN MY OPINION REPRESENT FAIR AND JUST CHARGES AGAINST THE AUTHORITY IN ACCORDANCE WITH THEIR RESPECTIVE AMOUNTS AS INDICATED THEREON.

RESPECTFULLY SUBMITTED,

1

\_\_\_\_\_\_\_ DATE CONTROLLER

MA . 1/27/2017

She that

7. 2 1.30-17

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
ALPHA ANALYTICAL LABORATORIES	19579	3,759.00		
CONTRACT SERV. (NON-MAINT.)		6082550RPSVCWA PLANT PROCESS LAB ANALYSIS	1,386.50	18
		60825501RPSVCW PLANT PROCESS LAB ANALYSIS	258.50	18
		6112654RPSVCW SC LAB ANALYSIS	925.00	18
		6112654RPSVCW SC LAB ANALYSIS	340.00	18
		6122230RPSVCW PLANT PROCESS LAB ANALYSIS	154.00	18
		6122310RPSVCW PLANT PERMIT LAB ANALYSIS	190.00	18
		6122822RPSVCW PLANT PERMIT LAB ANALYSIS	315.00	18
		6123094RPSVCW PLANT PERMIT LAB ANALYSIS	190.00	18
AMERICAN SOCIETY OF SAFETY ENG	19580	175.00		
MEMB. & MEET.		1001364536 MEMBERSHIP DUES-DAVID LEE	175.00	18
AON RISK INSURANCE SERVICES WE	19581	10,000.00		
CONSTADMIN. & LEGAL		82200000218190 11/30/16-1/15/17 WORKERS COMP/GEN LIAB	10,000.00	20
AQUADYNE ASSOCIATES	19582	2,531.48		
MACHINERY AND EQUIP MAINT MAT	E	16075 QTY 1 BRUSH ASSEMBLY, QTY 2 TEFLON GASKET	2,498.78	18
		16075 QTY 1 BRUSH ASSEMBLY, QTY 2 TEFLON GASKET	32.70	18
AT&T	19583	330.66		
UTILITIES		107201701511 1/7-2/6/17 SCPS AT&T SVC	66.89	18
		107201715339 1/7-2/6/17 RWCPS AT&T SVC	98.44	18
		107201724836 1/7-2/6/17 MPPS AT&T SVC	98.44	18
		107201796059 1/7-2/6/17 BLPS AT&T SVC	66.89	18
BAY AREA NEWS GROUP - EAST BAY	19584	229.99		
CONSTADMIN. & LEGAL		1023632 12/8/16 LEGAL AD - SAN MATEO COUNTY TIMES	115.00	14
		1023632 12/8/16 LEGAL AD - SAN MATEO COUNTY TIMES	114.99	14
BEARING ENGINEERING COMPANY	19585	1,279.06		
MISCELLANEOUS		5426075 QTY 8 RED UROTHANE	1,279.06	18

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
BROWN & CALDWELL	19586		3,176.25		
PROFESSIONAL SERVICES		11283250 2017 ENGINEERING SERVICES		3,176.25	18
BUCKLES SMITH ELECTRIC COMPANY	19587		2,079.23		
MACHINERY AND EQUIP MAINT MAT	E	301213300 QTY 1 STRATIX, QTY 2 STRATIX SFP		1,249.30	18
		301213300 QTY 1 STRATIX, QTY 2 STRATIX SFP		829.93	18
CAL-OSHA REPORTER	19588		395.00		
MEMB. & MEET.		468545 RENEWAL SUBSCRIPTION 1-2 SAFETY PROS		395.00	18
CALIFORNIA PRODUCT STEWARDSHIP	19589		4,500.00		
SUPPLIES		FY17099AF 2016-2017 CPSC ASSOCIATE FEES		4,500.00	18
CALIFORNIA WATER SERVICE CO	19590		168.84		
UTILITIES		12152016 11/15-12/14/16 SCPS WATER SVC		168.84	18
CALTEST ANALYTICAL LABORATORY	19591		836.10		
CONTRACT SERV. (NON-MAINT.)		566920 NPDES PERMIT LAB ANALYSIS		836.10	18
CDW GOVERNMENT, INC.	19592		2,074.11		
SUPPLIES		GHK8607 OTY 1 1FT USB A TO B CABLE		5.67	18
		GHL8558 OTY 4 SANDISK 32GB FLASH DRIVE		66.93	18
		GJB2879 QTY 5 CISCO IP PHONE 7945-GETH COL SPARE		2,001.51	18
CINTAS CORPORATION	19593		206.90		
SUPPLIES		5006749753 12/2016 LAUNDRY SVC		206.90	18

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
COLLABORATIVE STRATEGIES CONSU	19594		16,170.00		
CONTRUCTION-DESIGN		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	4,389.00	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	957.60	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	319.20	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	438.90	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	159.60	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	159.60	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	478.80	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	558.60	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	79.80	20
		6608SV0117 12/17/16-1/11/17 T.O.2016-08 ENHANCED P	ROJ	438.90	20
		12601SV0117 12/17/16-1/11/17 T.O.2016-01 BELMONT FO	ORCE	3,465.00	20
		12602SV0117 12/17/16-1/11/17 T.O.2016-03 INFLUENT (	CONN	735.00	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANG	CE S	219.45	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	2,194.50	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANG	CE S	478.80	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	159.60	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANG	CE S	219.45	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	79.80	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANG	CE S	79.80	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	239.40	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	279.30	20
		111604SV0117 12/17/16-1/11/17 T.O.2016-04 CONVEYANO	CE S	39.90	20
CONSOLIDATED PARTS INC.	19595		3,964.31		
MACHINERY AND EQUIP MAINT	MATE	5036048 QTY 1 EATON PANEL		3,029.75	18
		5036251 QTY 6 J11, QTY 4 J20		563.96	18
		5036251 QTY 6 J11, QTY 4 J20		370.60	18
COTTIER, DON R.	19596		100.06		
SUPPLIES		1112017 REIM-1/8/17 O&M STAFF OT MEALS - MOUNTAIN M	4IKE	100.06	18

PAGE 9555

# 01/27/17

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
COUNTY OF SAN MATEO - AIRPORT	19597	97	,300.00		
CONSTADMIN. & LEGAL		1272017 2/17 PERMIT#5384-LEASE PYMNT SAN CARLOS AIRPOR		97,300.00	20
COVELLO GROUP INC., THE	19598		,187.50		
CONSTRUCTION-CONTRACTOR		201303438 12/16 T.O.2013-02 GLOBAL CM CIP PROJECTS		7,187.50	20
D.W. NICHOLSON CORPORATION	19599	1	,951.10		
MISCELLANEOUS		6685 QTY 2 FAB HTCH CVRS PG		975.55	18
		6685 QTY 2 FAB HTCH CVRS PG		975.55	18
DALY, MICK	19600		180.00		
UTILITIES		1101706128 REIMB 9/11/16-1/10/17 AT&T CHARGES		180.00	18
DENCO CONTROLS INC.	19601		101.67		
MISCELLANEOUS		17645 QTY 2 TRERICE		101.67	18
DKF SOLUTIONS GROUP, LLC	19602		450.00		
CONTRACT SERV. (NON-MAINT.)		12851 MY SAFETY OFFICER-MONTHLY SUBSCRIPTION FEE		450.00	18
EDGLEY, KIP D.	19603	20	,701.42		
CONTRUCTION-DESIGN		REIS1230SV1612A 11/28-1/1/17 T.O.2016-01 LABOR OUTSIDE		3,240.00	20
		REIS1230SV1612B REIM 11/28-1/1/17 T.O.2016-01 TRAVEL E		3,575.59	20
MISCELLANEOUS		REIS1230SV1612C 11/28-1/1/17 T.O.2016-01 7% NON RESIDE		-1,045.17	20
CONTRUCTION-DESIGN		REISS1230SV1612 11/28-1/1/17 T.O.2016-01 LABOR IN CA		14,931.00	20
ENDRESS+HAUSER, INC	19604		389.84		
MISCELLANEOUS		6001853540 QTY 2 PROMAG		389.84	18
		-			

WARRANT NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND ENVIRO-CARE INC 19605 143,547.04 CONSTRUCTION-CONTRACTOR WEC21530375 OTY 1 FLO-SEPTAGE RECEIVING STATION 75% PA 137,176.50 20 WEC215303ADD CIRCUIT BREAKERS FOR FLO-SEPTAGE RECEIVIN 933.04 20 PILOT21530311 1/7-2/6/17 PILOT 215303-30 DAYS TEST FEE 1,850.00 20 PILOT2153036A 8/7-9/6/16 FLO-BEAST WASTE RECEIVING 30D 5,450.00 20 PILOT2153037A 9/7-10/6/16 FLO-BEAST WASTE RECEIVING 30 5,450.00 20 PILOT2153038A 10/7-11/6/16 PILOT 215303-30 DAYS TEST F 5,450.00 20 PILOT2153039A 11/7-12/6/16 PILOT 215303-30 DAYS TEST F 5,450.00 20 PILOT21530311A 1/7-2/6/17 PILOT 215303-30 DAYS TEST FE 3,587.50 20 PILOT2153036CR 8/7-9/6/16 FLO-BEAST WASTE RECEIVING 30 -5,450.00 20 PILOT2153037CR 9/7-10/6/16 FLO-BEAST WASTE RECEIVING 3 -5,450.00 20 PILOT2153038CR 10/7-11/6/16 PILOT 215303-30 DAYS TEST -5,450.00 20 PILOT2153039CR 11/7-12/6/16 PILOT 215303-30 DAYS TEST -5,450.00 20 ENVIRONMENTAL RESOURCE ASSOCIA 19606 2,296.82 SUPPLIES 813460 LAB SUPPLIES, CHEMICALS 867.43 18 814226 LAB SUPPLIES, CHEMICALS 1,429.39 18 ERS INDUSTRIAL SERVICES, INC. 19607 221,062.50 CONSTRUCTION-CONTRACTOR 10B 12/16 PRG PMT 10 PRIM SEDIMENTATION TANK REHAB 110,531.25 20 10B 12/16 PRG PMT 10 PRIM SEDIMENTATION TANK REHAB 110,531.25 20 3,795.11 FASTENAL COMPANY 19608 SUPPLIES CASAA50679 VARIOUS PARTS 1,520.74 18 MISCELLANEOUS CASAA50768 VARIOUS PARTS 502.10 18 CASAA50820 VARIOUS PARTS 815.41 18 CASAA50919 VARIOUS PARTS 3.27 MACHINERY AND EOUIP MAINT MATE 18 CASAA50919 VARIOUS PARTS 3.72 18 CASAA50919 VARIOUS PARTS 15.42 18 SUPPLIES CASAA51014 VARIOUS PARTS 934.45 18

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
FED EX	19609		194.61		
SUPPLIES		568160403 12/19-1/13/17 FED EX CHARGES		28.62	18
		568160403 12/19-1/13/17 FED EX CHARGES		34.24	18
		568160403 12/19-1/13/17 FED EX CHARGES		85.44	18
		568160403 12/19-1/13/17 FED EX CHARGES		38.34	18
CONTRUCTION-DESIGN		568160403 12/19-1/13/17 FED EX CHARGES		7.97	20
FENTON, CHARLES	19610		27,177.10		
CONSTADMIN. & LEGAL		66 10/24-11/18/16 SERVICES INSIDE CA		22,165.00	20
		66A 10/24-11/18/16 SERVICES OUTSIDE CA		1,852.50	20
		66B REIM-10/24-11/18/16 TRAVEL EXPENSE		4,711.15	20
MISCELLANEOUS		66C 7% NONRESIDENT WITHHOLDING		-1,551.55	20
FIELDMAN, ROLAPP & ASSOCIATES	19611		4,817.50		
CONSTADMIN. & LEGAL		22898 12/1-12/29/16 PROFESSIONAL SERVICES		4,817.50	20
FISHER SCIENTIFIC COMPANY	19612		3,431.51		
SUPPLIES		1613601 LAB SUPPLIES		1,359.78	18
		1613601 LAB SUPPLIES		469.46	18
		1613601 LAB SUPPLIES		81.05	18
		6545057 LAB SUPPLIES		20.75	18
		6545057 LAB SUPPLIES		18.58	18
		6545057 LAB SUPPLIES		4.28	18
		6545057 LAB SUPPLIES		4.99	18
		6545057 LAB SUPPLIES		40.48	18
		6545057 LAB SUPPLIES		58.21	18
SMALL TOOLS		7469483 LAB SUPPLIES		796.98	18
SUPPLIES		7469484 LAB SUPPLIES		63.97	18
MISCELLANEOUS		7579851 LAB SUPPLIES		512.98	18

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
FITZGERALD, HERMAN H. LAW OFFI	19613	23,813.10		
PROFESSIONAL SERVICES		1272017A 12/16 GENERAL PROFESSIONAL SERVICES	3,658.50	18
CONSTADMIN. & LEGAL		1272017A 12/16 GENERAL PROFESSIONAL SERVICES	1,998.00	20
PROFESSIONAL SERVICES		1272017B REIM-12/16 EXPENSES GENERAL	117.00	18
CONSTADMIN. & LEGAL		1272017C 12/16 PROF SVCS CONVEYANCE SYSTEM	3,577.50	20
PROFESSIONAL SERVICES		1272017D REIM-12/16 PROF SVCS	100.20	18
CONSTADMIN. & LEGAL		REISS11292016A 11/16 PROF SVCS CONVEYANCE SYSTEM	9,571.50	20
		REISS11292016B REIM-11/16 PROF SVCS CONVEYANCE SYSTEM	100.20	20
PROFESSIONAL SERVICES		REISS11302016A 11/16 PROF SVCS	4,590.00	18
		REISS11302016B REIM-11/16 PROF SVCS	100.20	18
FIVESKY	19614	1,729.73		
PROFESSIONAL SERVICES		FSUSIN5703A ENDPOINT SECURITY PROTECTION FOR WORKSTATI	1,729.73	18
FONG, PETER	19615	179.42		
SUPPLIES		1112017 REIM-1/4/17 SAFETY SHOES	179.42	18
FRANK A. OLSEN CO.	19616	8,853.86		
MACHINERY AND EQUIP MAINT MAT		236963 QTY 1 6" DEZ, QTY 2 12" DEZ	1,657.77	18
MISCELLANEOUS	-	236963 QTY 1 6" DEZ, QTY 2 12" DEZ	7,196.09	18
MIDCHLINICOD			,,190.09	10
FREYER & LAURETA, INC	19617	3,387.50		
CONSTRUCTION-CONTRACTOR		17003 12/16 T.O.2016-03 PUMP STATION VALVE REPLACEMENT	1,693.75	14
		17003 12/16 T.O.2016-03 PUMP STATION VALVE REPLACEMENT	1,693.75	14
GABLE, ERIC	19618	197.08		
SUPPLIES		1162017 REIM-1/13/17 SAFETY SHOES	197.08	18

01/27/17

WARRANT NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND GRAINGER 19619 4,239.36 MACHINERY AND EQUIP MAINT MATE 9301254075 QTY 1 TUBING, QTY 2 HH POLYETHYLENE SPRAYER 309.46 18 MISCELLANEOUS 9301254075 QTY 1 TUBING, QTY 2 HH POLYETHYLENE SPRAYER 147.32 18 9304973267 OTY 6 CLEAR CONSTRUCTION FILM 515.10 18 MACHINERY AND EQUIP MAINT MATE 9305559123 QTY 1 Y CONNECTOR 10PK 25.30 18 9310902888 OTY 1 PTFE HOSE 79.95 18 MISCELLANEOUS 9311194105 COGENERATION JENNBACHER TOOLS 108.69 18 9311194105 COGENERATION JENNBACHER TOOLS 70.46 18 SMALL TOOLS 9311194105 COGENERATION JENNBACHER TOOLS 145.11 18 9311194105 COGENERATION JENNBACHER TOOLS 124.67 18 9311194105 COGENERATION JENNBACHER TOOLS 73.46 18 9311194105 COGENERATION JENNBACHER TOOLS 10.53 18 9311194105 COGENERATION JENNBACHER TOOLS 34.29 18 9311194105 COGENERATION JENNBACHER TOOLS 276.93 18 MACHINERY AND EOUIP MAINT MATE 9311544408 OTY 2 PIPE WRENCH 18" 147.99 18 SUPPLIES 9311544416 OTY 8 FUSE, OTY 2 TONGUE & GROOVE PLIERS 169.71 18 SMALL TOOLS 9311544416 OTY 8 FUSE, OTY 2 TONGUE & GROOVE PLIERS 38.30 18 9311544416 QTY 8 FUSE, QTY 2 TONGUE & GROOVE PLIERS 74.88 18 MACHINERY AND EOUIP MAINT MATE 9314005357 OTY 1 DRAINAGE MAT 1,375.14 18 SUPPLIES 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 36.97 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 56.02 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 44.74 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 34.91 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 29.16 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 52.08 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 17.94 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 40.00 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 60.05 18 9314005365 MALE CONNECTOR, MALE ELBOW, PLUG IN REDUCER 33.53 18 9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS 27.78 18 9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS 78.89 18

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
GRAINGER	19620	1,396.06		
SUPPLIES		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	54.96	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	88.05	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	55.30	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	18.03	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	12.35	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	28.39	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	118.42	18
		9314230328 EXTENDED MALE ELBOW, UNION TEES, PLUGS	108.77	18
MISCELLANEOUS		9317129857 QTY 3 EXTENSION CORD	138.84	18
MACHINERY AND EQUIP MAINT MA	ATE	9318608594 QTY 1 ELEC TANKLESS HEATER, QTY 6 FLOAT SWI	356.47	18
		9318608594 QTY 1 ELEC TANKLESS HEATER, QTY 6 FLOAT SWI	277.64	18
MISCELLANEOUS		9318608594 QTY 1 ELEC TANKLESS HEATER, QTY 6 FLOAT SWI	138.84	18
HANSEN, ERIC	19621	135.00		
CONF. & TRAV.		REISS12302016 REIMB-10/16-12/16 CELL PHONE FLAT RATE	135.00	18
HANSON BRIDGETT LLP	19622	11,967.00		
PROFESSIONAL SERVICES	19000	1180785 11/16 LEGAL SVCS-PUBLIC WORKS CONTRACTING&INFR	11,967.00	18
HARDY DIAGNOSTICS	19623	130.49		
SUPPLIES		1728834 1 PKG DEIONIZED WATER 90ML	130.49	18
HARRINGTON INDUST PLASTICS	19624	389.40		
MACHINERY AND EQUIP MAINT MA	TE	3K3563 QTY 6 3/4" VALVE BALL	238.10	18
		3K3658 QTY 20 2" PIPE P/E CLR PVC	151.30	18

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
HILLYARD INC	19625		583.16		
MISCELLANEOUS		602356086 JANITOR SUPPLIES		93.72	18
		602356086 JANITOR SUPPLIES		24.20	18
		602356086 JANITOR SUPPLIES		37.96	18
		602356086 JANITOR SUPPLIES		63.07	18
		602356086 JANITOR SUPPLIES		79.30	18
		602356086 JANITOR SUPPLIES		175.86	18
		602364050 JANITOR SUPPLIES		109.05	18
HILTI, INC.	19626		222.78		
MISCELLANEOUS		4608771570 QTY 3 HAMMER DRILL BIT		106.24	18
		4608794559 QTY 9 HAMMER DRILL BIT		116.54	18
HOPKINS TECHNICAL PRODUCTS, IN	19627		6,907.61		
MISCELLANEOUS		3616301563 50 DIAPHRAGM CAP		6,907.61	18
IDEXX DISTRIBUTION, INC	19628		28.35		
SUPPLIES	19020	3010601401 QTY 1 PRE-DISP QT 2000 COMPARATOR	28.35	28.35	18
SUFFLIES		SUIDBUIAUI QII I FRE-DISF QI 2000 COMFARAIOR		20.35	10
IPMA-HR	19629		318.00		
MEMB. & MEET.		25559P8N9D4 4/1/17-3/31/18 AGENCY MEMBERSHIP-ONLINE	520100	318.00	18
JENTECH SERVICES	19630		6,114.20		
MACH & EQUIP MAINT SERVICES		2222 1/10-1/19/17 INSTRUMENT CALIBRATION		1,520.00	18
-		2222 1/10-1/19/17 INSTRUMENT CALIBRATION		190.00	18
		2222 1/10-1/19/17 INSTRUMENT CALIBRATION		2,565.00	18
		2222 1/10-1/19/17 INSTRUMENT CALIBRATION		1,839.20	18

WARRANT NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND JHS CONSULTING, LLC 19631 4,132.12 CONTRUCTION-DESIGN 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 227.27 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEOA 2,272.67 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEOA 495.85 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 165.28 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 227.27 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 82.64 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 82.64 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 247.93 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 289.25 20 2016033 12/16 T.O.2016-03 CONVEYANCE SYSTEM CEQA 41.32 20 KEENAN SUPPLY 19632 132.96 MISCELLANEOUS S0093555850001 OTY 8 VIC LUB 4.5 OZ 132.96 18 LENSCRAFTERS 19633 91.00 SUPPLIES 1804884328 SAFETY GLASSES-MICHAEL SERRANO 91.00 18 LIEBERT CASSIDY WHITMORE 19634 3,921.00 PROFESSIONAL SERVICES 1433895 12/16 WAGE AND HOUR AUDIT 46.00 18 1433896 12/16 CALPERS AUDIT 2,180.00 18 1433897 12/16 D.A. HALL MGMT PAY PERS 1,695.00 18 LOCKSWORKS UNLIMITED 19635 38.04 64185 10 FA3 KEYS 38.04 SUPPLIES 18 M-I-C, INC 19636 713.11 MISCELLANEOUS 2995 QTY 9 VAREC-BIOGAS FOR 8" FLAME ARRESTER 713.11 18 MADCO WELDING SUPPLY CO 19637 838.68 RENTAL/LEASES 8452 12/19/16 CYLINDER RENTAL 92.50 18 SUPPLIES G48862 12/19/16 GAS RENTAL 746.18 18

01/27/17

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
MCMASTER-CARR SUPPLY CO.	19638	230.17		
MACHINERY AND EQUIP MAINT MAT	E	97425436 QTY 1 FLOOR-MOUNT SUPPORT FLANGE STYLE	230.17	18
	19639	4,172.10		
SUPPLIES		CA24998978 FREIGHT ONLY - WASTE OIL SHED	1,376.79	18
MISCELLANEOUS		CA24873677 QTY 5 HOSE DISCHARGE	1,528.57	18
MACHINERY AND EQUIP MAINT MAT	E	CA24997148 QTY 2 FITTINGS QTY 2 MALE CONN FITTINGS	41.25	18
		CA24997148 QTY 2 FITTINGS QTY 2 MALE CONN FITTINGS	101.72	18
		CA24997616 ATY 1 ELECTRIC MOTOR	570.84	18
MISCELLANEOUS		CA24997948 QTY 14 PEAT ABSORBENT 11LB BAG	552.93	18
NATIONAL SAFETY COUNCIL	19640	450.00		
MEMB. & MEET.		1182017976475 MEMBERSHIP RENEWAL	450.00	18
NEXLEVEL INFORMATION TECHNOLOG	19641	1,950.44		
CONSTADMIN. & LEGAL		20161224 12/16 ERP PROCUREMENT ENGAGEMENT	1,950.44	20
PACE SUPPLY CORP	19642	280.80		
MACHINERY AND EQUIP MAINT MAT	E	93550953 QTY 3 COMPACT BALL VALVE, QTY 105 STEEL PIPE	204.93	18
MISCELLANEOUS		93550953 QTY 3 COMPACT BALL VALVE, QTY 105 STEEL PIPE	84.64	18
MACHINERY AND EQUIP MAINT MAT	E	CM093550953 CREDIT MEMO - RETURNED QTY 3 COMPACT BALL	-204.93	18
MISCELLANEOUS		93635415 QTY 6 WELD ON LOW VOC GRAY PVC CEMENT	98.23	18
		93647425 QTY 4 WELD ON LOW VOC PURPLE PRIMER	97.93	18
PAN-PACIFIC SUPPLY CO.	19643	17,823.11		
		29594973 QTY 2 REBUILD WEMCO PUMP MODEL C 4X4	17,823.11	18
Then a byott part obrateby			17,023.11	10
PARSONS BRINCKERHOFF	19644	2,440.88		
CONTRUCTION-DESIGN		PB18AR671256 8/16 T.O.2014-01 63"FM PIPELINE TUNNEL PE	1,258.19	20
		PB18AR671256A 8/16 T.O.2014-01 63"FM PIPELINE TUNNEL P	1,182.69	20

WARRANT NAME NUMBER INVOICE #/DESCRIPTION AMOUNT FUND DETAIL PENINSULA BATTERY, INC. 19645 543.48 MACHINERY AND EQUIP MAINT MATE 119407 QTY 4 BATTERY 6 VOLT, 1 MOTORCRAFT BAT 434.78 18 119407 QTY 4 BATTERY 6 VOLT, 1 MOTORCRAFT BAT 108.70 18 PETTY CASH - SILICON VALLEY CL 19646 481.44 MEMB. & MEET. 1272017 PETTY CASH DISBURSEMENTS 32.50 18 SUPPLIES 1272017 PETTY CASH DISBURSEMENTS 43.09 18 1272017 PETTY CASH DISBURSEMENTS 176.86 18 1272017 PETTY CASH DISBURSEMENTS 92.55 18 TRAINING 1272017 PETTY CASH DISBURSEMENTS 30.26 18 SUPPLIES 1272017 PETTY CASH DISBURSEMENTS 54.49 18 1272017 PETTY CASH DISBURSEMENTS 51.69 18 POWER ENGINEERING CONSTRUCTION 19647 269,757.06 CONSTRUCTION-CONTRACTOR 8M10615 7/10-9/24/16 PRG PMT 8 SVCW BIOFORCE CONCRETE 9,038.00 20 12M10630 12/16 PRG PMT 12 RWC PS 48" FM EMERG REPAIR 58,667.06 20 19M10558 12/16 PRG PMT 19 PLANT EFFLUENT OUTFALL LEAK 202,052.00 20 QPCS LLC 19648 4,779.19 MACH & EQUIP MAINT SERVICES 13227 MILESTONE LICENSE RENEWAL 837.00 18 PROFESSIONAL SERVICES 13233 CONDUIT RUN FOR INTAKE CAMERA 3,942.19 18 R & B COMPANY 19649 3,243.35 S1602801001 QTY 3 ECC PLUG VALVE CONSTRUCTION-CONTRACTOR 3,066.31 20 MISCELLANEOUS S1613223001 QTY 3 0-60 DRY GAUGE BACK MOUNT 68.71 18 S1619150002 QTY 25 S80 PVC SXS 90 ELBOW, QTY 1 THRD BA MACHINERY AND EOUIP MAINT MATE 17.70 18 S1619150002 OTY 25 S80 PVC SXS 90 ELBOW, OTY 1 THRD BA 90.63 18 R.F. MACDONALD CO. 19650 107.14 MISCELLANEOUS 1191961 OTY 2 GASKET SUCTION COVER/LOWER VOLUTE 107.14 18

WARRANT NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND RGM AND ASSOCIATES 19651 1,706.50 CONST. - ADMIN. & LEGAL 602 12/7-12/31/16 T.O.2013-01 LABOR COMPLIANCE 20 568.84 602 12/7-12/31/16 T.O.2013-01 LABOR COMPLIANCE 568.83 20 CONTRUCTION-DESIGN 602 12/7-12/31/16 T.O.2013-01 LABOR COMPLIANCE 568.83 20 ROYAL WHOLESALE ELECTRIC 19652 4,173.59 MACHINERY AND EOUIP MAINT MATE 7003624347 QTY 1 HIGH BAY LED LT FX 439.66 18 7003625184 QTY 9 HIGH BAY LED LT FX 3,733.93 18 S & S SUPPLIES AND SOLUTIONS 19653 1,383.93 MACHINERY AND EQUIP MAINT MATE S2921657001 OTY 3 SENSOR 420.42 18 S2921657003 OTY 5 SENSOR OXYGEN 963.51 18 SAN MATEO COUNTY ENVIRONMENTAL 19654 1.730.00 ADMINISTRATIVE EXPENSES 285481 MPPS FEE 636.00 18 285481A MPPS FEE 35.00 18 285331 RCPS STORMWATER ANNUAL FEE 71.00 18 285331 RCPS STORMWATER ANNUAL FEE 35.00 18 285331 RCPS STORMWATER ANNUAL FEE 953.00 18 SANDUL, DUANE 19655 2,684.00 CONTRUCTION-DESIGN 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 161.04 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEOA 147.62 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 1,476.20 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 322.08 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 147.62 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 53.68 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 53.68 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 187.88 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 26.84 20 12B 12/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA 107.36 20

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
SCP SCIENCE	19656		109.83		
SUPPLIES		IN0000191250 LAB SUPPLIES		31.61	18
		IN0000191250 LAB SUPPLIES		46.61	18
		IN0000191250 LAB SUPPLIES		31.61	18
SNAP-ON INDUSTRIAL	19657		196.19		
MACHINERY AND EQUIP MAINT MAT	ſE	ARV31116285 QTY 1 TIMING LIGHT		196.19	18
STATE WATER RESOURCES CONTROL	19658		350.00		
TRAINING		1252017 SWRCB GRADE 3 OPER CERT EXAM APP A.GILBERT		350.00	18
STEVEN ENGINEERING INC.	19659		5,352.08		
MACHINERY AND EQUIP MAINT MAT	re.	240520700 VARIOUS PHOENIX PARTS		1,002.23	18
		240520700 VARIOUS PHOENIX PARTS		159.96	18
		240520700 VARIOUS PHOENIX PARTS		2,086.63	18
		240520700 VARIOUS PHOENIX PARTS		119.10	18
		240520700 VARIOUS PHOENIX PARTS		1,300.97	18
		240520701 QTY 2 PHOENIX FL COMSERVER		683.19	18

NAME	WARRANT NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
TANNER PACIFIC, INC.	19660	75,200.80		
CONSTRUCTION-CONTRACTOR		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	10,034.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	10,672.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	1,316.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	2,942.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	2,146.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	6,357.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	93.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	12,015.00	20
CONTRUCTION-DESIGN		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	3,214.00	20
CONSTRUCTION-CONTRACTOR		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	10,012.50	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	9,186.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	784.00	20
		217002 1/1-1/14/17 T.O.2016-01 CONSTRUCTION MGMT VARIO	6,429.30	20
TELEPACIFIC COMMUNICATIONS	19661	10,053.28		
UTILITIES		864472630 1/9-2/8/17 TELEPACIFIC SERVICE	6,053.28	18
		864472630 1/9-2/8/17 TELEPACIFIC SERVICE	1,000.00	18
		864472630 1/9-2/8/17 TELEPACIFIC SERVICE	1,000.00	18
		864472630 1/9-2/8/17 TELEPACIFIC SERVICE	1,000.00	18
		864472630 1/9-2/8/17 TELEPACIFIC SERVICE	1,000.00	18
THERMO ELECTRON NORTH AMERICA	19662	3,751.00		
MACH & EQUIP MAINT SERVICES		9020682249 1/9/17-1/8/18 EXT WARRANTY	3,751.00	18
_				
THOMAS FISH CO.	19663	126.00		
SUPPLIES		21362 QTY 110 RAINBOW TROUT	126.00	18
TOPOS ARCHITECTS INC	19664	4,023.65		
CONTRUCTION-DESIGN		1032017 7/16-12/16 GREENDALE PROJECT CONSULTING	4,023.65	14

WARRANT

172.00

18

NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND U.S. BANK CORPORATE PAYMENT SY 19665 5,257.66 12222016BB1 11/23/16 MS OFFICE 365 TEST SOFTWARE LICEN 100.00 18 SUPPLIES 12222016BB2 11/30/16 POWER EXTENSION CORD-AMAZON 246.12 18 MEMB. & MEET. 12222016BB3 12/12/16 MEMBERSHIP RENEWAL-WATER ISAC 999.00 18 12222016BB4 12/14/16 3/1/17-2/28/18 AWWA-MEMBERSHIP RE 262.00 18 TRAINING 12222016BB5 12/16/16 9/2/16-9/1/17 ONLINE TRAINING-LYN 375.00 18 SUPPLIES 12222016DC1 11/22/16 TRAVEL EXP-FUEL-LOVES COUNTRY 53.25 18 12222016DC2 11/23/16 TRAVEL EXP-FUEL-MAVERIK #342 73.00 18 12222016DC3 11/28/16 TRAVEL EXP-FUEL-PILOT 55.00 18 12222016DC4 11/28/16 TRAVEL EXP-FUEL-LOVES COUNTRY 64.00 18 12222016DC5 12/5/16 TRAVEL EXP-BART FARE-BART SAN BRUN CONF. & TRAV. 8.60 18 SUPPLIES 12222016DC6 12/9/16 TRAVEL EXP-FUEL-LOVES COUNTRY 57.00 18 12222016DC7 12/10/16 TRAVEL EXP-FUEL-CITY EXPRESS #5 68.00 18 12222016DC8 12/10/16 TRAVEL EXP-FUEL-PILOT 57.25 18 CONF. & TRAV. 12222016DC9 12/14/16 TRAVEL EXP-PARKING-HYATT REGENCY 25.00 18 MACHINERY AND EQUIP MAINT MATE 12222016DM2 11/28/16 HANDLING FEE - EAST BAY MOTORSPOR 30.45 18 TRAINING 12222016EM1 12/12/16 2/14-2/17/17 WWTT OP CERT PREP RE 750.00 18 12222016EM2 12/15/16 OWPSACSTATE-MFS LEADERSHIP TRAINI 113.68 18 12222016IS1 11/23/16 SVCW HOLIDAY EVENT SUPPLIES-HONEY SUPPLIES 193.32 18 12222016IS2 11/29/16 ANNUAL HOLIDAY EVENT REFRESHMENTS 66.34 18 12222016IS3 12/7/16 ANNUAL HOLIDAY EVENT SUPPLIES-ICE-11.53 18 ADMINISTRATIVE EXPENSES 12222016JF1 11/28/16 SR ENGINEER JOB POSTING-CWEA 285.00 18 12222016JF2 11/28/16 SR ENGIN JOB POSTING-BROWN & CALD 200.00 18 12222016JF3 12/6/16 JOB POSTING-SR PLANT MECHANIC ELEC 285.00 18 12222016LB1 12/1/16 11/16-12/14/16 FASTRAK-BRIDGE TOLL SUPPLIES 160.00 18 12222016MA1 12/20/16 FINANCE TEAM ORIENTATION-RANGOON 112.00 18 MEMB. & MEET. 12222016MH1 12/7/16 BAAQMD MEETING-BART FARE 8.00 18 12222016ND1 12/9/16 ICE CHEST-HOLDING GREASE/SEPTAGE H 38.12 18 SMALL TOOLS 12222016TH1 12/14/16 TRAVEL EXP-CONVEYANCE SYSTEM CEQA MEMB. & MEET. 99.00 18 12222016VV1 11/21/16 2017 ASCE-MEMBERSHIP DUES FOR TER 18 290.00

12222016VV2 11/22/16 CWEA-MEMBERSHIP RENEWAL-ERIC HANS

# 7B-19

WARRANT

NAME NUMBER INVOICE #/DESCRIPTION AMOUNT DETAIL FUND U.S. BANK CORPORATE PAYMENT SY 19666 4,011.28 SUPPLIES 12222016VV3 12/5/16 FINANCE SOFTWARE DEMONSTRATION LUN 260.09 18 12222016VV4 12/6/16 FINANCE SOFTWARE DEMONSTRATION LUN 192.11 18 MACH & EQUIP MAINT SERVICES 12222016DC10 12/16/16 PUTNAM MAZDA AND VOLVO - AUTO RE 1,410.43 18 SUPPLIES 12222016DC11 12/16/16 TRAVEL EXP-FUEL-HOLLY GAS & DIES 12.50 18 12222016DC12 12/20/16 TRAVEL EXP-FUEL-CHEVRON 26.00 18 12222016DC13 12/20/16 TRAVEL EXP-FUEL-TA BARSTOW 49.00 18 12222016DC14 12/21/16 AUTO SUPPLIES-MAVERIK #487 7.42 18 12222016DC15 12/21/16 TRAVEL EXP-FUEL-MAVERIK #487 53.50 18 12222016DC16 12/21/16 TRAVEL EXP-FUEL-MAVERIK #538 30.50 18 MISCELLANEOUS 1222216JD2TAX SALES TAX LIABILITY -11.25 18 12222016DM1TAX SALES TAX LIABILITY ~36.25 18 12222016DM3TAX SALES TAX LIABILITY -34.92 18 12222016DM6TAX SALES TAX LIABILITY -2.58 18 12222016DM8TAX SALES TAX LIABILITY -45.00 18 12222016JD4TAX SALES TAX LIABILITY -1.3418 12222016JD5TAX SALES TAX LIABILITY -2.71 18 MACHINERY AND EOUIP MAINT MATE 122216JD1 12/1/16 VOLTAGE RELAY-BASLER 16.54 18 122216JD1 12/1/16 VOLTAGE RELAY-BASLER 462.16 18 12222016DM1 11/22/16 WATER FILTER & SCREENS - FRESH WA 393.38 18 12222016DM1 11/22/16 WATER FILTER & SCREENS - FRESH WA 45.69 18 MISCELLANEOUS 12222016DM3 12/7/16 FIBERGLASS LIFE RING CABINET - CHE 474.92 18 MACHINERY AND EQUIP MAINT MATE 12222016DM4 12/8/16 EXTENSION CABLE - AMAZON.COM LLC 101.16 18 12222016DM5 12/12/16 REBAR, LATH, SCREW - THE HOME DEP 15.19 18 12222016DM5 12/12/16 REBAR, LATH, SCREW - THE HOME DEP 4.63 18 12222016DM5 12/12/16 REBAR, LATH, SCREW - THE HOME DEP 20.71 18 12222016DM5 12/12/16 REBAR, LATH, SCREW - THE HOME DEP SMALL TOOLS 12.26 18 MACHINERY AND EQUIP MAINT MATE 12222016DM5 12/12/16 REBAR, LATH, SCREW - THE HOME DEP 29.95 18 SUPPLIES 12222016DM6 12/14/16 PHONE CETIS SCITEC - AMAZON MKTPL 31.23 18 12222016DM7 12/20/16 DESK & MAT - VARIDESK 430.56 18 12222016DM7 12/20/16 DESK & MAT - VARIDESK 65.40 18

PAGE 9570

01/27/17

NAME U.S. BANK CORPORATE PAYMENT SY	WARRANT NUMBER 19667	INVOICE #/DESCRIPTION AMOUNT 1,541.83	DETAIL	FUND
MISCELLANEOUS		12222016DM8 12/21/16 WATERPROOF JACKET - AMAZON MKTPLA	544.96	18
MACHINERY AND EQUIP MAINT MAT	Е	12222016DM9 12/21/16 MOUNTING KIT - AVCO	237.53	18
MACH & EQUIP MAINT SERVICES		12222016DM9 12/21/16 MOUNTING KIT - AVCO	48.37	18
SMALL TOOLS		12222016JD2 12/8/16 SOLAR LIGHT-OUTDOOR SOLAR	136.25	18
MISCELLANEOUS		12222016JD3 12/9/16 WATER-COSTCO	385.00	18
MACHINERY AND EQUIP MAINT MAT	E	12222016JD4 12/12/16 LOCKING HALF SB-350-ANDERSON POWE	9.11	18
		12222016JD4 12/12/16 LOCKING HALF SB-350-ANDERSON POWE	97.77	18
SUPPLIES		12222016JD5 12/14/16 SUNSUN YT-304 AMAZON	8.53	18
		12222016JD5 12/14/16 SUNSUN YT-304 AMAZON	24.30	18
MACHINERY AND EQUIP MAINT MAT	Е	12222016JD6 12/22/16 WINDOW FILM-ULINE	11.86	18
		12222016JD6 12/22/16 WINDOW FILM-ULINE	7.63	18
		12222016JD6 12/22/16 WINDOW FILM-ULINE	30.52	18
UNIVAR USA INC. CHEMICAL SUPPLIES	19668	7,521.38 SJ791489 12/26/16 SOD HYPO 12.5% LIQUICHLOR SJ791597 12/21/16 SOD HYPO 12.5% LIQUICHLOR SJ791626 12/27/16 SOD BISULFITE 25%	2,103.44 1,118.61 4,299.33	18 18 18
V&A CONSULTING ENGINEERS, INC. CONSTRUCTION-CONTRACTOR	19669	1,805.00 16542 9/24-12/31/16 ENG SVCS CCT COATING	1,805.00	20
VALLEY OIL COMPANY	19670	540.11		
SUPPLIES		17026 SVC CHARGE	243.63	18
		36282 SVC CHARGE	296.48	18
VALLEY OIL COMPANY (VEHICLE FU	19671	1,194.24		
SUPPLIES		439856 10/15-12/31/16 FUEL CHARGES	676.87	18
		442703 11/30/16-1/15/17 FUEL CHARGES	517.37	18

PAGE 9571

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
VWR INTERNATIONAL, LLC	19672		2,030.50		
SUPPLIES		8047149100 QTY 3 LAB SUPPLIES S-AUREUS		766.50	18
		8047276048 QTY 8 HYDROGEN SULF		578.12	18
		8047280355 LAB SUPPLIES		60.19	18
		8047280355 LAB SUPPLIES		135.81	18
		8047280355 LAB SUPPLIES		119.51	18
		8047280355 LAB SUPPLIES		149.46	18
		8047280356 QTY 3 THERMOMETER, QTY 5 DISH WEIGH AL		48.99	18
		8047280356 QTY 3 THERMOMETER, QTY 5 DISH WEIGH AL		104.79	18
		8047285241 QTY 1 BUFFER SOL		67.13	18
WHITLEY, BURCHETT AND ASSOCIAT	19673		3,886.35		
CONTRUCTION-DESIGN		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	365.56	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	60.93	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	60.93	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	167.55	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	121.85	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	182.78	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	167.55	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	30.47	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	213.24	20
		SVC1645 12/16 T.O.2016-02 CONVEYANCE SYSTEM PROGRAM	MG	1,675.49	20
CONSTADMIN. & LEGAL		SVC16211 12/16 T.O.2016-01 SRF FINANCIAL SVCS		840.00	20
XEROX CORPORATION	19674		1,231.82		
RENTAL/LEASES		87585769 1/17 XEROX LEASE		419.30	18
		87585770 1/17 XEROX LEASE		247.61	18
		87585771 1/17 XEROX LEASE		303.34	18
		87585772 1/17 XEROX LEASE		261.57	18

TOTAL

\$1,113,138.90

# SVCW WARRANT REGISTER

SVCW Warrant Register for January 31, 2017. Scanned copy was e-mailed to Commissioners on February 1, 2017.

#### SILICON VALLEY CLEAN WATER W A R R A N T R E G I S T E R 02/10/17

	WARRANT					
NAME	NUMBER	INVOICE #	/DESCRIPTION	AMOUNT	DETAIL	FUND
UNIVAR USA INC.	19675			18,587.94		
CHEMICAL SUPPLIES		SJ790165	12/13/16 SOD HYPO 12.5%		2,014.39	18
		SJ792369	1/2/17 SOD BISULFITE 25%		3,973.03	18
		SJ790483	12/19/16 SOD BISULFITE 25%		4,334.57	18
		SJ793577	1/5/17 SOD HYPO 12.5% LIQUICHLOR		2,141.91	18
		SJ792988	1/3/17 SOD HYPO 12.5% LIQUICHLOR		2,007.55	18
		SJ792239	12/30/16 SOD HYPO 12.5%		2,102.99	18
		SJ790879	12/20/16 SOD HYPO 12.5%		2,013.50	18

.

D. all 1-31-17

TOTAL

\$18,587.94

DR 1/21/2017

7B-2

PAGE 210

LIST AP VENDOR ID.SUP GID TOTAL	TOT . AMT	BREAK.SUP VEND REQUIRE.SELECT LPTR 11:02:04 01-31-17 PAGE 1	•
VENDOR NAME	VOUCHER	TOTAL AMOUNT	

UNIVAR USA INC.	163506	\$2,014.39
UNIVAR USA INC.	163507	\$2,013.50
UNIVAR USA INC.	163508	\$2,102.99
UNIVAR USA INC.	163509	\$2,007.55
UNIVAR USA INC.	163510	\$2,141.91
UNIVAR USA INC.	163511	\$4,334.57
UNIVAR USA INC.	163512	\$3,973.03

\$18,587.94

-----\$18,587.94

7 records listed.

# SVCW WARRANT REGISTER

SVCW Warrant Register for period covering December 31, 2016 to January 13, 2017. Scanned copy was e-mailed to Commissioners on January 17, 2017.

	SILICON VALLEY CLEAN WATER		
01-13-17	WARRANT REGISTER		PAGE 9546
	FUND RECAP		
NAME		FUND	AMOUNT
RETIREE HEALTH	INSUR. FD.	12	35,000.00
CAPITAL IMPROVI	EMENT FUND	14	241,866.84
OPERATION		18	586,682.86
PLANT - CIP BON	ND	20	411,515.58
TOTAL FOR APPROVAL		:	\$1,275,065.28
TOTAL FOR APPROVAL		5	\$1,275,065.28

CTUTON WALLEY GLEAN HAMPE

THIS IS TO CERTIFY THAT THE CLAIMS LISTED ON PAGES NUMBERED FROM 9533 THROUGH 9546 INCLUSIVE, AND/OR CLAIMS NUMBERED FROM 19466 THROUGH 19541 INCLUSIVE, TOTALING IN THE AMOUNT OF \$1,275,065.28, HAVE BEEN CHECKED IN DETAIL AND APPROVED BY THE PROPER OFFICIALS, AND IN MY OPINION REPRESENT FAIR AND JUST CHARGES AGAINST THE AUTHORITY IN ACCORDANCE WITH THEIR RESPECTIVE AMOUNTS AS INDICATED THEREON.

RESPECTFULLY SUBMITTED,

CONTROLLER DATE

Jul 1350- 2017



7B-2

01/13/17

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
ACE AMERICAN INSURANCE COMPANY	19466	99,139.55		
CONSTADMIN. & LEGAL		1072154 12/16 REIMB FOR W/C D.NEILL CLAIM#498/29838394	99,139.55	20
AIR PRODUCTS GROUP INC	19467	897.88		
MISCELLANEOUS		80255 QTY 16 BOX FILTER	453.44	18
SUPPLIES		80255 QTY 16 BOX FILTER	100.00	18
MISCELLANEOUS		80255 QTY 16 BOX FILTER	344.44	18
AKELA, ARVIND	19468	85.00		
UTILITIES	19100	12012016 REIMB-12/16 CELL/MEETING	45.00	18
MEMB. & MEET.		12012016 REIMB-12/16 CELL/MEETING	40.00	18
			40.00	10
APPLEONE EMPLOYMENT SERVICES	19469	1,987.84		
PROFESSIONAL SERVICES		14249341 W/E 10/15/16 ACCT TEMP SVCS-WONG	993.92	18
		14263291 W/E 10/29/16 ACCT TEMP SVCS-WONG	993.92	18
BANK OF NEW YORK MELLON, THE	19470	1,250.00		
INTEREST EXPENSES		2521993009 12/01/16-11/30/17 TRUSTEE FEE	335.50	20
		2521993009 12/01/16-11/30/17 TRUSTEE FEE	607.12	20
		2521993009 12/01/16-11/30/17 TRUSTEE FEE	189.25	20
		2521993009 12/01/16-11/30/17 TRUSTEE FEE	118.13	20
BAY ALARM COMPANY	19471	788.35		
CONTRACT SERV. (NON-MAINT.)		13308629 10/1/16-1/1/17 FIRE MONITORING FEE	776.70	18
		13431814 10/1/16-1/1/17 LATE FEE - FIRE MONITORING	11.65	18
BAY AREA AIR QUALITY MANAGEMEN	19472	15,715.00		
ADMINISTRATIVE EXPENSES		238572 2/1/17-2/1/18 ANNUAL PERMIT RENEWAL - RWCPS	354.00	18
		238573 2/1/17-2/1/18 ANNUAL PERMIT RENEWAL - BLPS	354.00	18
		238589 2/1/17-2/1/18 ANNUAL PERMIT RENEWAL - MPPS	354.00	18
		3XN42 3/1/17-3/1/18 ANNUAL PERMIT RENEWAL - SITE A1534	14,653.00	18

.

	WARRANT					
NAME	NUMBER	INVOICE	#/DESCRIPTION	AMOUNT	DETAIL	FUND
BEECHER ENGINEERING	19473		1:	3,940.00		
PROFESSIONAL SERVICES		111645	10/25-11/24/16 T.O.2016-01 ELECTRICAL ENG SVCS		5,248.00	18
CONTRUCTION-DESIGN		121643	11/25-12/24/16 T.O.2016-03 12KV PLANNING & CONS	5	82.00	20
		121643	11/25-12/24/16 T.O.2016-03 12KV PLANNING & CONS	5	82.00	20
PROFESSIONAL SERVICES		121645	11/25-12/24/16 T.O.2016-01 ELECTRICAL ENG SVCS		7,216.00	18
CONTRUCTION-DESIGN		121647	11/25-12/24/16 T.O.2016-06 IT OUTAGE/POWER SURG	3	820.00	14
CONTRUCTION-DESIGN		121651	11/25-12/24/16 T.O.2016-04 WETSIDE REDUNDANT PC	<b>)</b>	492.00	20
BROWN & CALDWELL	19474		12	2,697.40		
CONTRUCTION-DESIGN		1128208	9 9/30-11/24/16 T.O.2012-01 PUMP STATION PREDES	3	339.75	20
		1128208	9 9/30-11/24/16 T.O.2012-01 PUMP STATION PREDES	3	339.75	20
		1128208	9 9/30-11/24/16 T.O.2012-01 PUMP STATION PREDES	3	339.75	20
		1128208	9 9/30-11/24/16 T.O.2012-01 PUMP STATION PREDES	6	339.75	20
		1128209	0 10/28-11/24/16 T.O.2014-06 36" GRAVITY SEWER		1,271.50	20
		11282093	1 10/28-11/24/16 T.O.2015-06 PST REHAB		1,834.50	20
		1128209	1 10/28-11/24/16 T.O.2015-06 PST REHAB		611.50	20
		11282198	8 10/28-11/24/16 T.O.2015-07 REC LIFT STATION (	2	7,620.90	20
BUCKLES SMITH ELECTRIC COMPANY	19475		2	2,039.63		
MACHINERY AND EQUIP MAINT MATE	:	30167550	00 CREDIT INV 148258800 32PT ML 1400 DC IN RELA	1	-777.83	18
		30119270	00 QTY 2 SOLID STATE TIMING RELAY		2,023.74	18
		30166260	00 QTY1 ML 1400 DC IN RELAY OUT		793.72	18
C.W.E.A SCVS	19476		د	,260.00		
MEMB. & MEET.		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	2	315.00	18
		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	2	280.00	18
		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	ł	175.00	18
		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	2	210.00	18
		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	1	210.00	18
		11172016	5 6/16, 7/21, 8/18, 10/20, 11/17/16 CWEA DINNER	1	70.00	18

•

#### SILICON VALLEY CLEAN WATER W A R R A N T R E G I S T E R 01/13/17

PAGE 9535

NAME CA ST DEPT OF FISH AND GAME (C CONSTADMIN. & LEGAL	WARRANT NUMBER 19477	INVOICE #/DESCRIPTION AMOUNT 1,221.00 122216A NOTIF #1600-2012-0373-R3 AMENDMENT FEE LAKE/ST	DETAIL	FUND 20
CA ST DEPT OF FISH AND GAME (C CONSTADMIN. & LEGAL	19478	562.00 12222016 NOTIF #1600-2012-0373-R3 AMENDMENT FEE LAKE/S	562.00	20
CA ST-BOARD OF EQUALIZATION MISCELLANEOUS	19479	2,088.00 1132017 10/01/16-12/31/16 SALES TAX ACCRUAL 19-751218 1132017 10/01/16-12/31/16 SALES TAX ACCRUAL 19-751218	2,087.56 0.44	18 18
CA ST-BOARD OF EQUALIZATION ADMINISTRATIVE EXPENSES	19480	140.00 1132017 2016 UNDERGROUND STORAGE TANK MNTC TAX#44-0253	140.00	18
CA ST-FRANCHISE TAX BOARD MISCELLANEOUS	19481	8,727.68 1132017 09/01/16-12/31/16 FORM 592V NONRESIDENT WITHHO	8,727.68	20
CALIFORNIA DETAILERS, INC. MACH & EQUIP MAINT SERVICES	19482	275.00 42984 12/10/16 FLEET VEHICLE WASH ON-SITE	275.00	18
CALIFORNIA GENERATOR SERVICE MACH & EQUIP MAINT SERVICES	19483	13,380.71 47741 CONTROL BOARD REPLACEMENT & GENERATOR RENTAL	13,380.71	18
CALIFORNIA SANITATION RISK MAN MISCELLANEOUS	19484	79,906.89 6044 12/31/16-12/31/17 PLP POOLED DEPOSIT LESS PLP RET	79,906.89	18
CALPERS - FISCAL SERVICES DIVI RETIREE MEDICAL PAYMENTS	19485	35,000.00 1132017 01/17 PREFUNDING OPEB	35,000.00	12
CASCADE INTEGRATION & DEVELOPM CONTRUCTION-DESIGN	19486	9,990.00 1231 12/16 T.O.2016-01 SOLIDS PROCE AUTO C#8007/18/21 1231 12/16 T.O.2016-01 SOLIDS PROCE AUTO C#8007/18/21 1231 12/16 T.O.2016-01 SOLIDS PROCE AUTO C#8007/18/21	3,330.00 3,330.00 3,330.00	20 20 20

PAGE 9536

NAME CDW GOVERNMENT, INC. MACHINERY AND EQUIP MAINT MA	WARRANT NUMBER 19487 TE	INVOICE #/DESCRIPTION GDX7918 QTY 2 APC REPLACEMENT BATT	AMOUNT 789.82	DETAIL 789.82	FUND 18
CINTAS CORPORATION NO. 3 SUPPLIES	19488	464688867 12/2016 LAUNDRY SERVICE	778.86	778.86	18
COLLABORATIVE STRATEGIES CONSU	19489	4./	977.50		
CONTRUCTION-DESIGN		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		298.65	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		348.43	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		49.78	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		273.76	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		2,737.62	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		597.30	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		199.10	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		273.76	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		99.55	20
		5608SV1216 11/23-12/16/16 T.O.2016-08 ENHANCED PROJECT		99.55	20
CPI INTERNATIONAL INC	19490		136.34		
MISCELLANEOUS		20030562TAX SALES TAX LIABILITY		-8.81	18
SUPPLIES		20030562 LAB SUPPLIES		89.01	18
		20030562 LAB SUPPLIES		28.07	18
		20030562 LAB SUPPLIES		28.07	18
EDGLEY, KIP D.	19491	24,	124.16		
CONTRUCTION-DESIGN		1230SV1612 11/28-1/1/17 T.O.2016-01 LABOR IN CA		14,769.00	20
		1230SV1612A 11/28-1/1/17 T.O.2016-01 LABOR OUTSIDE CA		4,387.50	20
		1230SV1612B REIM 11/28-1/1/17 T.O.2016-01 TRAVEL EXPEN		6,001.49	20
MISCELLANEOUS		1230SV1612C 11/28-1/1/17 T.O.2016-01 7% NON RESIDENT W		-1,033.83	20
ENVIRO-CARE INC	19492	27,	435.30		
CONSTRUCTION-CONTRACTOR		WEC215303 PARTS C#9229 BEAST 1200 SEPATAGE REC STATION		27,435.30	20

01/13/17

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
ENVIRONMENTAL RESOURCE ASSOCIA	19493	227.80		
SUPPLIES		812471 LAB CHEMICALS	227.80	18
ESPOSTO'S	19494			
SUPPLIES	1)1)1	1,191.06		
		51348A 25TH ANNUAL EMPLOYEE RECOGNITION EVENT 2/1/17 I	1,191.06	18
FASTENAL COMPANY	19495	711.92		
SUPPLIES		CASAA50592 VENDOR MANAGED RESTOCK	134.84	18
MISCELLANEOUS		CASAA50680 QTY 20 CARBON STEEL WELDING WIRE	130.02	18
		CASAA50819 QTY 100 SS CHANNEL NUT, QTY 2000 NYLON CABL	343.07	18
		CASAA50819 QTY 100 SS CHANNEL NUT, QTY 2000 NYLON CABL	103.99	18
FIVESKY	19496	123,549.79		
CONTRACT SERV. (NON-MAINT.)		FSUSIN5853 11/9/16-11/8/17 DRUVA PHOENIX ENTERPRISE 1Y	23,544.00	18
SUPPLIES		FSUSIN5855 WYSE THIN OS SOFTWARE & MAINTENANCE	2,325.79	18
PROFESSIONAL SERVICES		FSUSIN5856 VULNERABILITY SCANNING IT	12,000.00	18
CONTRACT SERV. (NON-MAINT.)		FSUSIN5857 IT SUPPORT	67,680.00	18
PROFESSIONAL SERVICES		FSUSIN5858 IT PERFORMANCE & RISK REPORT SERVICES	18,000.00	18
FREYER & LAURETA, INC	19497	7,921.57		
CONTRUCTION-DESIGN		16460 11/16 PLANT LAND USE PROJ C#6004/9160/9192/9221	231.78	20
		16450 11/16 PLANT LAND USE PROJ C#6004/9160/9192/9221	231.78	20
		16460 11/16 PLANT LAND USE PROJ C#6004/9160/9192/9221	231.78	20
		16460 11/16 PLANT LAND USE PROJ C#6004/9160/9192/9221	231.79	20
CONSTRUCTION-CONTRACTOR		16480 11/16 T.O.2016-03 PUMP STATION VALVE REPLACEMENT	2,278.65	14
		16480 11/16 T.O.2016-03 PUMP STATION VALVE REPLACEMENT	2,278.65	14
CONTRUCTION-DESIGN		16489 11/16 T.O.2014-04 CONVEYANCE SYST PROG C#6006	170.00	20
		16489 11/16 T.O.2014-04 CONVEYANCE SYST PROG C#6006	170.00	20
		16490 11/16 T.O.2015-06 WWTF LAND USE FACILITY CIP#600	524.28	20
		16490 11/16 T.O.2015-06 WWTF LAND USE FACILITY CIP#600	524.28	20
		16490 11/16 T.O.2015-06 WWTF LAND USE FACILITY CIP#600	524.28	20
		16490 11/16 T.O.2015-06 WWTF LAND USE FACILITY CIP#600	524.29	20

NAME N	VARRANT NUMBER L9498	INVOICE #/DESCRIPTION 10233390 QTY 1 EZ COD RECYCLING KIT	AMOUNT 770.00	<b>DETAIL</b>	FUND 18
HANSEN, ERIC 1 CONF. & TRAV.	19499	1132017 REIM-12/9/16 MILEAGE	11.88	11.88	18
HARRINGTON INDUST PLASTICS 1	19500		5,380.86	11.00	10
MACHINERY AND EQUIP MAINT MATE		3K1825 PLUMBING SUPPLIES		1,284.24	18
		3K4147 CREDIT INV 3K1825 RETURN PARTS		-330.14	18
CONSTRUCTION-CONTRACTOR		3K3379 QTY 6 SANITARY BALL		1,204.19	20
MISCELLANEOUS		3K3379 QTY 6 SANITARY BALL		602.11	18
CONSTRUCTION-CONTRACTOR		3K3379 QTY 6 SANITARY BALL		1,754.66	20
MISCELLANEOUS		3K3379 QTY 6 SANITARY BALL		865.80	18
	.9501		782.21		
MISCELLANEOUS		602335650 JANITOR SUPPLIES		126.13	18
		602335650 JANITOR SUPPLIES		75.93	18
		602335650 JANITOR SUPPLIES		31.24	18
		602335650 JANITOR SUPPLIES		333.40	18
		602335650 JANITOR SUPPLIES		79.30	18
		602335650 JANITOR SUPPLIES		136.21	18
	9502		145.93		
MACHINERY AND EQUIP MAINT MATE		1228201647388 PARTS		145.93	18
	9503		4,094.50		
MACH & EQUIP MAINT SERVICES		2221 12/30-1/6/17 INSTRUMENT CALIBRATION		2,755.00	18
		2221 12/30-1/6/17 INSTRUMENT CALIBRATION		1,339.50	18
	9504		2,730.75		
MISCELLANEOUS		43847TAX SALES TAX LIABILITY		-245.77	18
MACHINERY AND EQUIP MAINT MATE		43847 OIL SAMPLE BOTTLES JENBACHER ENGINES		2,976.52	18

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
JW HEATING AND AIR	19505	INVOICE #/ DESCRIPTION	140.00	DETAIL	FUND
MACH & EQUIP MAINT SERVICES	19900	20161747 12/20/16 FURNACE AND DUCTING	140.00	140.00	18
KEN GRADY COMPANY, INC	19506		285.96		
MACHINERY AND EQUIP MAINT MAT	Е	2335 QTY 1 ATI POWER SUPPLY		285.96	18
MADCO WELDING SUPPLY CO	19507		83.75		
RENTAL/LEASES		8155 8/11-11/16/16 CYLINDER RENTAL		83.75	18
MCGUIREWOODS LLP	19508		44,887.50		
CONSTADMIN. & LEGAL		91814390 03/09/15-06/10/15 PROFESSIONAL SVCS		44,887.50	20
NAVIA BENEFIT SOLUTIONS	19509		182.20		
ADMINISTRATIVE EXPENSES		10070583 12/1-12/31/16 PARTICIPANT FEE		182.20	18
NEWARK ELEMENT14	19510		261.67		
MACHINERY AND EQUIP MAINT MAT	Е	28518339 QTY 4 PLUG & SOCKET CONNECTOR PLUG		247.69	18
		28518339 QTY 4 PLUG & SOCKET CONNECTOR PLUG		13.98	18
O.K. LUMBER COMPANY	19511		317.34		
MACHINERY AND EQUIP MAINT MAT	E	404535 QTY 38 CONCRETE MIX, QTY 3 REBAR		54.50	18
		404535 QTY 38 CONCRETE MIX, QTY 3 REBAR		9.81	18
		404535 QTY 38 CONCRETE MIX, QTY 3 REBAR		231.91	18
SUPPLIES		405145 QTY 2 DOUG FIR STD BTR		21.12	18

.

.

.

	WARRANT				
NAME	NUMBER	INVOICE #/DESCRIPTION	AMOUNT	DETAIL	FUND
OFFICE DEPOT	19512		907.32		
SMALL TOOLS		886103878001 OFFICE SUPPLIES		52.31	18
OFFICE SUPPLIES		887333659001 OFFICE SUPPLIES		72.79	18
SUPPLIES		887333659001 OFFICE SUPPLIES		52.83	18
OFFICE SUPPLIES		887409917001 OFFICE SUPPLIES		263.49	18
		887827303001 OFFICE SUPPLIES		153.35	18
SUPPLIES		887827303001 OFFICE SUPPLIES		167.87	18
OFFICE SUPPLIES		887832398001 OFFICE SUPPLIES		6.62	18
		889654626001 OFFICE SUPPLIES		138.06	18
OTIS ELEVATOR COMPANY	10510				
MACH & EQUIP MAINT SERVICES	19513		4,967.01		
MACH & EQUIP MAINI SERVICES		SJ04029117 1/1-3/31/17 ELEVATOR CONTRACT SERVICE		4,967.01	18
PACIFIC GAS AND ELECTRIC COMPA	19514	1	176,582.51		
UTILITIES		1221201690892 11/15-12/13/16 ELECT UTIL 1406		373.94	18
		1221201690892 11/15-12/13/16 ELECT UTIL 1406		443.77	18
		1121201619225 10/14-11/15/16 SCPS ELEC UTIL		5,633.35	18
		1128201626195 11/22-12/21/16 MPPS ELEC		4,722.75	18
		1130201683066 10/26-11/27/16 PLANT ELECTRIC		76,023.39	18
		1221201619225 11/15-12/13/16 SCPS ELEC UTIL		3,165.64	18
		1221201688673 11/15-12/13/16 BLPS ELEC UTIL		2,163.70	18
		1228201683066 11/28-12/26/16 PLANT ELEC		62,794.88	18
		1230201603894 11/23-12/22/16 LYNGSO ELEC		14.77	18
		75956250 11/2016 DEPARTING LOAD		10,757.51	18
		76031988 11/2016 PLANT DEPARTING LOAD		10,488.81	18
POWER ENGINEERING CONSTRUCTION	19515		80,842.26		
CONSTRUCTION-CONTRACTOR		1540 12/31/15-7/31/16 PRG PMT 3 PROJ#2013.034.40 C#9	•	2,725.00	20
		155711 11/16 PRG PMT 11 RWC PS 48" FM EMERG REPAIR C		78,117.26	20
PRE EMPLOYMENT, INC.	19516		45.00		
PROFESSIONAL SERVICES		31399 BACKGROUND CHECK-CHIU		45.00	18

PAGE 9541

NAME OPCS LLC	WARRANT NUMBER 19517	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
		1,745.00 12975 10/28/16 ONSITE TECH SUPPORT - INTERCOM SYSTEM	1,745.00	18
R & B COMPANY MACHINERY AND EQUIP MAINT MAT	19518 E	259.75 S1613138002 COMP FLANGE, REDUCING TEE, PVC SOC CROSS S1613138002 COMP FLANGE, REDUCING TEE, PVC SOC CROSS S1613138002 COMP FLANGE, REDUCING TEE, PVC SOC CROSS S1613138002 COMP FLANGE, REDUCING TEE, PVC SOC CROSS	11.22 9.07 11.99 98.17 129.30	18 18 18 18 18
REDWOOD CITY, CITY OF - FINANC MACH & EQUIP MAINT SERVICES	19519	146.71 BR42136 10/16-11/15/16 VEHICLE REPAIR/MAINTENANCE CHAR	146.71	18
REDWOOD CITY, CITY OF - WATER UTILITIES	19520	307.66 1222201632690 10/22-12/22/16 GREENDALE WATER	307.66	18
REYES, OSCAR MISCELLANEOUS	19521	2,928.41 1132017 COMPUTER LOAN PER ADMIN POLICY	2,928.41	18
SANDUL, DUANE PROFESSIONAL SERVICES	19522	1,700.00 12SVCW2016 12/16 PROFESSIONAL SERVICES	1,700.00	18
SILICON VALLEY CLEAN WATER (EE SUPPLIES	19523	225.00 1132017 02/17 EMPLOYEE ANNIVERSARY	225.00	18
SILICON VALLEY CLEAN WATER (SA ADMINISTRATIVE EXPENSES	19524	1,910.00 1132017 02/17 SAFETY INCENTIVE EARNED FOR FEBRUARY 201	1,910.00	18
SWRCB FEES - ST WATER RESOURCE ADMINISTRATIVE EXPENSES	19525	11,195.00 WD0121338 2016-2017 NPDES ANNUAL PERMIT FEE	11,195.00	18

.

#### SILICON VALLEY CLEAN WATER W A R R A N T R E G I S T E R 01/13/17

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	NT DETAIL	FUND
SYNAGRO TECHNOLOGIES INC 19 CONTRACT SERV. (NON-MAINT.)	19526	66,973.	92	
		3102714 11/2016 BIOSOLIDS HAULING	46,849.76	18
		3102714 11/2016 BIOSOLIDS HAULING	20,124.16	18
TANNER PACIFIC, INC.	19527	76,054	25	
CONSTRUCTION-CONTRACTOR		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	296.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	4,673.50	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	12,275.75	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	5,226.50	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	9,659.50	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	4,142.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	88.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	12,659.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	1,856.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	4,546.00	20
		216110 12/18-12/31/16 T.O.2016-01 VARIOUS CONSTRUCTION	5,028.00	20
PROFESSIONAL SERVICES		216111 9/25-12/31/16 T.O.2016-03 CONSTRUCTION ADVISORY	1,590.00	18
CONSTRUCTION-CONSTRUCTION MGM	т	216112 12/18-12/31/16 T.O.2016-04 UPS UPGRADE PROJECT	3,178.50	14
		216113 10/9-12/31/16 T.O.2016-05 CONSTRUCTION MGMT	288.00	14
		216113 10/9-12/31/16 T.O.2016-05 CONSTRUCTION MGMT	288.00	14
		216114 12/4-12/31/16 T.O.2016-06 CONSTRU MGMT FOR SAN	1,913.50	14
		216115 10/23-12/31/16 T.O.2016-07 PS VALVE REPLACEMENT	4,173.00	14
		216115 10/23-12/31/16 T.O.2016-07 PS VALVE REPLACEMENT	4,173.00	14
VAPEX ENVIRONMENTAL TECHNOLOGI	19528	222,475.5	54	
CONSTRUCTION-CONTRACTOR		2161211 11/2016 ODOR CONTROL SYSTEM CIP 269	137,397.77	14
		216212 11/2016 ODOR CONTROL SYSTEM CIP 269	85,077.77	14
VERIZON WIRELESS	19529	2,533.2	15	
UTILITIES		9777283176 11/20-12/19/16 VERIZON SERVICE	2,447.21	18
		9777283177 11/20-12/19/16 VERIZON SERVICE	76.02	18
		9777582122 11/24-12/23/16 VERIZON 4G BACKUP ROUTER PLA	10.02	18

01/13/17

PAGE 9543

NAME	WARRANT NUMBER	INVOICE #/DESCRIPTION		
VINCENT ELECTRIC MOTOR COMPANY	19530		DETAIL	FUND
MACH & EQUIP MAINT SERVICES	19990	20,442.80 903237 11/18/16 BLOWER REBUILD	20,442.80	18
VWR INTERNATIONAL, LLC	19531	493.84		
SUPPLIES		8046962958 QTY 1 SOLUTION COD	20.50	18
		8046962959 QTY 3 STIRRING ROD, QTY 1 SODIUM THIOSULFAT	47.91	18
		8046962959 QTY 3 STIRRING ROD, QTY 1 SODIUM THIOSULFAT	10.24	18
		8047002043 QTY 1 DOUBLE SIDED RACK BENCHTOP	138.40	18
		8047023645 QTY 2 DOUBLE SIDED RACK BENCHTOP	276.79	18
WANDRO, ROBERT	19532	84.96		
MEMB. & MEET.		1132017 REIMB-12/21/16 BACWA LAB MEETING	39.96	18
UTILITIES		1132017A REIMB 11/18-12/17/16 CELL PHONE	45.00	18
WATSON-MARLOW INC	19533	2,929.78		
MISCELLANEOUS		SI026425TAX SALES TAX LIABILITY	-259.20	18
		SI026425 QTY 10 PVC BORE PVC TUBING, QTY 10 MARPRENE T	1,144.50	18
		SI026425 QTY 10 PVC BORE PVC TUBING, QTY 10 MARPRENE T	2,044.48	18
WELLS FARGO-COMML OPERATIONS	19534	21,494.27		
INTEREST EXPENSES		1611884352 LOC#7829596836 STATEMENT 12/23/16	688.00	20
		1611884352 LOC#7829596836 STATEMENT 12/23/16	429.43	20
		1611884352 LOC#7829596836 STATEMENT 12/23/16	2,207.16	20
		1611884352 LOC#7829596836 STATEMENT 12/23/16	1,219.68	20
		161184712942 LOC#7829596836 STATEMENT 12/21/16	8,232.61	20
		161184712942 LOC#7829596836 STATEMENT 12/21/16	4,549.38	20
		161184712942 LOC#7829596836 STATEMENT 12/21/16	2,566.23	20
		161184712942 LOC#7829596836 STATEMENT 12/21/16	1,601.78	20
WESTERN ENERGY SYSTEMS	19535	10,151.42		
MACH & EQUIP MAINT SERVICES		3682267 9/26-9/29/16 JENBACHER TRAINING	10,151.42	18

PAGE 9544

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUNT	DETAIL	FUND
WESTERN STATES OIL	19536	2,651.38		
MISCELLANEOUS		298776 QTY 165 SHELL MYSELLA S3 N 40W	2,651.38	18
WESTERN WEATHER GROUP INC	19537	1,330.00		
MACH & EQUIP MAINT SERVICES		13977 12/7/16 QUARTERLY AUDIT METEOROLOGICAL STATION	1,222.00	18
		13985 2017 - WEATHER UNDERGROUND DATA UPLOAD	108.00	18
WHITLEY, BURCHETT AND ASSOCIAT	19538	3,456.25		
CONTRUCTION-DESIGN		REISSSVC14321 REISS CK#19053 DTD 11/4/16 7/16-8/16 T.O	3,456.25	20
WRA ENVIRONMENTAL CONSULTANTS	10000			
CONTRUCTION-DESIGN	19539	3,281.34		
CONTROCTION-DESIGN		201711628286 11/16 T.O.2015-03 CONVEYANCE SYSTEM CEQA	236.70	20
		201711628286 11/16 T.O.2015-03 CONVEYANCE SYSTEM CEQA	236.70	20
		201711628286 11/16 T.O.2015-03 CONVEYANCE SYSTEM CEQA	236.70	20
		201711628286 11/16 T.O.2015-03 CONVEYANCE SYSTEM CEQA	236.70	20
		201711628286 11/16 T.O.2015-03 CONVEYANCE SYSTEM CEQA	236.70	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	115.38	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	41.96	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	41.96	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	1,153.81	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	83.91	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	125.87	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	20.98	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	146.85	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	251.74	20
		201711828274 11/16 T.O.2016-01 CONVEYANCE SYSTEM CEQA	115.38	20
XEROX CORPORATION	19540	1,440.05		
RENTAL/LEASES		87351842 12/16 XEROX LEASE	1,184.00	18
		87351843 12/2016 XEROX LEASE	256.05	18

.

#### SILICON VALLEY CLEAN WATER W A R R A N T R E G I S T E R 01/13/17

PAGE 9545

	WARRANT			
NAME	NUMBER	INVOICE #/DESCRIPTION AMOUN	r DETAIL	FUND
ZUN ZUN	19541	2,500.0	)	
CONTRACT SERV. (NON-MAINT.)		4003 12/9-12/20/16 WASTERWATER AWARENESS PERFORMANCE	2,500.00	18

TOTAL

\$1,275,065.28

7B-15

### SOLIDS PROCESS AUTOMATION (CIP #8007, 8018, 8021) FINAL PROJECT ACCEPTANCE

## <u>ISSUE</u>

Final Acceptance of Solids Process Automation Project (CIP #8007, 8018, 8021) and Authorization to File Notice of Completion.

### BACKGROUND

SVCW's Commission has approved automation projects contained within the CIP as a high priority for implementation. The desired result of plant automation is to reduce manual operations, thereby improving permit compliance and overall treatment reliability while allowing for reductions in operations staff. Automation of a wastewater treatment process encompasses all equipment and systems necessary to achieve this desired result, including the Programmable Logic Control system (PLC), control strategies, conduit and wiring, electrical feeders, mechanical equipment, and reliable fail-safes. Removing a treatment plant Operator requires a significant capital investment with the goal being a reduction in long-term O&M expenses and continued compliance with all discharge permit requirements.

A project to automate the solids processes within the treatment plant was initiated in 2011. The processes were: thickening and digestion. Later, primary sedimentation was added. Work to automate these processes is extensive, complex, and time-consuming. With the completion of these systems, the automation program is approximately 50% complete.

### DISCUSSION

Bids were opened on October 1, 2013 for the Solids Process Automation (SPA) project. Three bids were received, with Monterey Mechanical (MMC) being the low bid at \$11,149,000 (the two other bids were \$12,231,149 and \$13,956,525). The construction contract was awarded to MMC in October 2013. Work has been ongoing for the project since the Notice to Proceed was issued in November 2013. The original SPA project construction scope included improvements to the Gravity Thickening, Anaerobic Digestion and Dewatering, and Primary Sedimentation systems to automate their operation and replace mechanical and electrical equipment.

During project construction, the scope of work on two of the three solids processes needed to be modified. SVCW had to re-evaluate the sludge thickening systems due to catastrophic failures of two of the four existing gravity thickeners during a plant-wide power failure. This portion of the project was put on hold for MMC until a decision was made on thickening methods. Following a successful Gravity Belt Thickener pilot test, the Gravity Thickener scope was deleted from the Contract and Gravity Belt Thickener system scope was added. In March 2014, while the thickening scope was being reconsidered, work on the Primary Sedimentation system was suspended due to the potential for the sludge thickening system modifications to affect the Primary Sedimentation design. The Primary Sedimentation work was ultimately released nearly eleven months later in January 2015.

Over the three-plus years of construction, there were a total of one hundred and one (101) contract change orders adding to a total cost of a \$1,858,784. There were four notable contract change order items, all related to the Gravity Thickener failures and resultant project suspension. The four items were presented to the Commission for approval at the costs and on the dates noted below.

- Gravity Belt Thickener procurement (\$489,798) Commission Approved July 2014
- Gravity Thickener deletion (-\$795,000). Commission Approved January 2015
- Gravity Belt Thickener Installation (\$1,285,000) Commission Approved January 2015
- Contract time and cost extension due to project suspension (\$441,930 and 239-day contract extension) Commission Approved August 2016

The overall project cost was \$13,007,784, or approximately 15 percent above the original Bid Amount. Minus the Commission approved change orders noted above, the total change order amount was \$437,056 or 3.92% of the original contract amount.

Substantial Completion was achieved and the certificate was issued December 23, 2016 (attached). A Punch List was issued upon Substantial Completion to be completed before final payment and release of retention. This project was extremely complex in and of itself; with the added complexity of changing major portions of the work, it was a significant coordination and cooperative work effort. The quality of work by the Contractor on this project is excellent and staff is now utilizing the new facilities.

## FINANCIAL IMPACT

The Solids Process Automation project is funded from three CIP projects: 8007 – Primary Sedimentation Automation, 8018 – Thickening Process Automation, and 8021 – Anaerobic Digestion Automation. The 2015 CIP Update allocates \$21,200,972 for the three projects; as of December 31, 2016, \$20,615,623 has been expended.

## RECOMMENDATION

Move approval to ACCEPT SOLIDS PROCESS AUTOMATION PROJECT (CIP #8007, 8018, 8021) AND AUTHORIZE FILING OF NOTICE OF COMPLETION – Monterey Mechanical Company

### Silicon Valley Clean Water **Solids Process Automation** CIP No. 8007, 8018, and 8021 SUBSTANTIAL COMPLETION CERTIFICATE

The following portions of Solids Process Automation - Location Code 14 and 23 are accepted as Substantially Complete in accordance with Specification Sections 00700-8.6 and 00800-1.5, Contract Change Order 041: "Substantial Completion Requirements", Contract Change Order 064: "Contract Time Extension," and as defined herein.

As of December 23, 2016, these portions of the Project are accepted:

- 1. All work Location Code 14 Primary Sedimentation except as noted below: a. All work on the attached Punch List, dated December 23, 2016.
- 2. All work on Digester No. 1 in Location Code 23 except as noted below: a. All work on the attached Punch List, dated December 23, 2016.

As of the above dates the following responsibilities are agreed to:

- 1. Authority:
  - a. The Authority assumes responsibility for security, maintenance (except as noted below). heat, utilities, damage to the Work (except as caused by the Contractor's actions) and insurance for the facilities.
- 2. Monterey Mechanical:
  - The Contractor shall maintain and provide proof of insurance as required by Specification a. Section 00800-3.1.4 for all work required to complete the Punch List and for five years following Final Completion as required by Specification Section 00800-3.2.
  - b. The Contractor shall be responsible for repairs or maintenance, as necessary, until the Contractor has submitted, and the Authority has accepted all Record Documents and Operation & Maintenance Manuals.
  - c. The Contractor shall work in an expeditious manner to the complete the remaining work and administrative requirements on the Project including the items on the Punch List, dated December 23, 2016.

The one year (365 Calendar Days) warranty for the accepted Work shall commence per Specification Section 01740-1.0 on the date of Acceptance by Silicon Valley Clean Water.

The undersigned hereby acknowledge agreement to the above provisions:

Accepted By (Monterey Mechanical Co.):

Ed Moore, Project Engineer

Recommended By (Tanner Pacific, Inc.): Andrew Matey, P.E., Construction Manager

12/22/16 Date

## ACTIONS IN SUPPORT OF PURSUING FEDERAL MONIES THROUGH THE WATER INFRASTRUCTURE FINANCING AND INNOVATION (WIFIA) ACT

### <u>ISSUE</u>

Approval of Master Service Agreements and Task Orders for Financial Administrative Assistance Services Associated with the Water Infrastructure Finance and Innovation Act (WIFIA) Loan Program and other Governmental Finance Opportunities.

### BACKGROUND

Since the inception of its 2008 Capital Improvement Program (CIP), Silicon Valley Clean Water (SVCW) completed over 100 projects and invested approximately \$227 million to rehabilitate and replace aging infrastructure. Total expenditures, once the CIP is complete, are estimated at \$813 million. The majority of the remaining expenditures are to replace a conveyance system built in the 1960s.

As described in the updated January 2017 Long Range Financial Plan, SVCW strives to fund the CIP with the most cost-effective financing possible. To date, the lowest cost source of funds has been the subsidized State Revolving Fund (SRF) program administered by the California State Water Resources Control Board (SWRCB). To illustrate, SVCW has thus far secured three separate SRF loans for a total of \$55 million at interest rates ranging from 1.6 to 2.6 percent.

In September 2016 the SWRCB advised that the SRF program is oversubscribed. They cautioned that unless the state takes significant additional funding action it is unable to satisfy the demand for SRF loans. SVCW will therefore pursue SRF loans along with all other government loan programs that may save money for ratepayers.

In December 2016 the federal government passed legislation to fund the Water Infrastructure Finance and Innovation Act (WIFIA). Administered by the United States Environmental Protection Agency (EPA), the WIFIA mission is to accelerate investments in water and wastewater infrastructure by providing long-term, low-cost supplemental credit assistance to creditworthy water and wastewater projects of national and regional significance. SVCW intends to pursue the WIFIA program due to its flexible borrowing structure and attractive interest rates (currently ~3.1 percent).

## DISCUSSION

Governmental loan programs like WIFIA require considerable administrative and financial support during the application process. Activities where assistance is needed includes the development of effective communication to policy-makers, financial proforma, revenue feasibility studies, consultations with rating agencies, and proposed terms of any financing agreements. SVCW staff negotiated scopes of work and budgets for the administrative and financial support associated with the WIFIA loan process, and recommends securing the support of three organizations:

• Fieldman, Rolapp & Associates ("FRA") is a California municipal financial advisory firm with extensive experience in wastewater finance issues. The firm is

familiar with SVCW, having entered into a Master Services Agreement (MSA) in July 2015 to develop financial models and debt strategies useful for long range financial planning. Additionally, FRA has direct experience with debt issuance strategies that are aligned with SVCW goals to access capital at the lowest possible cost. Its activities over the next twelve months will include any financial modeling support needed during the WIFIA loan application process. Over the next twelve months, it is anticipated that fees paid to FRA will not exceed \$106,600.

- Ginger Bryant & Associates ("GBA") is a public relations firm specializing in matters related to local and federal government interactions. GBA will prepare communication materials, including graphic design and branding concepts used during the WIFIA loan application process and in Washington DC meetings. Specific services include identifying the appropriate depth and substance of communication materials, developing talking points for use in Washington DC, and preparation of follow up information. Over the next twelve months, it is anticipated that fees paid to GBA will not exceed \$144,200.
- The Ferguson Group, LLC ("TFG") provides federal advocacy services with a
  public sector client base and specializes in securing federal funding, grants, and
  authorizations for public agencies. TFG has partnered with GBA on other local
  water projects, and its expertise will be especially valuable in navigating the
  EPA's recently-staffed WIFIA program. Over the next twelve months, it is
  anticipated that fees paid to TFG will not exceed \$126,000.

## FINANCIAL IMPACT

Funds will derive from CIP Project #9158, CIP Financial Assistance, to be used for the duration of the CIP. To date, \$1.08 million remains unspent. The total budget for the requested task orders is \$376,800.

### RECOMMENDATION

- i. Move approval of TASK ORDER NO. 2017-01 SCOPE AND BUDGET FOR WIFIA ADMINISTRATIVE SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$106,600 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – Fieldman, Rolapp & Associates
- ii. Move adoption of RESOLUTION APPROVING MASTER SERVICES AGREEMENT FOR PUBLIC RELATIONS CONSULTING SERVICES - Ginger Bryant & Associates
- iii. Move approval of TASK ORDER NO. 2017-01 SCOPE AND BUDGET FOR WIFIA PUBLIC RELATIONS SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$144,200 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS – Ginger Bryant & Associates

- iv. Move adoption of RESOLUTION APPROVING MASTER SERVICES AGREEMENT FOR INTERGOVERNMENTAL CONSULTING SERVICES -Ferguson Group, LLC
- v. Move approval of TASK ORDER NO. 2017-01 SCOPE AND BUDGET FOR WIFIA INTERGOVERNMENTAL CONSULTING SUPPORT (CIP #9158) IN AN AMOUNT NOT TO EXCEED \$126,000 AND AUTHORIZE MANAGER TO APPROVE UP TO TEN PERCENT CONTINGENCY FOR ADDITIONAL WORK ON AN AS-NEEDED BASIS –Ferguson Group, LLC

## INSTALLATION OF FLO-BEAST SEPTAGE RECEIVING UNIT (CIP #9229)

### **ISSUE**

Issue Installation Contract for a New Flo-Beast Septage Receiving Unit.

### BACKGROUND

Silicon Valley Clean Water has operated its Grease Receiving Station (GRS) since the late 1980s. GRS receives fats, oils and grease (FOG) from grease haulers who clean grease traps at local restaurants and other food establishments; the material is then injected into the anaerobic digesters, which increases the amount of digester gas produced. The digester gas is used by the cogeneration system to produce electricity and heat for treatment processes.

The GRS is the interface between SVCW and outside haulers to receive the FOG before injection into the digesters. FOG delivered by the grease haulers contains inorganic material such as rags, rocks, silverware, and grit. An existing 4-inch manual bar screen removes some of the inorganic material but does not capture the majority. Also, the material builds up over time, resulting in overflow of the FOG, bypassing the screening step. The inorganic material that builds up over time in the holding tanks causes frequent cleaning and maintenance of the tank and the digesters, and often clogs the transfer pipe. When inorganic debris builds up in the digesters, the only way it can be removed is through a digester cleaning process that costs in excess of \$50,000 per digester. Minimizing the amount of inorganic solids in the digesters is a high priority for lowering operating and maintenance costs.

Staff became aware of a piece of equipment that is designed to remove inorganic material from FOG and has worked with the local manufacturer's representative, Enviro-Care, to pilot test the equipment. The equipment is called a "Flo-Beast" and removes debris and contaminants from FOG before the FOG enters the holding tank. Grease haulers connect to the inlet of the Flo-Beast via a quick-connect hose coupling and empty their tanks into it. From the Flo-Beast the now-clean FOG enters the holding tank and, from there, is injected into the digesters.

The Flo-Beast pilot unit has been operating since March 18, 2016 and the results of the pilot test have been stellar. Staff noticed significant removal of contaminants from the FOG (evidenced by the reject captured in the debris bin) and much cleaner FOG entering the holding tank. The maintenance of the equipment was near zero and the operational effort is very low requiring only the emptying of the dumpster on a weekly basis. Additionally, the transfer pipe is not clogging as it was without the Flo-Beast. The Operations and Maintenance Divisions are very satisfied with the operation of the unit.

### DISCUSSION

On May 12, 2016 SVCW staff recommended, and the Commission approved, purchase of a Flo-Beast for permanent installation. SVCW received the unit in early January 2017 and is now ready to be installed.

Report By: <u>T.H.</u>

To install the new Flo-Beast unit, SVCW staff prepared installation design documents and requested quotations from three contractors. Two contractors declined to provide quotes and D.W. Nicholson provided a quotation in the amount of \$96,432. This amount is in line with SVCW Engineering staff's expected cost for installation. The reasons provided by other contractors for not providing quotations is 1) an inability to procure the services of an electrical subcontractor 2) lack of resources (staff) to provide services in the amount of time requested by SVCW. D.W. Nicholson is both a General and an Electrical contractor and has performed work for SVCW for over 25 years. The work of D.W. Nicholson has been consistently superior.

## FINACIAL IMPACT

The Flo-Beast installation will be funded from CIP Project #9229 which provides budget for the Food Waste Project in an amount of \$13 million. The purchase price of the Flo-Beast unit is anticipated to be reimbursed by the California Energy Commission (CEC) as part of the CEC grant awarded for Food Waste Study. The grant is in the amount of \$600,000; \$300,000 available to purchase equipment, \$200,000 for design and \$100,000 for digester cleaning. The installation cost will be funded by SVCW and will be credited towards the matching funds committed under the CEC grant.

Several months ago, staff lowered the FOG disposal tipping fee for haulers to determine if this would increase the amount of deliveries. Nearly immediately, the amount of grease being received increased; for example, one hauler began to haul approximately 50,000 gallons per month which is more than half of the previous month's grease received from all haulers combined. Increased FOG received at the plant results in production of extra digester gas, in turn saving SVCW money through increased onsite power cogeneration and offsetting power purchases from PG&E. Also, even with the reduced tipping fee, year-to-date revenues from FOG deliveries are better than forecasted (\$56,984 actual versus \$48,750 budgeted; 16.9% to the positive). The net benefit is power savings and increased revenue for SVCW along with lower disposal cost for the haulers.

### RECOMMENDATION

Move adoption of RESOLUTION APPROVING CONTRACT DOCUMENTS FOR FLO-BEAST INSTALLATION CONTRACT - CIP #9229; AUTHORIZING EXECUTION OF AGREEMENT AND AUTHORIZING MANAGER TO APPROVE CHANGE ORDERS UP TO TEN PERCENT OF THE CONTRACT VALUE FOR SAID PROJECT – (\$96,432) – D.W. Nicholson Corporation